
# Burke-Gilman Trail Missing Link Project




**Segment Workshop** 

September 28, 2017



#### PROJECT SEGMENTS



## SEGMENT 1 NW 54TH ST & NW MARKET ST

# NW 54TH ST (EXISTING)



# NW MARKET ST (EXISTING)



#### **CHANGES BETWEEN EIS AND 30%**



- 1. Maintain bus/metro layover zones along 54th St at the Ballard Locks
- 2. Relocated bus stop at Market St / 28th
- 3. Added westbound left turn lane with protected signal phase at Market / 28<sup>th</sup>
- 4. Coordinated trail design with Nordic Heritage Museum (video)
- 5. Substituted concrete for asphalt along NW Market St portion of the trail

#### **CHANGES BETWEEN 30% AND 60% DESIGN**




- Restriped parking at the Ballard Locks and the Lockspot Café
- 2. Added mixing zone treatments at the Ballard Locks
- 3. Added low maintenance street trees at multiple locations
- 4. Improved connections to the Neighborhood Greenway at 28<sup>th</sup> / Market
- 5. Converted 26th to one-way south of Market St
- 6. Reconfigured 24th / Market intersection, modified sidewalk cafes, and added mixing zone
- 7. Extended bicycle lanes on 24th to Market St and added crossing treatments

## SEGMENT 2 SHILSHOLE AVE NW

# SHILSHOLE (EXISTING)




#### **CHANGES BETWEEN EIS AND 30%**



- 1. Extended 54th and converted 24th to a dead end
- 2. Extended left turn pocket on Shilshole
- 3. Added striped parking to the northside of Shilshole Ave NW
- 4. Added signal to Shilshole / Vernon
- 5. Incorporated LED signs at key locations along Shilshole
- Maintained staging and parking space south of the trail on Shilshole Ave NW
- 7. Added left turn pocket at 17th and Shilshole
- 8. Avoided drainage impacts on nearby properties
- Improved and widened rail crossing for cyclists

#### **CHANGES BETWEEN 30% AND 60% DESIGN**



- Added landscape terrace at 24th / Shilshole
- Added perpendicular parking along 24th
- 3. Added rapid flash beacons and crosswalk at 54th / Shilshole
- 4. Added low maintenance street trees at multiple locations
- 5. Added truck aprons for WB67 truck movements at multiple locations
- 6. Extended sidewalk and landscaping at 20th Street End
- Installed crosswalks and a halfsignal at Dock / Shilshole
- Redesigned 17th / Shilshole for truck turning movements
- 9. Added lighting, fencing, and signage at trail/railroad crossing

## SEGMENT 3 NW 45TH ST

# NW 45TH ST (EXISTING)



#### **CHANGES BETWEEN EIS AND 30%**



- 1. Increased lane width to 11 feet on 45th St to accommodate large trucks
- 2. Retained loading access for properties on the south side of 45th between 11th and 14th

#### **CHANGES BETWEEN 30% AND 60%**



- 1. Connected the trail to the existing King County bike lane including new crosswalks, rapid flash beacons, and pedestrian lights
- 2. Restriped parking on the south side of 45th between 11th and 14th
- 3. Coordinated with Ballard Blocks 2 project
- 4. Added low maintenance street trees at multiple locations
- 5. Coordinated with SPU Ship Canal Water Quality Project

### October 2 - Field Test



## October 12 - Public Event October 14 - Self-guided Walking Tour



# Thank you!

louisa.galassini@seattle.gov | (206) 615-0185 www.seattle.gov/transportation/BGT MissingLink.htm

### www.seattle.gov/transportation











# Reference

#### **Ballard Locks**




### Market / 54th


NEW CURB EXTENSION AND MOUNTABLE TRUCK APRON




#### Market / 28th




#### Market / 24th




### Shilshole / 54th




## Shilshole / Vernon



#### Shilshole / Dock




## Shilshole / 17th / 46th






## **Ballard Bridge**



## 45th / 11th




## Signals



### **Bike/Ped Connections**




#### **Places of Interest**



#### **Trees**



## **Parking**



#### Site Preparation



<sup>\*</sup>Place temporary No Parking Signs on 9/29, restricting parking on 10/1-10/2

<sup>\*\*</sup>Place Traffic Barrels out on Sunday (10/1) or Monday Morning (10/2)

#### **Demonstration Construction**

