



Revised 03/21/2023

The table below displays edits to the 2020 edition of the City of Seattle's Standard Plans and Specifications for Municipal Construction. These edits were used to create the 2023 edition of the City of Seattle's Construction Standards.

Note: Cross reference links between Sections do not function in this document.

A summary of Standard Plan edits are included further down, with redline markups of revisions provided under a separate file on this same webpage.

[illegible]

Section # or/ Plan #	Current Title	Text
		<p>Revise existing definitions in this Section to match the following:</p> <p>HOLIDAY Per SMC 4.20.190 and RCW 1.16.050, Holidays for the City of Seattle are:</p> <ol style="list-style-type: none"> 1. First Day of January (New Year's Day) 2. Third Monday of January (Dr. Martin Luther King, Jr.'s Birthday) 3. Third Monday of February (President's Day) 4. Last Monday of May (Memorial Day) 5. June 19 (Juneteenth) 6. Fourth Day of July (Independence Day) 7. First Monday of September (Labor Day) 8. Second Monday of October (Indigenous Peoples' Day) 9. Eleventh Day of November (Veterans' Day) 10. Fourth Thursday of November and the Friday immediately following (Thanksgiving Day) 11. Twenty fifth Day of December (Christmas Day) <p>When any Holiday falls on a Sunday, the following Monday is considered a Holiday. When any Holiday falls on a Saturday, the preceding Friday is considered a Holiday. Holidays are Non-Working Days.</p>
1-02.4(1)	Examination of Bid Documents and Project Site – General	<p>Delete the website in the first paragraph of this Section and replace it with the following:</p> <p>http://www.seattle.gov/purchasing-and-contracting/construction-contracting</p>
1-02.6	Addenda	<p>Delete the website in the first paragraph of this Section and replace it with the following:</p> <p>http://www.seattle.gov/purchasing-and-contracting/construction-contracting</p>
1-02.7	Bid Guaranty	<p>Insert the following text at the end of this Section:</p> <p>A Bid Guaranty must accompany all Bids. A PDF Bid File must include a scanned copy of the wet signed and notarized Bid Guaranty. For all electronically submitted Bids, mail Bid Guaranty originals with a postmark no later than one Business Day following the Bid opening date. PC will not accept Electronic Signatures or electronic notarizations on the Bid Guaranty originals. Mail original Bid Guaranty documents to:</p> <p>FAS - Purchasing and Contracting City of Seattle P.O. Box 94669 Seattle, WA 98124-4669</p> <p>A Bidder submitting an electronic Bid who fails to mail a hard copy original of the Bid Guaranty with the required USPS postmark may be declared non-responsive.</p>
1-02.9(1)	Bid Submittal - General	<p>Delete the third paragraph of this Section and replace it with the following:</p> <p>Bidders have 2 options for Bid Submittal:</p> <ol style="list-style-type: none"> 1. Electronic Bid Submittal:

Section # or/ Plan #	Current Title	Text
		<p>Bidders may submit Bids electronically. Bids must be fully contained within one PDF Bid File with a maximum size of 15MB. The PDF Bid File must contain all specified components of the Bid required at the time of Bid Submittal. PC will accept Electronic Signature for the Bid Form Declaration and the Bidder/Subcontractor List, if applicable. The PDF Bid File must be electronically transmitted to the following email address:</p> <p>FAS_PWSecureBid@seattle.gov</p> <p>Identify both the email and the attached PDF Bid File with the full Public Works Contract Number (PW#) and name of the Bidder (e.g. "PW# 2020-001 – Pat's Construction").</p> <p>Bids must be transmitted by 2:00 PM on the Bid opening date. The Email Time Stamp constitutes the official time of transmission for PDF Bid Files. No electronic Bid Submittal of a PDF Bid File will be accepted with an Email Time Stamp past 2:00 PM of the Bid opening date.</p> <p>In the event that hardware, software or other automated email delivery process cause delay in the electronic delivery of an email and PDF Bid File, the City exercises its right to accept and consider an electronic Bid where the Email Time Stamp meets the 2:00 PM transmission deadline.</p> <p>2. United States Postal Service:</p> <p>Bidders may submit hard copy Bids via United States Postal Service (USPS). PC must receive mailed, hard copy Bids by 2:00 PM on the Bid opening date. Timely receipt by PC for a mailed Bid is the sole responsibility of the Bidder. PC is not responsible for late Bids caused by USPS or internal City of Seattle mail processing delays. Bidders acknowledge that USPS mail deliveries addressed to PC are centrally processed and routed through the City of Seattle mail delivery service. Mailed Bids must be mailed to:</p> <p>FAS - Purchasing and Contracting City of Seattle P.O. Box 94669 Seattle, WA 98124-4669</p> <p>The deadline for all Bids is 2:00 PM on the Bid opening date. The Email Time Stamp constitutes the official time for electronic Bid Submittal receipt. Bids mailed via USPS must be received by PC by 2:00 PM.</p> <p>If mandatory pre-bid meetings were required as part of the Bid's solicitation, the Bidder's company must be represented on the pre-bid meeting sign-in sheet, or the Bid will not be accepted.</p> <p>If the Bidder/Subcontractor List is required and not included with the Bid, it must be submitted to the City with the Bid or within 1 hour following the Bid submittal deadline. A Bidder submitting a Bidder/Subcontractor List electronically may email it to: FAS_PWSecureBid@seattle.gov. Identify both the email and attached Bidder/Subcontractor List document with the full Public Works Contract Number (PW#) and Bidder name. A Bidder/Subcontractor List sent via USPS must be received by PC within 1 hour following the Bid Submittal deadline.</p>
1-02.9(3)	Bidder/Subcontractor List	<p>Delete the first 3 paragraphs of this Section and replace with the following:</p> <p>In compliance with RCW 39.30.060 for all projects estimated to cost \$1,000,000 or more, all Bidders must complete and submit the Bidder/Subcontractor List, Section 0-01.5 of the Project Manual. The completed Bidder/Subcontractor list must identify the Subcontractors that the Bidder will contract with for HVAC, plumbing, electrical, structural steel, or rebar installation work; or indicate that the Bidder intends to self-perform the work, if awarded the Contract; or that category of work is not applicable. The Bidder/Subcontractor List may be submitted with the Bid, or separately within 1 hour of the time and date for Bid submittal. The Bidder is responsible for the timely delivery of the Bidder/Subcontractor List.</p> <p>The Bidder may list no more than 1 Subcontractor for each category of work, unless Subcontractors vary with Bid Alternates, Additives, or Deductives, in which case the Bidder must indicate on a separate Bidder/Subcontractor List which Subcontractor will be used for which Alternate, Additive, or Deductive.</p> <p>If the HVAC, plumbing, electrical, structural steel, or rebar installation specialty is left blank meaning either the name of a Subcontractor is blank, or a checkbox is not checked, the City will accept the blank as self-performance. The Bidder is bound to self-performance of that specialty for the duration of the Project.</p>
1-02.12	Public Opening of Bids	<p>Delete the contents of this Section and replace with the following:</p> <p>Emailed PDF and mailed hard copy Bids received will be opened and read aloud via Webex following the 2:00 PM bid submittal deadline specified in the Advertisement for Bids or in an Addendum. No attendees will be allowed at the Bid opening.</p> <p>Webex call-in information is as follows:</p> <ol style="list-style-type: none"> 1. Webex Phone number to connect: <ol style="list-style-type: none"> a. 206-207-1700 (Seattle) or b. 1-408-418-9388 (United States Toll) 2. Meeting Number Access Code: 146 108 8903

Section # or/ Plan #	Current Title	Text
1-03.1(2)	Claim of Error and Relief of Award	<p>Delete the last sentence of the first paragraph and replace it with the following:</p> <p>The statement and the worksheets must be submitted to: Purchasing and Contracting, City of Seattle, Department of Facilities and Administrative Services, 700 Fifth Avenue, Seattle Municipal Tower, Suite 4350 Seattle, WA 98104-5008, or by email to FAS_PW_Admin@Seattle.gov by 5:00 p.m. the next Business Day or as acceptable to the Owner.</p>
1-03.6	Protests	<p>Delete paragraphs 3 through 5, and replace with the following:</p> <p>Submit the protest to: Director, Purchasing and Contracting, Department of Facilities and Administrative Services.</p> <p>Physical Address: City of Seattle Seattle Municipal Tower 700 Fifth Ave., Suite 4350 Seattle, WA 98104-5008</p> <p>By mail, or email: City of Seattle FAS-Purchasing and Contracting PO Box 94669 Seattle, WA 98124-4669 Email: FAS_PW_Admin@Seattle.gov</p>
1-05.3(1)E	General Submittal Distribution and Format Summary	<p>With the exception of Bulk Samples, change all preferred submittal/correspondence formats in the table to read “electronic”, and delete the Alternate column.</p>
1-05.3(13)	As-Built Record Submittals	<p>Delete this Section and Title and replace with the following:</p> <p>1-05.3(13) RED-LINE DRAWINGS, AS-BUILT DRAWINGS AND RECORD DRAWINGS</p> <p>1-05.3(13)A RED-LINE DRAWINGS</p> <p>The Contractor must maintain one set of full size conformed Drawings for recording Red-Line Drawing mark-ups at the Project Site. The Red-Line Drawings must be updated with clear and accurate mark-ups on a daily basis, and within 2 Business Days after receipt of information a change to the Work has occurred.</p> <p>Red-Line Drawings must provide the applicable reference for all mark-ups including the date, change order number, the request for information (RFI) number, field directive (FD), design change (DC) or the approved Shop Drawing number. All mark-ups must clearly identify changes utilizing symbols and abbreviations found in the Contract. Mark-ups must be created using with minimum 1/8-inch lettering conforming to the following color code: Additions (Red), Deletions (Green), Comments, (Blue) and Dimensions (Graphite).</p> <p>The Red-Line Drawings must be available for review upon the Engineer’s request.</p> <p>All costs associated with preparing, maintaining and submitting Red-Line Drawings are considered incidental to the Work.</p> <p>1-05.3(13)B AS-BUILT DRAWINGS</p>

Section # or/ Plan #	Current Title	Text
		<p>As-Built Drawings are completed Red-Line Drawings as reviewed and approved by the Engineer. As-Built Drawings must incorporate all deviations from the conformed Drawings and graphically depict all information contained within Addendums, Change Orders, design changes, field memos, requests for information, substitution requests, Contractor notes and all other changes to the Work.</p> <p>As-Built Drawings must show accurate locations of Storm Drain, Sewer, Water Mains and other piping appurtenances, structures, conduits, light standards, vaults, width of roadways, sidewalks, landscaping areas, building footprints, channelization and pavement markings, pipe invert elevations, top of castings, maintenance holes, inlets, etc.</p> <p>Any buried utilities encountered and not shown on the conformed Drawings must be recorded on the As-Built Drawings and be reported to the Engineer.</p> <p>The Contractor must create and maintain As-Built Drawings within 10 Working Days of completed changes to that portion of the Work. The Contractor must submit to the Engineer As-Built Drawings monthly or when a progress estimate is submitted. Review and acceptance of the As-Built Drawing by the Engineer is a prerequisite for approval of the Contractor's progress estimate. Failure to maintain clear and up to date As-Built Drawings may delay the Contractor's monthly progress payment or the Owner may progressively withhold payment until the As-Built Drawings are properly updated.</p> <p>The Contractor must submit conformed Drawings and compiled draft As-Built Drawings post Substantial Completion and prior to punch list acceptance. Physical Completion will not be established until the Contractor has submitted and the Engineer has approved final As-Built Drawings.</p> <p>As-Built Drawing sheets must be stamped "AS-BUILT DRAWING".</p> <p>All costs associated with preparing, maintaining and submitting As-Built Drawings are considered incidental to the Work. For Record Drawing requirements, see www.seattle.gov/util/CAD.</p>
1-05.13(2)	Performance	<p>Replace this Section with the following:</p> <p>A Contractor Performance Evaluation is required for all projects with an engineer's estimate of \$1,000,000 or more. The Contractor Performance Evaluation process consists of 2 reviews:</p> <ol style="list-style-type: none"> 1. Mid-point Contractor Performance Evaluation will take place at mid-point of the project as determined by the Engineer. 2. Final Contractor Performance Evaluation will be completed prior to Project's Completion Date. <p>The Final Contractor Performance Evaluation will record the permanent evaluation scores for the Contractor's performance. Deficient scores of 59 or below for any individual category may be grounds for a determination of non-responsibility on future City projects. Overall performance evaluation scores deemed deficient with scores of 59 or below from 3 separate projects may be grounds for Contractor debarment under Section 1-08.10(8) and SMC 20.70.</p> <p>The Contractor may contest final criteria scores by filing a protest in writing. Protests must be submitted to PC within 5 business days after receipt of the Final Contractor Performance Evaluation.</p> <p>Submit protests to: Director, Purchasing and Contracting, Department of Facilities and Administrative Services.</p> <p>USPS Mailing Address: P.O. Box 94687 Seattle, WA 98104-4687</p> <p>Email: FAS_PW_Admin@Seattle.gov</p> <p>Protests must comply with the following requirements:</p> <ol style="list-style-type: none"> a. The protest must specifically identify which scoring criteria is contested; b. The protest must propose a score that reflects the protester's opinion of the Contractor's final performance; and c. The protest must provide the basis of information and facts that refute the final criteria score and supports a revision to the proposed score.

Section # or/ Plan #	Current Title	Text
		The PC Director or designee will review and decide on all final criteria score protests. The Director's decision on the protest is final and exhausts all administrative remedies.
1-05.5	Construction Stakes	<p>Delete the first sentence in this Section and replace with the following:</p> <p>All Work constituting the practice of engineering or land surveying requires the vertical datum and horizontal datum used to match the current National Geodetic Survey (NGS) Datum. See Standard Plan 001.</p>
1-05.15	Method of Serving Notice	<p>Delete the contents of this Section and replace with the following:</p> <p>All notices must be in writing and are considered delivered and service complete when:</p> <ol style="list-style-type: none"> 1. Delivered by certified or registered mail to the other party at their last provided address; or 2. Delivered in person to the other party; or 3. Delivered to an authorized representative of the other party at the Project Site; or 4. An electronic copy is delivered by electronic mail to the Engineer if sent to the City, and, if sent to the Contractor, to an authorized representative of the Contractor.
1-07.1(1)	Laws to be Observed - General	<p>Delete the first paragraph in this Section and replace it with the following:</p> <p>The Contractor is responsible for knowing and complying with all federal, state, tribal, county, and city laws, executive orders, ordinances, rules, and regulations applicable to the Work. All references to laws, executive orders, ordinances, rules, and regulations include all laws, executive orders, ordinances, rules, or regulations as adopted or amended after the Contract Date.</p>
1-07.3(1)	Management and Disposal of Waste - General	<p>Delete the phone number in the last sentence of the third paragraph and replace it with the following:</p> <p>(206)477-6585</p> <p>Delete the fifth paragraph and replace it with the following:</p> <p>Disposal sites used under the Contract must comply with all applicable rules, ordinances, codes, regulations and laws, and must have all required authorizations for the waste to be disposed.</p> <p>Loads of recyclable construction and demolition waste of a single material may be transported directly to a recycling facility. Mixed construction and demolition waste containing materials required to be recycled must be transported to a certified construction and demolition waste processor listed on the City's certified facilities website:</p> <p>https://www.seattle.gov/utilities/construction-resources/collection-and-disposal/construction-and-demolition/qualified-facilities</p> <p>per SMC21.36.089. Unrecyclable construction and demolition waste must be transported to disposal facilities per SC 21.36.112.</p>
1-07.3(4)	Recyclable Materials	<p>Replace the 1st paragraph with the following:</p> <p>The City requires specific types of construction and demolition waste to be recycled per SMC 21.36.089 and SPU Director's Rule SW-640 (https://www.seattle.gov/utilities/about/policies). Recyclable materials include but are not limited to asphalt and cement concrete, bricks, ferrous and non-ferrous metal, cardboard, untreated and unpainted wood, and new construction gypsum scrap.</p>
1-07.6	Permits	Delete the last paragraph in this Section and replace it with the following:

Section # or/ Plan #	Current Title	Text
		Information on Street Use Permits: https://www.seattle.gov/transportation/permits-and-services/permits
1-07.8	High Visibility Apparel	<p>Replace the last sentence of this Section with the following:</p> <p>High-visibility garments must be in a condition compliant with the ANSI 107-2015 (or later version) and must be used per manufacturer recommendations.</p>
1-07.8(1)	Traffic Control Personnel	<p>Replace items one and two with the following:</p> <p>1. During daylight hours with clear visibility, workers must wear a high-visibility ANSI/ISEA 107 Type R Class 2 or 3 vest or jacket, and hardhat meeting the high-visibility headwear requirements of WAC 296-155-305.</p> <p>2. During hours of darkness (1/2 hour before sunset to 1/2 hour after sunrise) or other low-visibility conditions such as snow or fog, workers must wear a high-visibility ANSI/ISEA 107 Type R Class 2 or 3 vest or jacket, high-visibility lower garment meeting ANSI/ISEA 107 Class E, and hardhat meeting the high-visibility headwear requirements of WAC 296-155-305.</p>
1-07.9(1)D1	Written Overtime Agreement	<p>Delete the last 2 paragraph in this Section and replace with the following:</p> <p>Physical address: City of Seattle Seattle Municipal Tower 700 Fifth Ave., Suite 4350 Seattle, WA 98104-5008</p> <p>Mailing address: City of Seattle FAS-Purchasing and Contracting PO Box 94669 Seattle, WA 98124-4669</p>
1-07.9(2)	Payroll Reports	<p>In the second paragraph, delete the cited website and replace it with the following:</p> <p>https://www.dol.gov/agencies/whd/government-contracts/construction/payroll-certification</p>
1-07.9(7)	Required Documents	<p>Delete the cited website in the last paragraph in this Section and replace it with the following:</p> <p>https://lni.wa.gov/licensing-permits/public-works-projects/prevailing-wage-policies</p>
1-07.11	Social Equity in Contracting	<p>Delete the last 2 paragraph in this Section and replace with the following:</p> <p>Physical address: City of Seattle Seattle Municipal Tower 700 Fifth Ave., Suite 4350 Seattle, WA 98104-5008</p> <p>Mailing address:</p>

Section # or/ Plan #	Current Title	Text
		City of Seattle FAS-Purchasing and Contracting PO Box 94669 Seattle, WA 98124-4669
1-07.11(1)	Equal Benefits	<p>Delete the cited website in the last paragraph in this Section and replace it with the following:</p> <p>http://www.seattle.gov/purchasing-and-contracting/social-equity/equal-benefits</p>
1-07.13(1)	General	<p>Delete the contents of this Section and replace with the following;</p> <p>Except as provided for otherwise in the Contract, the Work, including Change Order Work, is at the sole risk of the Contractor until the Completion Date. Except as specifically limited for underground utilities by RCW 19.122.040(3), damage to or destruction of either permanent or temporary portions of the Work, and existing utilities, street improvements, Materials, or equipment and facilities on the Project Site must be promptly rebuilt, restored, repaired, corrected, or replaced by the Contractor, at the Contractor's expense, regardless of the cause of damage.</p> <p>Exceptions to the above are limited exclusively to the following:</p> <ol style="list-style-type: none"> 1. Damage to the permanent Work caused by acts of nature, such as earthquake, flood, or other cataclysmic phenomenon of nature. 2. An act of the public enemy or a government authority. 3. A slide occurring on a finished slope after the Physical Completion Date of the Work. 4. Third party damage or vandalism occurring after the Physical Completion Date. <p>The above exceptions do not apply when damages are due to the Contractor's failure to comply with any contractual responsibilities or to perform sound engineering and construction practices in the conduct of the Work, or to take reasonable precautions under the circumstances.</p> <p>If Work is delayed as a result of damage by others not party to the Contract, an extension of time will be evaluated as specified in Section 1-08.8.</p> <p>Damage qualifying under any of the exceptions listed in Section 1-07.13(1) must be corrected promptly upon request, and payment will be made as specified in Section 1-04.3. Where public safety is affected and an emergency exists, the Engineer may elect to accomplish repair by Owner or other forces as specified by Section 1-05.8. The contents of this Section do not relieve the Contractor of responsibility for, or damage resulting from, the Contractor's, or Subcontractors, operations or negligence, nor is the Contractor relieved from full responsibility for making good any defective Work or unauthorized Work.</p> <p>The Contractor is solely responsibility for:</p> <ol style="list-style-type: none"> a. Damage to property located within or outside the Project Site limits as a result of the Contractor's construction operation, this includes, but is not limited to, damage caused by erosion, situation, or runoff; and b. Any pollution of a river, stream, ground water, or other water that may occur as a result of the Contractor's construction operation.:
1-07.13(4)	Repair of Damage	<p>Delete the first sentence of this paragraph and replace with the following:</p> <p>The Contractor must promptly repair all damage as directed by the Engineer.</p>
1-07.16.(2)	Tree Soil and Vegetation Protection	<p>Delete this Section and Replace with the following:</p> <p>All trees, vegetation, and soil not designated for removal must be left in place and protected from damage in accordance with Standard Plan 132 and Section 8-01.3(2)B until the Substantial Completion Date has been established by the Engineer.</p> <p>Destroyed or damaged trees and vegetation not designated for removal must be replaced or mitigated by the Contractor at no cost to the Owner. The dollar value of impacted trees and vegetation will be determined by the Engineer in accordance with the current edition of the Guide for Establishing Values of Trees and Other Plants prepared by the Council of Tree and Landscape Appraisers. Unless otherwise required, replacements must be of the same species and size as the tree or vegetation destroyed or damaged by the Contractor during construction. Replacements for trees larger than 4-inch DBH must be provided in a 3-1/2 to 4-inch caliper</p>

Section # or/ Plan #	Current Title	Text
		<p>size. When the replacement tree is smaller in caliper than the tree impacted by construction, the Contractor will be assessed damages equal to the difference in dollar value between the replacement tree and the impacted tree. Where physical limitations prevent the full restoration of destroyed or damaged trees and vegetation, the Contractor will be assessed damages equal to the difference in the dollar value between the trees and vegetation provided and the trees and vegetation impacted. Damages are not to be construed as a penalty and the Owner may deduct these damages from any money due or to become due to the Contractor.</p> <p>Replacement trees and vegetation must be installed and maintained as specified in Section 8-02.3(6). The Contractor must allow at least 2 Working Days advance notice for inspection and approval of replacement stock by the Engineer.</p> <p>Soils in areas disturbed by construction, including but not limited to areas impacted by vehicle traffic, materials storage and areas that have been graded, ripped, stripped, or trenched, must be decompacted, amended, and restored as specified in Section 8-02.</p>
1-07.18(2)	General Requirements (do not apply to state of Washington statutory workers' compensation insurance)	<p>Delete the sixth paragraph and replace it with the following:</p> <p>Notice under this paragraph must be issued to: Purchasing and Contracting, Department of Facilities and Administrative Services, 700 Fifth Avenue, P.O. Box 94687, Seattle, WA 98124-4687.</p>
1-07.18(5)	Evidence of Insurance (does not apply to state of Washington statutory workers' compensation)	<p>Delete the fourth paragraph and replace it with the following:</p> <p>Certification of insurance must be issued to: PC, Department of Facilities and Administrative Services, 700 Fifth Avenue, P.O. Box 94687, Seattle, WA 98124-4687.</p>
1-07.28	Notifications Relative to Contractor's Activities	<p>Replace paragraph (e) in item "2. For Work That Partially..." with the following:</p> <p>When signs are Owner furnished, signs will be provided by SDOT. To order signs, or to coordinate SDOT's installation of signs, the Contractor must provide at least 30 Working Days and no more than 40 Working Days advance notification to the Engineer and must verify signs and locations per the Contract for signs to be installed by the Contractor, and/or provide notification of signs to be installed by SDOT. The Contractor must provide a list of locations and specify the number and type of signs needed and include contract information for the coordination of work to be performed by SDOT crews. The Engineer will notify the Contractor of when the signs are ready for pickup and the signs must be picked up with 10 Working Days of notification. The Contractor must pick up the signs at the SDOT sign shop at 4200 Airport Way South on Business Days between the hours of 8:00 a.m. to 3:00 p.m.</p>
1-08.1(3)A	Subcontractor Communications	<p>Insert the following new Section:</p> <p>1-08.1(3)A SUBCONTRACTOR COMMUNICATIONS</p> <p>The Contractor may not impede, restrict, or prohibit subcontractors, suppliers, and vendors from communicating directly with the Engineer for any of the following reasons:</p> <ol style="list-style-type: none"> 1. Responding to City-initiated communications 2. Inquiring, seeking assistance on, or reporting a violation of Acceptable Work Site provisions of 1-07.11(4)A 3. Inquiring or seeking assistance on weekly payroll issues involving LPCracker per 1-07.9(2) 4. Inquiring or seeking assistance on issues related to equal opportunity, non-discrimination, Affirmative Efforts and Apprenticeship provisions of 1-07.11, 1-07.11(3), 1-07.11(4), 1-07.11(6)B and 1-07.11(6)E 5. Inquiring or seeking assistance related to progress payments and prompt pay requirements per 1-09.11(2); or 6. Inquiring or seeking assistance related to Subcontractor retainage per 1-09.11(4)A. <p>The Owner is not obligated to respond to any direct communication from a Subcontractor, Vendor or Supplier allowed by this Section, and this Section does not create a contractual relationship between the Owner and any Subcontractor, Vendor or Supplier, or bestow the status of a third-party beneficiary on any of those entities for any purpose. This Section does not alter or waive any notice requirement under the Contract or otherwise.</p>

Section # or/ Plan #	Current Title	Text
1-08.1(4)	Hours of Work	<p>Delete the first paragraph in this Section and replace it with the following:</p> <p>The normal hours of Work must be between 7:00 a.m. and 7:00 p.m. on any Working Day and consists of 8 hours, exclusive of a lunch period of not more than 1 hour. On City Holidays, Work must not begin before 9:00 a.m. See SMC Chapter 25.08.425 for additional information. The normal work week must not exceed 40 hours of Work. The normal hours of Work are established at the preconstruction conference or before the Contractor starts the Work and must not be changed or extended without approval of the Engineer.</p>
1-09.1	Measurement and Quantities	<p>Replace Item 2 of the 3rd paragraph with the following:</p> <p>2. Linear Foot: Measure length along an element unless required otherwise.</p>
2-01.3(1)	Clearing	<p>Delete Paragraphs 1, 2 and 3 and replace with the following:</p> <p>The Contractor must fell trees marked for removal within the area to be cleared. The Contractor must notify the Engineer at least 10 Business Days in advance of tree removal and must post Engineer-provided placards on trees before removal. The Contractor must comply with Section 1-07.28 whenever tree removal is near overhead wires. For removal of trees larger than 6 inches diameter at 1 foot above the ground, see Section 2-02.3(3)l.</p> <p>If pruning is specified or approved in the TVSPP or otherwise deemed necessary in areas to be cleared, the Contractor must conduct pruning per Section 8-02.3(7)A.</p>
2-02.3(3)A	Remove Non Rigid Pavement and Untreated Roadway Surfaces	<p>Move the 5th paragraph of Section 2-02.3(3)A to the end of Section 2-02.5, item 4</p> <p>Required sawcutting on the perimeter of full depth non-rigid pavement openings is paid as "Sawcut Asphalt Concrete, Full Depth." All other sawcutting associated with removal of non-rigid pavement is considered incidental to the removal Bid Item.</p>
2-02.3(3)B	Remove Asphalt Overlay	<p>Move the 3rd paragraph of Section 2-02.3(3)B to be the last paragraph of Section 2-02.5, item 4</p> <p>Required sawcutting on the perimeter of an asphalt overlay removal area will be paid as "Sawcut Asphalt Concrete, Full Depth." All other sawcutting associated with removal of asphalt overlay is considered incidental to the removal Bid Item.</p>
2-02.3(3)l	Remove Tree	<p>Delete Paragraphs 2, 3 and 4 and replace with the following:</p> <p>The Contractor must notify the Engineer at least 10 Business days in advance of tree removal, and must post Engineer-provided placards on trees before removal. The Contractor must comply with Section 1-07.28 whenever tree removal is near overhead wires.</p> <p>In improved areas and/or areas to be paved, stump removal must be completed by grinding and removing the stump to a 2-1/2-foot depth below finished grade, unless otherwise specified in the Contract. In unimproved areas, removal of the tree does not include complete removal of the stump unless directed by the Engineer.</p>
2-02.3(7)F	Drainage and Sewer Materials	Delete this Section.
2-04.3(7)	Drain Pipe Excavations	Replace the title of this Section with "Subsurface Drain Excavation"

Section # or/ Plan #	Current Title	Text
2-09.3(5)	Subgrade for Structure	<p>Replace this Section with the following:</p> <p>When a foundation will rest on rock, excavation must penetrate it at least 1 foot, or more if the Contract requires, to form a key for the footing. The Contractor must cut the bottom of the excavation to a firm surface, level, stepped, or serrated as the Engineer directs, and remove all loose material.</p> <p>For an arch abutment, the back face must be trimmed to true lines so that concrete can be poured against undisturbed material.</p> <p>If concrete will rest on any excavated surface other than solid rock, the Contractor must not disturb the bottom of the excavation. The Contractor must also remove all loose or soft material just before pouring the concrete.</p> <p>Upon completing any foundation excavation, the Contractor must notify the Engineer. No concrete or other permanent part of the Structure may be placed until the Engineer has given permission to proceed.</p>
2-13.3(1)A	General	<p>Replace this Section with the following:</p> <p>Rock facings except fire hydrant wall requirements per Standard Plan 313 must be constructed, rebuilt, or relocated at the locations and to the limits shown on the Drawings. The subgrade elevation and location of the rock facing must be as shown on the Drawings or established by the Engineer.</p>
2-16.3(3)E	Visual Verification of Existing Underground Facilities	<p>Replace the first sentence of this Section with the following:</p> <p>When the proposed bore path is within 36 inches of an existing underground facility or service lateral, or where shown on the Drawings, the Contractor must visually verify the DHA safely clears an underground facility and that the underground facility is isolated from drilling fluid.</p>
2-17.3(3)E	Visual Verification of Existing Underground Facilities	<p>Replace the first sentence of this Section with the following:</p> <p>When the proposed auger bore alignment is within 24 inches of an existing underground facility or service lateral, or where shown on the Drawings, the Contractor must visually verify that the leading edge of the casing safely clears the underground facility by exposing the underground facility while the leading edge advances.</p>
6-02.3(6)E	Tolerances	<p>Insert New Section:</p> <p>Section 6-02.3(6)E TOLERANCES</p> <p>Unless noted otherwise, concrete construction tolerances must be in accordance with this section. Tolerances in this section do not apply to cement concrete pavement.</p> <p>Deviation from plane: ±0.5 inch in 10 feet.</p> <p>Deviation from plumb or specified batter: ±0.5 inch in 10 feet, but not to exceed a total of ±1.5 inches.</p> <p>Vertical deviation of top surfaces (except roadway surfaces): ±0.75 inch.</p> <p>Thickness of bridge decks and other structural slabs not at grade: ±0.25 inch.</p> <p>Length, width and thickness of elements such as columns, beams, crossbeams, diaphragms, corbels, piers, abutments and walls, including dimensions to construction joints in initial placements: +0.5 inch, -0.25 inch.</p> <p>Length, width and thickness of spread footing foundations: +2 inches, -0.5 inch.</p>

Section # or/ Plan #	Current Title	Text
		<p>Horizontal location of the as-placed edge of spread footing foundations: The greater of $\pm 2\%$ of the horizontal dimension of the foundation perpendicular to the edge and ± 0.5 inch. However, the tolerance must not exceed ± 2 inches.</p> <p>Location of opening, insert or embedded item at concrete surface: ± 0.5 inch.</p> <p>Cross-sectional dimensions of opening: ± 0.5 inch.</p> <p>Bridge deck, bridge approach slab, and bridge traffic barrier expansion joint gaps with a specified temperature range, measured at a stable temperature: ± 0.25 inch.</p> <p>Horizontal deviation of centerline of bearing pad, oak block or other bearing assembly: ± 0.125 inch.</p> <p>Horizontal deviation of centerline of supported element from centerline of bearing pad, oak block or other bearing assembly ± 0.25 inch.</p> <p>Vertical deviation of top of bearing pad, oak block or other bearing assembly: ± 0.125 inch.</p>
6-03.3(14)	Edge Finishing	<p>Replace this Section with the following:</p> <p>All rolled, sheared, and thermal cut edges must be true to line and free of rough corners and projections. Corners along exposed sheared or cut edges must be broken by light grinding or another method acceptable to the Engineer to achieve an approximate 1/16- inch chamfer or rounding.</p> <p>Sheared edges on plates more than $\frac{5}{8}$ inch thick must be planed, milled, ground, or thermal cut to a depth of at least $\frac{1}{8}$ inch.</p> <p>Re-entrant corners or cuts must be filleted to a minimum radius of 1 inch.</p> <p>Exposed edges of main load-carrying tension members or tension components of flexural members must have a surface roughness no greater than 250-micro inches as defined by the American National Standards Institute, ANSI B46.1, Surface Texture. Exposed edges of other members must have surface roughness no greater than 1,000-micro inches.</p> <p>The Rockwell hardness of thermal-cut edges of structural low alloy or high-strength steel flanges, as specified in Sections 9-06.2 and 9-06.3, for main load-carrying tension members or tension components of flexural members must not exceed RHC 30 when tested in accordance with ASTM A1038. The fabricator must prevent excessive hardening of flange edges through preheating, post heating, or control of the burning process as recommended by the steel manufacturer.</p> <p>Hardness testing must consist of testing thermal-cut edges with a portable hardness tester. The Contractor must submit the hardness tester, and its operating test procedures to the Engineer for approval. The hardness tester must be convertible to Rockwell C scale values.</p> <p>At two locations, two tests must be performed on each thermal-cut edge, one each within $\frac{1}{4}$ inch of the top and bottom surfaces. The tests must be located $\frac{1}{4}$ the length of each thermal-cut edge from each end of the cut. If one or more readings are greater than RHC 30, the entire length of the edge must be ground or machined to a depth sufficient to provide acceptable readings upon further retests. If thermal-cutting operations conform to procedures established by the steel manufacturer, and hardness testing results are consistently within acceptable limits, the Engineer may authorize a reduction in the testing frequency.</p> <p>Hardness testing is the responsibility of the fabricator. The hardness testing device operator must be trained in its operation and competent in its use. Documentation of operator training must be made available to the Engineer upon request. Results of all hardness testing must be submitted to the Engineer.</p>
6-09.3(14)	Checking for Bonds	<p>Delete the contents of this Section and replace with the following:</p> <p>After the requirements for curing have been met, the entire overlaid surface must be sounded by the Contractor, as approved by and in the presence of the Engineer, to ensure total bond of the concrete to the bridge deck. Concrete in un-bonded areas must be removed and replaced by the Contractor with the same modified concrete as used in the overlay at no additional expense to the Owner, as specified in Section 6-09.3(6) except as modified here.</p> <p>All removal must maintain square edges at the boundaries of the repair area. Concrete for patching must be the same modified concrete as used in the overlay.</p> <p>The repair area must be wet cured for 42 hours in accordance with Section 6-09.3(13). After curing requirements have been met, all repaired areas must be sounded by the Contractor in accordance with this Section.</p>

Section # or/ Plan #	Current Title	Text
6-09.3(15)	Sealing and Texturing Concrete Overlay	<p>Insert the following new Section:</p> <p>6-09.3(15) Sealing and Texturing Concrete Overlay</p> <p>After the requirements for checking for bond have been met as specified in Section 6-09.3(14), all joints and visible cracks must be filled and sealed with a high molecular weight methacrylate resin (HMWM). Cracks 1/16 inch and greater in width must receive two applications of HMWM. Immediately following the application of HMWM, the wetted surface must be coated with sand for abrasive finish. After all cracks have been filled and sealed and the HMWM resin has cured, the concrete overlay surface must receive a longitudinally sawn texture in accordance with Section 6-02.3(10)D. Traffic must not be permitted on the finished concrete until it has reached a minimum compressive strength of 3,000 psi, as verified by rebound number determined in accordance with ASTM C805, and the longitudinally sawn texture is completed.</p>
6-12.3(9)B	Inspection of Access Tubes	<p>Replace this Section with the following:</p> <p>After placing the shaft concrete and before beginning the crosshole sonic log testing of a shaft, the Contractor must inspect the access tubes. Each access tube that the test probe cannot pass through must be replaced, at the Contractor's expense, with a 2-inch diameter hole cored through the concrete for the entire length of the shaft.</p> <p>Unless directed otherwise by the Engineer, cored holes must be located approximately 6 inches inside the reinforcement and must not damage the shaft reinforcement. The Contractor must submit to the Engineer, for review and approval per Section 1-05.3(3), a plan describing the conduct of the core hole drilling operation including measures to ensure core hole verticality and avoidance of reinforcement. Descriptions of inclusions and voids in cored holes must be logged and a copy of the log must be submitted to the Engineer. Findings from cored holes must be preserved, identified as to location, and made available for inspection by the Engineer.</p>
7-08.5	Payment	<p>Add the following to item 7. Other Payment Information:</p> <p>The cost for removal and disposal of existing pipe within trench neat line limits of new pipe to be installed is incidental to the new pipe installation and no separate payment will be made.</p>
7-11.3(6)E	Insulated Couplings and Flange Kits	<p>Add the following new Section (Moved from 7-11.3(9)C1):</p> <p>7-11.3(6)E INSULATED COUPLINGS AND FLANGE KITS</p> <p>Install insulated couplings and flange kits to electrically isolate the Water Main from other Structures. Locate insulated joints as shown on the Drawings.</p> <p>Carefully align and install insulating couplings and flange kits according to the manufacturer's recommendations to avoid damaging insulating Materials. Coat all exposed surfaces of insulating flange, including fasteners, with petroleum impregnated wax tape as specified in AWWA C217. Submit the manufacturer's installation recommendations to the Engineer for review at least 3 Working Days before use.</p>
7-11.3(9)	Connections	<p>Replace this Title and Section with the following:</p> <p>7-11.3(9) WORK ON EXISTING WATER MAINS</p> <p>7-11.3(9)A GENERAL</p> <p>Do not operate any valve on an existing Water Main.</p> <p>SPU Water Operations will make all connections to charged Water Mains and will operate all valves to accomplish shutdowns and subsequent reactivation. The Contractor must contact the Engineer at least 10 Working Days in advance to schedule Work requiring SPU Water Operations per Section 1-07.28. However, the Contractor is encouraged to communicate and coordinate with the Engineer as early in the project as possible regarding the scheduling of these connections as SPU Water Operations' shutting down and starting up portions of the water system will take into consideration:</p> <ol style="list-style-type: none"> 1. Size of Water Main and total system impacts. 2. Coordination with Fire Department. 3. End user Customer needs and coordination.

Section # or/ Plan #	Current Title	Text
		<p>4. SPU Water Operation's workforce availability.</p> <p>5. Contractor's workforce availability.</p> <p>6. Notifications of the scheduled shutdown will be made by SPU Customer Service / Inspection Services personnel to the affected consumers a minimum of 5 Working Days in advance of the shutdown.</p> <p>Also see Section 7-15 Water Service Connections.</p> <p>7-11.3(9)B CONNECTIONS TO EXISTING WATER MAIN</p> <p>Newly installed Water Main must be pressure tested and must be acceptable as specified in Sections 7-11.3(11) and 7-11.3(12) before making any connection. When required, newly installed Water Main must pass the taste and odor rating test as specified in Sections 7-11.2(2) and 7-11.2(3) before and/or after making any connection.</p> <p>After all tests, flushing, and disinfection have been completed and the installed Water Main has been approved by the Engineer, the Contractor may submit a request to the Engineer to schedule the shutdown and connection with SPU Water Operations. Connections must be made within 14 Calendar Days after the date of written notice that flushing and disinfection sample analysis indicated acceptable results per Section 7-11.3(12)A.</p> <p>Provide the Engineer 2 Working Days advance notice for scheduling inspections for approval of Water Main installations for connection. Within 2 Working Days after the inspection, the Contractor will be provided with written approval or with a list of items to be corrected. Items to be corrected will be reinspected. The notification requirement and reinspection response times are the same as the initial inspection. Approval is contingent on the Water Main and appurtenances being completely installed and tested per Contract.</p> <p>The Contractor's scheduling of connections requires the Engineer's approval on the following items:</p> <ol style="list-style-type: none">1. Verification of existing Water Main grade and alignment per Section 7-11.3(4)B. The Contractor must match the grade and alignment of the new Water Main to the existing Water Main.2. Contractor's written list of materials being supplied.3. Verification and inspection of Contractor's supplied materials. <p>All connections to existing Water Main will be performed by SPU Water Operations. Contractor must assist SPU Water Operations with connections and the Contractor is responsible for the following elements of work:</p> <ol style="list-style-type: none">a. Protection of the Water Main and services during construction.b. Coordination with Engineer and SPU Water Operations staff including scheduling per Section 7-11.3(9)A.c. Preparation of the Project Site prior to arrival of SPU Water Operations, including excavation, dewatering, support and safety systems, and traffic control.d. The Contractor must furnish all materials and equipment required to complete the connection not specifically called out in the Contract as being furnished by SPU Water Operations. The Contractor must furnish and install the connection fitting on new Water Mains (see Standard Plan 300a, 300b, and 300c). SPU will furnish connection fittings to existing Water Mains, unless otherwise specified. All required materials and equipment supplied by the Contractor must be available on the Project Site during the shutdown.e. Provide equipment and operators required for trench excavation and to move and lower the component parts of the connection into position. A dedicated crew must be provided for the duration of the Work and must be solely dedicated to assist SPU Water Operations. Additional equipment and operators must be provided as necessary for multiple connections during the same shutdown.f. Removal of abandoned pipes, appurtenances, and blocking.g. Coat, wrap, and joint bond the connection to conform with the requirements of the new Water Main.h. Provide pipe bedding per Standard Plan 350, backfill, compaction, and temporary pavement patch. <p>In addition to those connections shown on the Drawings, segments of a new Water Main may be placed in service before completion of the entire Water Main. All connections between the charged and uncharged segments of the new Water Main will be done by SPU Water Operations. Locations of connections between segments of new Water Main are dependent on Contractor's operations and are not shown. The Contractor must furnish all Materials for such connections.</p> <p>7-11.3(9)C CUT, CAP, AND BLOCKING FOR EXISTING WATER MAIN</p> <p>Where indicated in the Drawings or as directed by the Engineer, a cut, cap, and blocking to isolate existing Water Main will be performed by SPU Water Operations. The Contractor must verify the existing Water Main grade and alignment per Section 7-11.3(4)B prior to scheduling the cut and cap.</p> <p>The Contractor must assist SPU Water Operations with the cut, cap, and blocking, and is responsible for the following elements of work::</p> <ol style="list-style-type: none">1. Protection of the Water Main and services during construction.2. Coordination with Engineer and SPU Water Operations staff including scheduling per Section 7-11.3(9)A.3. Preparation of the Project Site prior to arrival of SPU Water Operations, including excavation, dewatering, support and safety systems, and traffic control.4. Provide equipment and operators required for trench excavation and to move component parts of the cut and cap into position. A dedicated crew must be provided for the duration of the work and must be solely dedicated to assist SPU Water Operations. Additional equipment and operators must be provided as necessary for multiple cut and caps during the same shutdown.5. Furnish and install precast Ecology Block or Dailey Block as indicated in the Contract or as directed by the Engineer.6. Removal of abandoned pipes and appurtenances.7. Backfill, compaction, and placement of temporary pavement patch.

Section # or/ Plan #	Current Title	Text
		<p>7-11.3(9)D TEMPORARY WATER MAINS AND SERVICES</p> <p>Temporary Water Mains 4" diameter and larger must be installed and maintained by the Contractor in such a manner as to provide constant, adequate water supply to customers and to avoid impeding traffic and access to abutting properties. Temporary Water Mains 2" and smaller will be installed by SPU Water Operations unless otherwise noted on the Drawings or Project Manual.</p> <p>The Contractor's critical path schedule must allow adequate time for installation and connection of these temporary Water Mains and services. Provide the Engineer a minimum of 10 Working Days advance written notice for scheduling of the temporary Water Main and service work.</p> <p>Support SPU Water Operations by performing all required excavation, backfill, and compaction. SPU Water Operations will furnish the necessary equipment and pipe for 2" and smaller temporary Water Mains, unless otherwise noted in the Contract.</p> <p>All temporary Water Mains will be disinfected, flushed, and sampled for bacteriological testing by the SPU Customer Service / Inspection Services. When found acceptable, the temporary Water Mains will be placed in service per 7-11.3(9)B.</p> <p>The Contractor is solely responsible for maintaining private water service laterals in service. When it is necessary to provide temporary water supply, the Contractor is responsible for providing temporary services on the private side of the water service. Should construction activity damage or disrupt private water service laterals or appurtenances, immediately notify the Engineer of any such damage or disruption. The Contractor must start repairs immediately as directed by the Engineer, and work continuously until the water service lateral is restored.</p>
7-11.3(9)C1	Insulated Couplings and flange kits	Editor's Note – This Section was moved verbatim to a new section: Section 7-11.3(6)E
7-11.5		<p>Add new item g. to payment item 1"</p> <p>g. Costs of all Material, labor and equipment associated with making a cut, cap and blocking to isolate existing water main unless otherwise specified. and</p>
7-14.3(1)	Setting Hydrants	<p>Replace the third paragraph with the following:</p> <p>For each new hydrant requiring vertical adjustment, see Section 7-14.3(5).</p>
7-15.3	Construction Requirements	<p>Replace this Section with the following:</p> <p>7-15.3 CONSTRUCTION REQUIREMENTS</p> <p>Where existing services are transferred from old to new Water Mains, the Contractor must plan and coordinate the Work with SPU Water Operations to ensure service is resumed with the least possible inconvenience to customers.</p> <p>Water service connections, number and type of connections, sequencing of work, operation and construction needs and related work will be addressed at the preconstruction conference. Service transfers must not be connected until the new Water Main has been tested and accepted by the Engineer.</p> <p>Provide the Engineer at least 10 Working Days advance notice when transfer of existing water service is required per Section 1-07.28.</p> <p>SPU will, at no cost to the Contractor, mark the exact field locations of service taps and tees on services 2 inches and smaller. Locations of services larger than 2 inches will be identified on the Drawings. The Contractor must assist SPU Water Operations and the Contractor is responsible for the following elements of work:</p> <ol style="list-style-type: none"> 1. Protection of the Water Main and services during construction. 2. Excavation for the water service connections, including shoring and dewatering. 3. Furnish and install tees, valves, plugs, and valve boxes for 4-inch, 6-inch, or 8-inch service connections. A 3-inch water service is considered a 4-inch water service. The tees must be mechanical joint (MJ) x mechanical joint x flange (FLG). Valves must be MJ x FLG, and removable plugs must be MJ for the service connection. The MJ plugs will be returned to the Contractor after SPU Water Operations completes the service connections. 4. Removal of abandoned pipes, appurtenances, and blocking. 5. Backfill, compaction, and placement of temporary pavement patch. Maintain the temporary pavement patch until completion of all work by SPU Water Operations. 6. Upon completion of work by SPU Water Operations, make all final adjustments of valve boxes, water meter boxes, and rings and covers to final grade at no cost to the Owner, and then make the final surface restorations as specified in the Contract. <p>If existing water service material to be reconnected to the new or existing Water Main is considered substandard material, such as plastic, cast iron, or galvanized iron pipe, SPU Water Operations will replace it with copper, for 2-inch and smaller, or ductile iron for, 3-inch and larger, from the water service union to the new or existing Water Main.</p> <p>To supply customers with water during the construction, where any section of pipe has passed the required hydrostatic and bacteriological tests, SPU Water Operations may tap corporation stops into a section of a new Water Main and install corporation stops and service connections at locations where SPU Water Operations deems necessary, at no expense to the Contractor. The attaching of any such service connections by SPU Water Operations does not constitute acceptance by the Engineer of any part of the Work required under the Contract.</p>

Section # or/ Plan #	Current Title	Text
		<p>The Contractor must not remove or abandon existing Water Main until all existing service connections have been transferred to the new Water Main or temporary service has been provided, and the Engineer has provided approval.</p> <p>See also Section 7-11.3(9) Work on existing Water Mains.</p>
7-17.3(2)H2	Casing Pipe, Spacers and End Sealing	<p>Delete the second sentence of the second paragraph:</p> <p>The annular space between the casing and carrier pipes must be filled with Material specified in the Contract.</p>
7-17.3(3)G4	Television Inspection Record Submittal Requirements	<p>Replace item 3. of the first paragraph with the following:</p> <p>3. A complete video recording of the television inspection in MP4 format.</p>
7-20.3(4)	Adjustment of Valve Box Castings	<p>Replace this Section with the following:</p> <p>If an existing water valve box requires adjustment, it must be done by excavating the casting and vertically adjusting the top section of the valve box. The flange must be cast into surrounding pavement as shown on Standard Plan 315. Do not use ring extensions.</p>
8-01.3(2)A	Construction Stormwater and Erosion Control Plan	<p>Add note 5a. to this Section:</p> <p>5a. Show locations of existing surface waters and natural or vegetated buffers to be maintained.</p>
8-01.3(2)B	Tree, Vegetation and Soil Protection	<p>Replace this Section with the following:</p> <p>The construction stormwater pollution prevention submittals must include a TVSPP.</p> <p>The Contractor must develop a TVSPP for the specific Project Site. The TVSPP must be accepted by the Engineer before any mobilization occurs at the Project Site. Alteration of protective measures described in the TVSPP must be approved by the Engineer.</p> <p>The TVSPP must show the location of BMPs used to protect existing trees (not designated for removal), vegetation, and soil for the duration of the Contract. The TVSPP may be submitted in phases when specified or approved by the Engineer. The Contractor must maintain and regularly update the TVSPP submittal as necessary to document site conditions and show required BMPs.</p> <p>The Contractor's schedule for installation of protective measures must be shown in the Critical Path Schedule and applicable weekly look-ahead schedules. Locations, extent, and type of BMPs must be approved by the Engineer during a joint field review with the Contractor. Conflicts between protection measures and Work required under the Contract must be brought to the attention of the Engineer during the joint field review and during weekly project meetings.</p> <p>Trees, vegetation, soil, and other areas to be protected may include any of the following:</p> <ol style="list-style-type: none"> 1. Trees identified by the note "Protect Trees" on the Drawings or trees not identified for removal where Zone B (see Standard Plan 133) is within the construction limits. 2. Vegetation identified by the note "Protect Landscaping" on the Drawings or vegetation identified for protection during the TVSPP joint field review. 3. Soil and existing tree and vegetation roots in areas identified by the note "Do Not Disturb" on the Drawings. 4. Tree roots encountered during excavation, except when the roots are less than 2 inches in diameter and are within roadway surfacing section, driveway surfacing section, sidewalk surfacing section, utility prisms, and within 1-foot of improvement structures geometrics (such as retaining walls, bridge abutments, and pole foundations.) A utility prism is the volume centered about the utility equal to the trench width in both vertical and horizontal dimensions. Utility prisms are not defined for conduit or for trenchless construction methods. 5. Areas marked "Pervious Concrete" on the Drawings.

Section # or/ Plan #	Current Title	Text
		<p>6. Areas marked “Rain Garden” or “Bioretention” on the Drawings.</p> <p>7. Other areas to be protected as directed by the Engineer during the joint field review and as documented in the approved TVSPP.</p> <p>Storage of equipment or materials is not allowed within the areas marked on the Drawings as “Do Not Disturb” or within the Zone B of a tree unless BMPs per the approved TVSPP are in place. BMPs for approved storage within Zone B or areas marked as “Do Not Disturb” must be at a minimum 1-inch steel plate or 4-inch thick timber planking over 2 to 3 inches of AWCM, or a minimum 3/4-inch plywood over 6 to 8 inches of AWCM.</p> <p>For protection of trees, as specified in item 1. above, the TVSPP must address the following protective measures unless otherwise approved by the Engineer in writing:</p> <p>a. Where construction operations are within the limits of Zone B for a duration of more than 30 Calendar Days, protect trees in unpaved planting strips or in tree pits per Standard Plan 132a.</p> <p>b. Where construction operations are within the limits of Zone B for a duration of 30 Calendar Days or less, protect trees in tree pits per Standard Plan 132b. The temporary tree protection fence must surround the entire tree pit area and be anchored and maintained in a stable upright condition.</p> <p>c. Where excavation will occur within the limits of Zone B, show the limits of each excavation location and review the excavation method with the Engineer during the joint field review. Within Zone B, excavation methods may include tunneling, air spade or hand digging to minimize root damage. The method of excavation must allow for all roots 2 inches and larger in diameter to be protected. Where roots 2 inches in diameter and larger are discovered, the Contractor must promptly notify the Engineer. If allowed, root pruning must be as specified in Section 8-02.3(7)A.</p> <p>For protection of soil conditions and existing roots, as specified in items 3. and 4. above, the TVSPP must include the following specific protective measures to prevent damage to existing soils and roots during all construction activities within Zone B:</p> <p>1) Double-layered burlap cover for all newly exposed soil and/or roots and daily watering for exposure of 5 Working Days or less.</p> <p>2) 6 inches of AWCM cover for all newly exposed soil and/or roots and twice weekly watering to protect soil from compaction, retain soil moisture, and control erosion.</p> <p>3) Temporary or chain link construction fencing enclosing all newly exposed soil and/or roots associated with trees and other vegetation beyond the construction limits.</p> <p>For protection of pervious concrete sidewalks and pavements, as specified in item 5. above, following the removal of any existing pavement, a Standard Plan 132b enclosure must surround the entire area where pavement was removed, and the enclosure must be anchored and maintained in a stable upright condition.</p> <p>For protection of rain gardens or bioretention areas, as specified in item 6. above, and where construction operations abut, impact, or are within the limits of rain gardens or bioretention areas for a duration of more than 30 Calendar Days, protection per Standard Plan 132a, Option 2, surrounding the entire area as shown on the Drawings is required. Where construction operations are within the limits shown on the Drawings for a duration of 30 Calendar Days or less, a Standard Plan 132b enclosure must surround the entire area and be anchored and maintained in a stable upright condition.</p> <p>The TVSPP must also address the following general protective measures unless otherwise approved by the Engineer in writing:</p> <p>a) If canopy/clearance pruning is required to perform the Work within standard vertical clearances, the Contractor must notify the Engineer at the TVSPP joint field review, or at least 15 Working Days in advance to allow pruning by the Owner or private property owner. The Engineer may require that this canopy/clearance pruning be performed by the Contractor as specified in Section 1-04.3. Standard vertical clearances are 14 feet for roadway, 10 feet for bicycle paths, 8 feet for sidewalks, and as specified in the Contract.</p> <p>b) Pruning of canopy for construction clearance above standard vertical clearances is not allowed unless no alternative options, such as temporary tie-up of low limbs or alternative construction methods, are feasible, as determined by the Engineer.</p> <p>c) Where canopy/clearance pruning above standard vertical clearances is approved by the Engineer, the Contractor is responsible for this pruning and all associated costs.</p> <p>d) If the Contractor performs canopy/clearance pruning, the Work must be done by a registered Tree Service Provider with a current registration on file with SDOT Urban Forestry, and the pruning work must be performed by technicians with current ISA certification. See Section 8-02.3(7)A for pruning specifications. When pruning is necessary to perform the work and the pruning is not identified and brought to the attention of the Engineer during the TVSPP joint field review,</p>

Section # or/ Plan #	Current Title	Text
		<p>the Contractor must submit a canopy/clearance plan for approval by the Engineer. The canopy/clearance plan must include the current registration and ISA certification as an addendum to the TVSPP. A separate TVSPP-canopy/clearance pruning submittal must be submitted at least 5 Working Days in advance as specified in Section 1-05.3. If pruning is performed at both the Owner's and Contractor's cost as described here within, the cost will be prorated.</p> <p>e) Where construction activity involves the operation of equipment or redirection of traffic from established travel lanes into Zone B of trees within or overhanging the Right Of Way, the Contractor must depict these conditions on the TVSPP.</p> <p>f) Protective measures installed over grass, groundcover, or vegetation to be preserved must be removed in a timely manner to minimize impacts to plant health.</p> <p>g) Soil management/protective measures must include eradication of ivy and other invasive weed species before placement of AWCM in areas to be protected from disturbance.</p> <p>h) Excavation or tunneling of any kind within the Critical Root Zone (Zone A) of a tree requires approval by the Engineer. The Contractor must provide at least 2 Working Days advance written notice for review and must not proceed without field inspection and approval.</p> <p>i) Excavation excluded from specific protective measures but within Zone B of a tree must be performed with care to minimize damage to roots. In all excavations, if roots 2 inches and larger are encountered, the excavation at the root location must stop and the Contractor must promptly notify the Engineer. If root pruning is required, see Section 8-02.3(7)A for pruning cuts and methods.</p> <p>j) Protect trees from exhaust heat. Exhaust deflection panels may be required on some equipment to prevent burning of foliage and branches of trees to be protected.</p> <p>See Standard Plans 132a and 132b for additional tree protection guidance. See Standard Plan 133 for a description of tree root Zones A, B, and C.</p>
8-02.3(9)B	Flexible Porous Surface Treatment	<p>Replace this Section with the following:</p> <p>Flexible porous surface treatment must be designed, mixed, and installed per the manufacturer's recommendations. Flexible porous surface treatment must be Porous Pave XL, KBI Flexipave, or approved equal. Color must be grey-black or granite, or an approved equivalent or alternate color. Mix must have 25 to 30-percent void ratio and be comprised of 50-percent recycled rubber chips and 50-percent kiln-dried aggregate.</p> <p>For approval of equal material, the Contractor must submit product information, including limitations related to weather conditions or site-specific conditions, to the Engineer for approval. Submittal must also include a minimum of three examples of product installations within the last five years at a project location within 75 miles of the work site.</p> <p>All material submittals must include confirmation from the manufacturer that the Contractor or Subcontractor installing the flexible porous surface treatment has been trained and is currently certified to install the product.</p> <p>Install a base course of Mineral Aggregate Type 22 to a minimum 2-inch depth prior to placement of flexible porous surface treatment to provide a stable and uniform base. Flexible porous surface treatment must be placed to a minimum depth of 2 inches where applied adjacent to a sidewalk or curb, or a minimum depth of 4 inches where applied adjacent to multi-use trails. The finished surface of the flexible porous surface treatment must be uniform and flush with adjacent surfaces. Uniform and flush surface conditions must be maintained throughout the landscape establishment period.</p> <p>Flexible porous surface treatment must not be placed adjacent to trees within 10 Working Days of when the tree was installed and the pit and surrounding areas were backfilled and allowed to settle under natural conditions. See Section 8-02.3(6)B.</p> <p>Flexible porous surface treatment is subject to inspection and repair at the time of project acceptance, at quarterly inspections, and at the end of the landscape establishment period or warranty period described in Section 1-05.10.</p>
8-14.3(7)	Curb Ramp	<p>Delete the second paragraph in this Section and replace it with the following:</p>

Section # or/ Plan #	Current Title	Text
		Curb passing through the curb ramp must be monolithic with the curb ramp unless the curb ramp is built within a curb and gutter section. Curb ramps, including landings and shared landings, must be constructed separately from the sidewalk with a through joint per Section 8-14.3(6). Bond-breaking material such as polyethylene film, roofing paper, or other material as approved by the Engineer must be installed between the pavement and curb and gutter.
8-17.3(1)	Construction Requirements - General	Delete the first Paragraph in this Section and replace it with the following: Where shown on the Drawings, the Contractor must construct curb wall and support wall as shown on Standard Plan 800 and 801.
8-17.4	Measurement	Delete the contents of this Section and replace with the following: Measurement for support wall and curb wall will be per cubic yard of concrete based on neat lines indicated on Standard Plans 800, and 801.
8-17.5	Payment	Delete the contents of this Section and replace with the following: 1. “Wall, Cement Concrete, Support, Type 800” , per cubic yard The Bid Item price for “Wall, Cement Concrete, Support, Type 800” must include all costs for the work required to construct the wall as shown on Standard Plan 800. Payment for excavation, for disposal of materials, backfill, geotextile, and for reinforcing steel (including steel extending into pavement slab) for the support wall must be considered included in the Bid Item price. 2. “Wall, Cement Concrete, Curb, Type 801” , per cubic yard The Bid Item price for “Wall, Cement Concrete, Curb, Type 801” (including reinforcing steel extending into pavement slab) must include all costs for the work required to construct the wall as shown on Standard Plan 801. Payment for excavation, for disposal of materials, backfill, geotextile, and for reinforcing steel for curb wall is considered included in the Bid Item price.
8-19.3(3)	Placing and Finishing Cement Concrete Driveway and Alley	Replace the first sentence of the second paragraph with the following: Through joints as shown on the Standard Plans must be 3/8-inch thick premolded joint filler.
8-19.4	Measurement	Delete the last two paragraphs in this Section and replace with the following: Measurement for alley will be by the square yard for the class and thickness of concrete actually placed per Standard Plan 403 and will be measured as “cement concrete driveway”.
8-19.5	Payment	Delete list Item 4 in this Section and replace it with the following: 4. Alley payment information Payment for alley will be made as “Driveway, Cement Concrete...” as shown on the Drawings.
8-22.1(2)D	Pavement Marking Callout Examples	Replace the last row of the table with the following: S-T720c Right Arrow per Standard Plan 720 detail 720c
8-22.3(7)	Temporary Pavement Marking	Delete the reference to Section 1-10.3(4)C.
8-31.3(3)B	Vehicle Signal Heads	Replace the seventh paragraph with the following:

Section # or/ Plan #	Current Title	Text
	Editor's Note: See also 9-32.1(1)A	Vehicle signal heads must be attached to the mast arm either with a signal coupling unit or bracket mounted as detailed on Standard Plan 510A and 562b. Signal head attachment type is shown on the Drawings. Coupling mounts must include elevator straight plumbizer units between the red and yellow signal sections, or 90 degree plumbizers. Bracket mounts must include a cable mount kit and a clamp kit.
8-31.3(14)	Owner Furnished Equipment and Materials	<p>Add the following to this Section:</p> <p>The Contractor must provide written notice to the SDOT Signal Operations Engineer at least 5 months in advance of the proposed pickup date for any traffic signal controller cabinets that are needed for permanent or temporary signal work. For installation of the traffic signal controller cabinet, the Contractor is required to have power service at the cabinet location and to be hooked up to keep the electronics warm and dry until energizing the traffic signal.</p>
8-31.3(16)	Turn On/Cut Over Procedure	<p>Replace the third sentence of the first paragraph with the following:</p> <p>A request for “turn on” of a new signalized intersection or “cut over” modifications to existing signalized intersection must be submitted in writing to the Engineer at least 15 Working Days before the proposed date of an existing signal cut over, and 15 Working Days before the proposed date of a new signal turn on.</p> <p>Add the following to the third paragraph:</p> <p>Any alternative times must be submitted by the Contractor at least 15 Working Days before the proposed date and time of the signal turn on or cut over. Alternative times must be approved by the Engineer.</p> <p>Replace the first sentence of the sixth paragraph with the following:</p> <p>Do not install signal heads at any intersection earlier than 10 Working Days before turn on or cut over. All new vehicular and pedestrian signals including backplate and illuminated signs must be temporarily covered completely with a 6 mil opaque polyethylene sheeting, or approved equal until the new signals are ready to be energized.</p>
8-31.3(19)	CCTV Camera	Replace this Section number with 8-31.3(19)A
8-31.3(19)B	Fish-Eye Camera	<p>Insert this new Section:</p> <p>Contractor must submit for approval to the Engineer the manufacturer's recommended video camera cable. Contractor must furnish and install a continuous cable between the camera and the termination in the controller cabinet. Camera cable must be coiled in the handhole adjacent to the controller cabinet. The Contractor must notify the Engineer 10 Working Days before final pull into cabinet. Sufficient cable slack must be provided in the adjacent controller handhole to enable final connection to the camera processor.</p> <p>Contractor must furnish all camera mounting bracket and hardware to mount the luminaire bracket arm, mast arm, or pole as specified on the Drawings. Mounting hardware must include a camera mount kit and a clamp kit.</p> <p>All external screws, nuts and locking washers must be stainless steel or galvanized. Self-tapping screws must not be used. All parts must be made of corrosion resistant materials. All materials used in construction must be resistant to fungus growth and moisture deterioration. An inert dielectric material must separate dissimilar metals. The camera assemblies must be capable of accurate detection when mounted greater than 30 feet above the road surface. The camera assemblies must be capable of accurate detection when mounted up to 150 feet from the stop bar.</p> <p>Installation of the camera must require no aiming or focusing of the camera assembly. The minimum Video Imaging Vehicle Detection System (VIVDS) set-up, as needed for detector setup and viewing of vehicle detections, must consist of a field setup computer with application software and/or a video monitor with interface software built-in to the VIVDS processor unit. The field-setup computer must have an Ethernet port for connection to the Machine Vision Processor (MVP).</p>
8-31.4	Measurement	<p>Add the following:</p> <p>Measurement for “Fish- Eye Detection Camera ” will be per each installed.</p>

Section # or/ Plan #	Current Title	Text
8-31.5	Payment	<p>Delete the first paragraph of this Section.</p> <p>Edit item 24. to read:</p> <p>“Service Cabinet (Type)”, per each.</p> <p>Add item 27. “Fish-Eye Detection Camera”, per each.</p> <p>The Bid item price for “Fish-Eye Detection Camera” must include all costs for the work required to furnish and install a fully functioning camera, including all wiring, testing, mounting hardware and other appurtenances.</p>
8-32.3(6)	Chief Seattle Base and Collar	<p>Replace this Section with the following:</p> <p>Where shown on the Drawings, the Contractor must install decorative Chief Seattle base and collar at the foundations of poles.</p> <p>Chief Seattle base and collar materials must be purchased from SCL. For information on Chief Seattle base and collar purchase costs, lead times, and delivery requests, contact a SCL Electrical Service representative at (206) 615-0600 for orders north of Denny Way, or (206) 386-4200 for orders South of Denny Way.</p> <p>Contractor must coordinate with SCL Electrical Service representative at the preconstruction meeting or a minimum of 120 Working Days advance notice for Chief Seattle base and collar pick up schedule. The Contractor must pick up the Chief Seattle base and collar and deliver to Project Site for installation.</p> <p>Install decorative Chief Seattle base and collars as specified in Seattle City Light Construction Standard 1716.38.</p>
9-02.1(4)	Asphalt Cement	<p>Replace the word “shall” with “must” in the second paragraph.</p>
9-05.2(1)	Concrete Pipe General	<p>Replace the last sentence of this Section with the following:</p> <p>The identification of the minor axis of elliptical reinforcement must be in accordance with Section 7-17.2(1).</p>
9-07.5	Dowell Bars (For Cement Concrete Pavement)	<p>Replace this Section with the following:</p> <p>Corrosion resistant dowel bars must be the dimensions specified in Standard Plan 405c and meet the requirements of one of the following:</p> <ol style="list-style-type: none"> 1. Stainless Steel Clad dowel bars must have a minimum 0.06 inches clad to a plain steel inner bar meeting the chemical and physical properties of AASHTO M31, Grade 60, or AASHTO M255, Grade 60. Stainless Steel Clad must meet the chemical properties of ASTM A249 or A269, Grade TP 316L. 2. Stainless Steel Tube dowel bars must have a minimum 0.06-inch-thick tube press fitted onto a plain steel inner bar meeting the chemical and physical properties of AASHTO M31, Grade 60, or AASHTO M255, Grade 60. A lubricant/adhesive must be used between the tube and the plain steel bar to fill any voids. Stainless Steel Tube material must meet the chemical properties of ASTM A249 or A269, Grade TP 316L. 3. Stainless Steel Solid dowel bars must be ASTM A276, Type 316L. 4. Corrosion-resistant, low-carbon, chromium plain steel bars for concrete reinforcement meeting all the requirements of ASTM A 1035 Alloy Type CS Grade 100 or Alloy Type CS Grade 120. 5. Zinc Clad dowel bars must be solid bars or tubular bars with the dimensions specified in Standard Plan 405c and meet the chemical and physical properties of AASHTO M 31, Grade 60 or AASHTO M 255, Grade 60. The bars must have a minimum 0.035 inches A710 Zinc alloy clad in addition to the to the plain steel solid bar or tube dimensions. A710 Zinc must be composed of: zinc: 99.5 percent, by weight, minimum; copper: 0.1 – 0.25 percent, by weight; and iron: 0.0020 percent, by weight, maximum. Each end of tubular bars must be plugged using a snug-fitting insert to prohibit any intrusion of concrete or other materials. 6. Multicoated fusion bonded epoxy bars must consist of an ASTM A615 bar with alternating layers of ASTM A934 coating and an abrasion resistant overcoat (ARO). The ASTM A934 coating must form the base and there must be two layers of each coating material. The minimum thickness of the combined layers of the ASTM A934 coating and ARO coating must be 20 mils. The ARO must meet the following requirements:

Section # or/ Plan #	Current Title	Text			

Section # or/ Plan #	Current Title	Text
		<p>4. System components must comply with the environmental requirements detailed in the NEMA TS 2 standard.</p> <p>5. The system must be designed to operate reliably in an operating temperature ranging from -34°C (-30° F) to +74°C (+165°F) degrees Celsius at 0 percent to 95 percent relative humidity, noncondensing.</p> <p>6. The camera, mounting hardware, and any related material, when properly installed, must be able to withstand 150 mph wind speeds.</p> <p>7. Detection system field hardware must meet the requirements listed in the Federal Communications Commission (FCC) 2005 Code of Federal Regulation (CFR) Title 47, Part 15 and must not interfere with any known equipment. Must be ALDIS GRID SMART or equal.</p> <p>8. The camera must feature an additional warranty to require no aiming or focusing for a period of five (5) years, following successful installation and configuration. This excludes any changes required due to extraordinary impact or duress on the camera.</p> <p>The VIVDS must consist of the following components:</p> <p>a. Camera assembly(ies), machine vision processor (MVP), detection algorithms, application software, and all associated equipment required to setup and operate in a field environment including a field setup computer (if required), connectors and camera mounting hardware.</p> <p>b. The VIVDS must use camera assembly(ies) to collect video image data for the MVP for purposes of detecting vehicle presence and generating traffic data.</p>
STANDARD PLAN (SP) 002e	Abbreviations	Revised abbreviations to include SDCI for Seattle Department of Construction Inspection .
SP 003f	Standard Symbols Paving	Revised Standard Symbols for different types of paving.
SP 003G	Standard Symbols Paving	Revised Standard Symbols for different types of paving.
SP 020c	Survey Monument	Revised call-out for Cap Details A and B.
SP 030	Desirable Locations for Utilities	Revised title, wording, tree clearance notes, and removed incorrect reference.
SP 132a	Tree Protection During Construction	Revised Tree Protection features and notes to align with proposed Specification changes.
SP 132b	Reusable Temporary Protection Fence	Revised by adding note.
SP 133	Tree Protection during Trenching Tunneling or Excavation	Revised Tree Protection features and notes to align with proposed Specification changes.
SP 141	Rock Facing	Revised off set and fencing requirement notes.
SP 230	2' 0" Diameter Frame and Cover	Revised notes concerning height of castings in the Roadway.
SP 240	Type 240 Catch Basin	Revised inlet and outlet call-outs for knock outs.

Section # or/ Plan #	Current Title	Text
SP 260a	Inlet/Catch Basin Location and Installation	Revised to require ADA accessible castings in crosswalks.
SP 260b	Catch Basin and Inlet Installation	Revised to update Welded Wire Fabric (WWF) call-outs.
SP 262	Type 262 Inlet Frame	Revised to show more dimensions.
SP 263a	Type 263 Inlet Frame and Hood	Revised to show more dimensions.
SP 264	Inlet Frame and Grate	Revised Callouts
SP 265a	Vaned Grate	Revised notes to expand the different types of grates that are acceptable to use.
SP 265b	Vaned Grates	New Standard Plan showing different types of grates
SP 266	Type 266 Replacement Vaned Grate	Revised notes to expand the different types of grates that are acceptable to use.
SP 270	Flow Control Structure With Detention Pipe	Revised to remove restrictive sizing table for maintenance hole diameters and adjusted notes accordingly.
SP 283	Side Sewer Installation	Revised to update notes and add a legend.
SP 286a	Sewer & Water Spacing & Clearances	Revised note to include an approval requirement for any exceptions.
SP 286b	Sewer & Water Spacing & Clearances	Revised call-out to include an SDCI inspection requirement.
SP 301	Water Service Relocation for up to 2" Service Pipe Through Bioretention	New Standard Plan showing water service location, construction requirements and clearance requirements in relation to bioretention cells.
SP 302	Watermain Setback Requirement for C.I. Lead Joint and D.I. Slip Joint Pipe	New Standard Plan showing watermain clearances in relation to bioretention cells and notification requirements.

Section # or/ Plan #	Current Title	Text
SP 310a	Type 310 Hydrant Setting Detail	Revised to clarify jointing requirements for Hydrant Connection Pipe to the watermain.
SP 310b	Type 310 Hydrant Setting Detail	Revised to clarify jointing requirements for Hydrant Connection Pipe to the watermain.
SP 311b	Type 311 Hydrant Setting Detail	Revised to add new detail and edit callouts.
SP 312	Fire Hydrant Marker Layout	Revised to correct location of hydrant nut.
SP 313	Wall Requirements for Hydrants	Revised to correct location of hydrant nut.
SP 314a	Fire Hydrant Locations and Clearances	Revised graphics and notes to clarify clearance requirements for fire hydrant locations near curb ramp.
SP 314b	Clearances for Typical Water Service Vaults	Revised graphics and notes to clarify clearance requirements from water service vaults.
SP 340a	2" Blow Off Type A Non Traffic Installation	Revised to include an additional Valve Box located above the isolation valve, where the watermain connects to the copper pipe leading to the blow off assembly.
SP 340b	2" Blow Off Detail Type B Traffic Installation	Revised to include an additional Valve Box located above the isolation valve, where the watermain connects to the copper pipe leading to the blow off assembly.
SP 350	Water Main Trench and Bedding	Revised to correct Specification Section reference.
SP 359	Rebuild Existing Brick Water Valve Chamber	New Standard Plan
SP 401	Residential Pavement Sections	Revised subtitles to better match Specification bid items.
SP 402	Commercial and Arterial Pavement Sections	Revised titles to better match Specification bid items.
SP 405a	Roadway Concrete Pavement Repair	Revised to match new dowel bar requirements

Section # or/ Plan #	Current Title	Text
SP 405c	Roadway Concrete Pavement Joints	Revised to match new dowel bar requirements
SP 406	Frame & Cover Cement Concrete Reinforcement Detail	Revised to change steel spacing requirement.
SP 410	Type 410 curb	Revised to change requirement of concrete thickness.
SP 411	Curb Joints & Dowels	Revised bedding requirements
SP 422a	Curb Ramp Details	Revised notes and call-outs.
SP 422b	Curb Ramp Details	Revised notes and call-outs.
SP 422c	Curb Ramp Details	Revised notes and call-outs.
SP 422d	Curb Ramp Details	Revised notes and call-outs.
SP 422e	Curb Ramp Details	Revised notes and call-outs.
SP 422f	Curb Ramp Details	Revised notes and call-outs.
SP 422g	Curb Ramp Details	Revised notes and call-outs.
SP 422h	Curb Ramp Details	Revised notes and call-outs.
SP 422i	Curb Ramp Details	New Standard Plan
SP 422k	Curb Ramp Details	Revised notes and call-outs.
SP 422l	Curb Ramp Details	Revised dimensions, notes and call-outs.
SP 422f	Curb Ramp Details	Revised to allow for clear space to fall within extended face of curb.
SP 424a	Expandable Tree Pit Detail	Revised callouts for mineral aggregate.

Section # or/ Plan #	Current Title	Text
SP 430a	Type 430a Driveway	Revised Standard Plan 430 and made two Standard Plans 430a and 430b to visually clarify direction of broom finish and jointing requirements.
SP 430b	Type 430b Driveway	Revised Standard Plan 430 and made two Standard Plans 430a and 430b to visually clarify direction of broom finish and jointing requirements.
SP 431	Cement Concrete Driveway placed with Cement Concrete Sidewalk	Revised to visually clarify direction of broom finish and jointing requirements.
SP 440b	Cement Concrete Stairway and Handrail	Revised spacing call out.
SP 510a	Vehicular Signal Mounting	Revised to add additional mounting bracket options.
SP 541a	Traffic Signal Pole Foundation	Revised to change call-outs and detail dimensions.
SP 543a	Street Light Pole Foundations	Revised to clarify concrete collar requirements and add shrubbery and foliage planting clearance note.
SP 543b	Pedestrian Street Light Pole Foundations	Revised to clarify concrete collar requirements and add shrubbery and foliage planting clearance note.
SP 550a	Handholes	Revised to add shrubbery and foliage planting clearance note.
SP 562b	Steel mast Arm Pole Foundation Schedule & Detail W/O Metro Trolley Loads	Revised to add new detail.
SP 710b	Typical Lane Drop Channelization and Legend Placement	Revised call-outs.
SP 710C	Typical Intersection Guideline Channelization	Revised notes and call-outs.
SP 712	Typical Crosswalk & Stop Line Installation Details	Revised notes and graphic.

Section # or/ Plan #	Current Title	Text
SP 717	Typical curbside red bus lane layout	Revised Standard Plan number.
SP 750	Red Bus Lane Markings	Revised details and notes for Red Bus Lane Markings
SP 775	Narrow Bike Lane Turn Arrow Symbols	New Standard Plan
SP 780	Cross Bike Pavement	Revised bike lane dimension notes
SP 800	Support Wall	Substantially Revised
SP 801	Curb Wall	Substantially Revised

End of document