Proposed DRAFT 2026 Standard Plans for Municipal Construction

This DRAFT is published for the 60 day comment period:

November 7th – January 7th, 2026

Table of Contents

For the convenience of some of our users, the Table of Contents shows revised Plans with a vertical bar as well as bold type.

000 General-Legal-Mis	Elevations & Datums	001
	Elevations & Datums	001a
Abbreviations	Abbreviations 00	02a-002f
Standard Symbols	Electrical	003a
•	Electrical	003b
	Electrical	003c
	Electrical	003d
	Signalization / Channelization & Signage	003e
	Paving	003f
	Paving	003g
	Sewer & Drainage	003h
	Sewer & Drainage	003i
	Sewer & Drainage	003j
	Topographic & Misc	003j
	Topographic & Misc	0031
		003i 003m
	Topographic & Misc	
	Topographic & Misc	003n
	Private Utilities	003o
	Water	003p
	Water	003q
	Water	003r
yment	Sewer/Drainage Measurement Diagram	010
onument	Monument Frame & Cover	020a
	Monument Frame & Cover	020b
	Survey Monument	020c
scellaneous	Desirable Locations for Utilities (Residential Street)	030
	Stabilized Construction Entrance	040
00 Landscape Planti	ng	
rees	Deciduous Tree Planting in Planting Strip	100a
	Tree & Shrub Planting on Slopes	100b
	Tree Planting in Amended Trench	100c
	Coniferous Tree Planting	101
nrub & Ground Cover	Shrub Planting	110
	Ground Cover Planting	111
	Planting Pattern	112
	Median Planting	113
igation	Irrigation Point of Connection Diagram Irrigation Point of Connection Diagram for Batter	115a
	Operated Controllers	115b
	Irrigation Master Valve & Flow Sensor	120
	Irrigation Master Valve & Flow Sensor Irrigation Hose Bib Assembly & Quick Coupler Val	
	Irrigation Valves	122
	Irrigation Valves	123

Tree Protection	Irrigation Valves Irrigation Valves Pop Up & Fixed Irrigation Heads Irrigation Controller Pedestal & Enclosure Grounding Irrigation Trenches Irrigation Trenches Irrigation Controller Cabinet Tree Protection During Construction Reusable Temporary Protection Fence Tree Protection During Trenching, Tunneling or Excavation	124 125 126 127 128a 128b 129 132a 132b
Grading	Slope Rounding Rock Facing Soil Amendment and Depth	140 141 142
Soil Cell	Soil Cell Soil Cell Irrigation for Tree Pits with Soil Cells Irrigation for Planting Strips with Soil Cells	150a 150b 151 152
200 Sewer-Drainage App Maintenance holes	Type 204a Maintenance Hole Type 204.5a Maintenance Hole Type 205a Maintenance Hole Type 205a Maintenance Hole Type 205b Maintenance Hole Type 206a Maintenance Hole Type 206a Maintenance Hole Type 206b Maintenance Hole Type 207a Maintenance Hole Type 207b Maintenance Hole Type 208a Maintenance Hole Type 208b Maintenance Hole Type 208b Maintenance Hole Type 209a Maintenance Hole Type 209b Maintenance Hole Type 210a Maintenance Hole Type 211a Maintenance Hole Type 211b Maintenance Hole Type 212a Maintenance Hole Type 212b Maintenance Hole Flexible Joint for VCP Connection Rebuild Existing Brick Maintenance Hole	204a 204b 204.5a 204.5b 205a 205b 206a 206b 207a 207b 208a 208b 209a 210a 210b 211a 211b 212a 212b 215 220
Materials	2'-0" Diameter Frame & Cover Sewer Replacement Cover Maintenance Hole Ladder Step & Handhold Maintenance Hole Ladder Step & Handhold Outside Drop Connection Inside Drop Connection 6" or 8" Vertical Connection to Concrete or Clay 6" or 8" Vertical Connection to Ductile Iron	230 231 232a 232b 233a 233b 234a 234b
Catch Basins	Type 240 Catch Basin Type 241 Catch Basin	240 241a

	Type 241 Catch Basin Installations Type 242 Catch Basin Precast Catch Basin Top Slab Precast Catch Basin Extension Risers	241b 242 243a 243b
Inlets	Type 250 Inlet Type 252 Inlet Inlet/Catch Basin Location & Installation Catch Basin & Inlet Installation Catch Basin & Inlet with 563b Hood Typical Catch Basin Connection Type 262 Inlet Frame Type 263 Inlet Frame Type 263 Alternative Inlet Hood Inlet Frame & Grate Vaned Grate Vaned Grates Type 266 Replacement Vaned Grate Outlet Trap Extension for Inlet Beehive Grate for Bioretention	250 252 260a 260b 260c 261 262 263a 263b 264 265a 265b 266 267 268 269
Flow Control	Flow Control Structure with Detention Pipe CMP Detention Pipe Private System Only CMP Detention Structure End Plate Details Types A & B CMP Detention Structure End Plate Details Types C CMP Detention Structure End Plate Dimensions Flow Control Device Assembly PVC Shear Gate for Use in ROW Only Type 277 Junction Box & Installation Vertical Clean Out/Corrugated Metal Pipe	270 271a 271b 271c 271d 272a 272b 277 278
Pipe Installation	Tee Installation Corrugated Metal Pipe 8" Clean Out Bioretention Under Drain Clean-out & Observation Port Corrugated Metal Pipe Coupling Bands Corrugated Metal Pipe Coupling Bands Side Sewer Installation Typical Trench Detail for Sewer & Storm Drain Pipe Bedding For Sewer/Storm Drain	279 280 281 282a 282b 283 284 285
Clearance Plans	Spacing & Clearances for Sewer/Storm Drain & Water Spacing & Clearances for Sewer & Water	286a 286b
Drains	Bridge Drain PVC Subsurface Drain Pipe	290 291
	Infiltrating Bioretention with Sloped Sides Infiltrating Bioretention with Sloped Sides& Under	292
	Drain Non-Infiltrating Bioretention with Sloped Sides & Under Drain Vegetated Conveyance Swale	293a 293b 294

Sloped Sides

Drain Curb Cut Type 1

Drain Curb Cut Type 2

Typical Drain Curb Cut for Bioretention with

295a

295b

295c

400

401

	Drain Curb Cut Type 3	295d
	Presettling Zone	299
300 Watermain Appu	ırtenances	
Pipe Connections	Connections to Existing Watermains	300a
, -	Connections to Existing Watermains	300b
	Connections to Existing Watermains	300c
	Water Service Relocation for Up To 2" Service Pipe	301
	Watermain Setback Requirements for C.I. Lead	
	Joint & D.I. Slip Joint Pipe	302
Hydrants	Type 310a Hydrant Setting Detail	310a
	Type 310b Hydrant Setting Detail	310b
	Type 311 Hydrant Setting Detail	311a
	Type 311 Hydrant Setting Detail	311b
	Fire Hydrant Marker Layout	312
	Wall Requirements for Hydrants	313
	Fire hydrant Locations & Clearances	314a
	Clearances for Typical Water Service Vaults	314b
Valves	Cast Iron Valve Box & Operating Nut Extension	315a
	Cast Iron Valve Box & Operating Nut Extension	315b
	Water Service Connection to New Water Main	316
	Air Release Air Vacuum Valve	320
Concrete Blocking	Watermain Thrust Blocking Vertical Fittings	330a
	Watermain Thrust Blocking Vertical Fittings	330b
	Watermain Thrust Blocking Horizontal Fittings	331a
	Watermain Thrust Blocking Horizontal Fittings	331b
Blow Off	2" Blow Off Type A Non Traffic Installation	340a
	2" Blow Off Detail Type B Traffic Installation	340b
Pipe Bedding	Watermain Trench and Bedding	350
, ,	Rebuild Existing Brick Water Valve Chamber	359
Miscellaneous	Watermain Electrolysis Test Station	360
	Type 361a Valve Chamber Frame & Cover	361a
	Type 361b Valve Chamber Frame & Cover	361b
	Type 361c Valve Chamber Frame & Cover	361c
	Type 361d Valve Chamber Frame & Cover	361d
	Joint Bonding for DIP Watermains &	
	Joint Bonding Detail	362
	Electrolysis Test Station Wire Installation Details	363
	Sacrificial Anode Bonded to Pipe	364
	Sacrificial Anode Installation Details	365
400 Street Paving &	Appurtenances	
D	Half Oartham Onedham	400

Half Section, Grading

Residential Pavement Sections

Paving

	Commercial and Arterial Pavement Sections	402
	Roadway Cement Concrete Alley Pavements	403
	Pavement Patching	404a
	Pavement Patching	404b
	Pavement Patching Zone of Influence	404c
		4040 405a
	Roadway Concrete Pavement Repair	
	Pavement Repair Dowel Bar & Tie Bar Details	405b
	Roadway Concrete Pavement Joints	405c
	Through Joints and Optional Keyways	
	for Cement Concrete Roadway	405d
	Frame & Cover Cement Concrete Reinforcement	
	Detail	406
Overland	T 440 O	440
Curbs	Type 410 Curb	410
	Curb Joints & Dowels	411
	Extruded Curb	412
	3' Precast Traffic Curb (Dual Sloped)	413a
	8' Block and Radial Traffic Curb	413b
	Traffic Circle Details	415
Sidewalks	Concrete Sidewalk Details	420
	Sidewalk with Monolithic Curb	421
	Curb Ramp Details	422a
	Curb Ramp Details	422b
	Curb Ramp Details	422c
	Curb Ramp Details	422d
	Curb Ramp Details	422e
	·	422f
	Curb Ramp Details	
	Curb Ramp Details	422g
	Curb Ramp Details	422h
	Tactile Warning Surface Indicators	422i
	Curb Ramp Details	422k
	Curb Ramp Sections	422l
	Evnandable Tree Dit Detail	4246
	Expandable Tree Pit Detail	424a
	Tree Pit Detail	424b
	Alternative Walkways	425
Driveways	Type 430a Driveway	430a
Billowayo	Type 430b Driveway	430b
	Cement Concrete Driveway Placed with Cement	4000
	Concrete Sidewalk	431
	Multi-Purpose Trail at Street Crossing	432a
	Multi-Purpose Trail at Street Crossing	432b
	Waste Access Ramp	433
	Speed Hump	436a
	Speed Cushion	436b
Stainway Stans	Coment Concrete Stainway 9 Handrail	4400
Stairway, Steps	Cement Concrete Stairway & Handrail	440a
	Cement Concrete Stairway & Handrail	440b
	Cement Concrete Stairway & Bike Runnel	440c
	Cement Concrete Stairway & Single Bike Runnel	440d
	Cement Concrete Steps	441
	Steel Pipe Handrail	442
	Pedestrian Railing	443
_		
Fence	Chain Link Fence	450a

	Chain Link Fence Chain Link Gates	450b 450c
Miscellaneous	Temporary Pedestrian Walkway Temporary Pedestrian Curb Ramp Ecology Block, Concrete Fixed & Removable Wood Bollard Removable Steel Bollard Fixed Steel Bollard	456a 456b 460 463 464 465
500 Signalization-Lighting	ng	
Signal Controller	Signal Controller Cabinet & Foundation Signal Controller Foundation Conduit Layout Service Cabinet Foundation Detail Joint Signal Controller/Service Cabinet Foundation Detail	500a 500b 501a 501b
Vehicular Signal	Vehicular Signal Mounting Vehicular Signal Mounting Signal Head Bracket Assembly	510a 510b 511
Pedestrian Signal	Pedestrian Signal Clamshell Mounting Pedestrian Pushbutton Post & Foundation Accessible Pedestrian signal (APS) PED	520 521
	Pushbutton Assembly Bicycle Pushbutton Assembly Pedestal & Foundation Rectangular Rapid Flashing Beacon	522a 522b 524 525
Loop Detectors	Detector Loop Lead-In Detector Loop Details Detector Loop Wire & Signal Cable Splice	530a 530b 530c
Pole Foundations	Traffic Signal Pole Foundation Detail Strain Pole Foundation	541a
	Schedule / Notes (Type T, V, X & Z) Street Light Pole Foundations Pedestrian Street Light Pole Foundations	541b 543a 543b
Handholes	Handholes Handholes Polymer Concrete Handholes Polymer Concrete Handholes	550a 550b 550c 550d
Poles	Steel Mast Arm Pole Steel Mast Arm Pole Foundation Schedule & Detail (w/o METRO Trolley Loads) Miscellaneous Steel Pole Details	562a 562b 563a
	Miscellaneous Steel Pole Details Terminal Cabinet Pole Mounting Strain Pole Details (Type V, X & Z Poles) Strain Pole Details (Type V, X & Z Poles) Type T Strain Pole Details Traffic Signal Only Type T Strain Pole Details Traffic Signal Only Steel Street Light Pole with Bracket Arm	563b 564 566a 566b 567a 567b 572

	for Municipal Construction	
Conduit Risers	Traffic Conduit Riser	580
600 Signs		
Overhead	Span Wire Installation	601a
	Overhead Signs Span Wire Mounted	601b
	Sign Installation (Non-Spanwire Mounting)	601c
Pole Mounted	Standard Sign Installation Stool Polos	610
-ole Mounted	Standard Sign Installation Steel Poles SNS Bracket for Steel Poles	615
	Traffic Sign Mounting on Metal Poles	616
Post Mounted	Stop and Yield Sign Post and Anchor	
	Installation	620
	Warning and Regulatory Sign Post	621a
	Warning and Regulatory Sign Post	
	Anchor Installations	621b
	Street Name Sign Installation	622
	Street Name Sign Pedestal Installation	623
	Post Cap	624
	Traffic Sign Posts	625
		626
	Object Marker Installation in Traffic Circle	
	Metro Bus Zone Sign Installation	630
	Pedestrian Wayfinding Sign	631
700 Pavement Markings		
Traffic Buttons/Lane Markers	Traffic Buttons and Lane Markers	700
Channelization	Typical Left Turn Channelization and	
Sharmon Educin	Legend Placement	710a
		1 TOA
	Typical Lane Drop Channelization and	710h
	Legend Placement	710b
	Typical Intersection Guideline Channelization	710c
	Typical White Barrier Area Channelization	711
	Typical Crosswalk & Stop Line Installation Details	712
	Curb Marking Details	713
	Typical Angled Parking Stall Channelization	714
	Trail Obstruction Channelization	715
	Typical Curbside Red Bus Lane Layout	717
_eaends / Symbols	Mandatory Movement Arrows	720
egends / Symbols	Mandatory Movement Arrows Optional Movement Arrows	720 721
egends / Symbols	Optional Movement Arrows	721
egends / Symbols	Optional Movement Arrows Optional Movement Arrows with Oblique Arrows	721 722
egends / Symbols	Optional Movement Arrows Optional Movement Arrows with Oblique Arrows Merge Arrows	721 722 723
egends / Symbols	Optional Movement Arrows Optional Movement Arrows with Oblique Arrows Merge Arrows Speed Hump & Speed Cushion Symbol	721 722 723 728
egends / Symbols	Optional Movement Arrows Optional Movement Arrows with Oblique Arrows Merge Arrows Speed Hump & Speed Cushion Symbol Yield Line Layout & Yield Line Triangle Symbols	721 722 723 728 729
egends / Symbols	Optional Movement Arrows Optional Movement Arrows with Oblique Arrows Merge Arrows Speed Hump & Speed Cushion Symbol Yield Line Layout & Yield Line Triangle Symbols Pavement Markings Legends	721 722 723 728 729 730
egends / Symbols	Optional Movement Arrows Optional Movement Arrows with Oblique Arrows Merge Arrows Speed Hump & Speed Cushion Symbol Yield Line Layout & Yield Line Triangle Symbols Pavement Markings Legends International Symbol of Accessibility	721 722 723 728 729 730 740
egends / Symbols	Optional Movement Arrows Optional Movement Arrows with Oblique Arrows Merge Arrows Speed Hump & Speed Cushion Symbol Yield Line Layout & Yield Line Triangle Symbols Pavement Markings Legends International Symbol of Accessibility Pedestrian Symbol	721 722 723 728 729 730 740 741
egends / Symbols	Optional Movement Arrows Optional Movement Arrows with Oblique Arrows Merge Arrows Speed Hump & Speed Cushion Symbol Yield Line Layout & Yield Line Triangle Symbols Pavement Markings Legends International Symbol of Accessibility Pedestrian Symbol Red Bus Lane Markings	721 722 723 728 729 730 740 741 750
egends / Symbols	Optional Movement Arrows Optional Movement Arrows with Oblique Arrows Merge Arrows Speed Hump & Speed Cushion Symbol Yield Line Layout & Yield Line Triangle Symbols Pavement Markings Legends International Symbol of Accessibility Pedestrian Symbol Red Bus Lane Markings Helmeted Bicyclist Symbol with Arrow	721 722 723 728 729 730 740 741
egends / Symbols	Optional Movement Arrows Optional Movement Arrows with Oblique Arrows Merge Arrows Speed Hump & Speed Cushion Symbol Yield Line Layout & Yield Line Triangle Symbols Pavement Markings Legends International Symbol of Accessibility Pedestrian Symbol Red Bus Lane Markings	721 722 723 728 729 730 740 741 750
egends / Symbols	Optional Movement Arrows Optional Movement Arrows with Oblique Arrows Merge Arrows Speed Hump & Speed Cushion Symbol Yield Line Layout & Yield Line Triangle Symbols Pavement Markings Legends International Symbol of Accessibility Pedestrian Symbol Red Bus Lane Markings Helmeted Bicyclist Symbol with Arrow	721 722 723 728 729 730 740 741 750 770
egends / Symbols	Optional Movement Arrows Optional Movement Arrows with Oblique Arrows Merge Arrows Speed Hump & Speed Cushion Symbol Yield Line Layout & Yield Line Triangle Symbols Pavement Markings Legends International Symbol of Accessibility Pedestrian Symbol Red Bus Lane Markings Helmeted Bicyclist Symbol with Arrow Sharrow & Bike Symbol Bicycle Detector Symbol	721 722 723 728 729 730 740 741 750 770
egends / Symbols	Optional Movement Arrows Optional Movement Arrows with Oblique Arrows Merge Arrows Speed Hump & Speed Cushion Symbol Yield Line Layout & Yield Line Triangle Symbols Pavement Markings Legends International Symbol of Accessibility Pedestrian Symbol Red Bus Lane Markings Helmeted Bicyclist Symbol with Arrow Sharrow & Bike Symbol Bicycle Detector Symbol Bike DOT Symbol with Arrow	721 722 723 728 729 730 740 741 750 770 771 772 773
egends / Symbols	Optional Movement Arrows Optional Movement Arrows with Oblique Arrows Merge Arrows Speed Hump & Speed Cushion Symbol Yield Line Layout & Yield Line Triangle Symbols Pavement Markings Legends International Symbol of Accessibility Pedestrian Symbol Red Bus Lane Markings Helmeted Bicyclist Symbol with Arrow Sharrow & Bike Symbol Bicycle Detector Symbol Bike DOT Symbol with Arrow Greenway Markings	721 722 723 728 729 730 740 741 750 770 771 772 773 774
egends / Symbols	Optional Movement Arrows Optional Movement Arrows with Oblique Arrows Merge Arrows Speed Hump & Speed Cushion Symbol Yield Line Layout & Yield Line Triangle Symbols Pavement Markings Legends International Symbol of Accessibility Pedestrian Symbol Red Bus Lane Markings Helmeted Bicyclist Symbol with Arrow Sharrow & Bike Symbol Bicycle Detector Symbol Bike DOT Symbol with Arrow	721 722 723 728 729 730 740 741 750 770 771 772 773

800 Structures		
Walls	Support Wall	800
	Curb Wall	801

REV DATE: DEC 2010

Vertical Datums within the City of Seattle:

The National Geodetic Survey (NGS) Benchmark 944 7130 TIDAL 7 PID SY0289 is a disk set 3.0 feet above the concrete sidewalk in the SW granite cornerstone of the National Building located on the NE corner of the intersection of the Western Avenue and Madison Street, Seattle, Washington.

The following elevations are values for that benchmark in different datums.

NAVD 88 = 19.26 feet NGVD 29 = 15.67 feet King Co & Metro = 115.67 Obsolete COS Datum = 9.54 feet USACOE = 22.51 feet MLLW = 21.59 feet

NAVD88 = The North American Vertical Datum of 1988 (Official City of Seattle Datum per Ordinance #121291 of October 9, 2003)

NGVD 29 = The National Geodetic Vertical Datum of 1929

King Co & Metro = Add 100 feet to NGVD 29

Obsolete COS = The Old City of Seattle Elevation. Plans, profiles and records prior to 2004 use this datum. Add 9.7 feet to this datum to get to NAVD88.

USACOE = US Army Corps of Engineers Lake Washington & Lake Union Datum

MLLW = Mean Lower Low Water Datum (TIDAL EPOCH 1983 TO 2001)

NOTES


- 1. Tidal elevations vary according to tidal observations in 18 year epochs.
- The Old (Obsolete) City of Seattle Datum varies between 9.1 and 9.9 feet below NAVD88 depending on the location in the City. The difference between these two datums must be ascertained from field observations in each specific area. Add approximately 9.7 feet to the old COS Datum to get to the NAVD elevation.

REF STD SPEC SEC 1-07.16(1)A, 1-07.28



NOT TO SCALE

ELEVATIONS & DATUMS



AASHTO	American Association of State Highway & Transportation Officials
ABAN	Abandon(ed)
ABW	Asphalt Bike Way
ACV	Automatic Control Valve
ACP	Asphalt Concrete Pavement
ADA	Americans with Disabilities Act
ADJ	Adjust
AHD	Ahead
AIC	Aerial Interconnect Cable
AL	Aluminum
AP	Angle Point
APP	Approved
APPROX	Approximate
APS	Accessible Pedestrian Signal
APWA	American Public Works Association
ASPH	Asphalt
ASTM	American Society for Testing & Materials
ATB	Asphalt Treated Base
AV	Air Valve
AVB	Automatic Vacuum Breaker
AVE	Avenue
AVG	Average
AW	Asphalt Walk
AWG	American Wire Gage
AWWA	American Water Works Assoc.
BAT	Backflow Assembly Tester
B&B	Ball & Burlap
ВС	Bolt Circle, Back of Curb
BF	Bottom Face
BFV	Butterfly Valve
ВК	Back

BLDG	Building
BLK	Block
BLKG	Blocking
BLKHD	Bulkhead
BLRD	Bollard
BLVD	Boulevard
ВМ	Bench Mark
во	Blow Off
вос	Beginning of Curb
BPD	Backflow Prevention Device
BR	Bare Root, Brick
BRG	Bearing
BRKN	Broken
BSMT	Basement
BTW	Between
BV	Ball valve
BVC	Beginning of Vertical Curve
C&G	Curb & Gutter
CAL	Caliper
CALC	Calculation
СВ	Cable, Catch Basin
CBW	Concrete Bike Way
C-C	Center to Center
СС	Concrete Culvert
CD	Conduit
CDF	Controlled Density Fill
CEM	Cement
CF	Cubic Feet
СН	Chamber
CIP	Cast Iron Pipe
CL	Center Line or Class
Ę.	Center Line
CLF	Chain Link Fence

REF STD SPEC SEC 1-01.2



NOT TO SCALE

CLR	Clearance
CMP	Corrugated Metal Pipe
СО	Clean Out
СОМР	Compression
CONC	Concrete
COND	Condition
CONN	Connect/Connection
CONSTR	Construction
CONT	Continuous
CORP	Corporation
cos	City of Seattle
CPEP	Corrugated Polyethylene Pipe
CR	Cross, Curb Radius
CSB	Chief Seattle Base
CSECP	Construction Stormwater & Erosion Control Plan
CULV	Culvert
CW	Concrete Walk
CY	Cubic Yard
DB	Direct Burial Cable
DC	Direct Current
DCVA	Double Check Valve Assembly
DEPT	Department
DGV	District Gate Valve
DIA Ø	Diameter
DIP or DI	Ductile Iron Pipe
DIPRA	Ductile Iron Pipe Research Assoc.
DR	Drive
DS	Downspout
DWG	Drawing
DWY	Driveway
Е	East
EA	Each
ECB	Electrical Cable

ECC Eccentric ECD Electrical Conduit ED Electrical Duct EL/ELEV Elevation ELEC Electric/Electrical EMH Electrical Maintenance Ho ENCL Enclosure ENGR Engineer EOC End of Curb EQ Equal ESAL Equivalent Single Axle Lo ESMT Easement EV Electrical Vault EVC End of Vertical Curb EVD Emergency Vehicle Detector EW Each Way EX Existing EXP Expansion FACB Fire Alarm Cable FAHH Fire Alarm Handhole FC Face of Curb FCS Flow Control Structure f'c Specified compressive st concrete FDN Foundation	
ED Electrical Duct EL/ELEV Elevation ELEC Electric/Electrical EMH Electrical Maintenance Ho ENCL Enclosure ENGR Engineer EOC End of Curb EQ Equal ESAL Equivalent Single Axle Lo ESMT Easement EV Electrical Vault EVC End of Vertical Curb EVD Emergency Vehicle Detect EVPD Emergency Vehicle Preent Detector EW Each Way EX Existing EXP Expansion FACB Fire Alarm Cable FAHH Fire Alarm Handhole FC Face of Curb FCS Flow Control Structure f'c Specified compressive standing to the control of the contr	
EL/ELEV Elevation ELEC Electric/Electrical EMH Electrical Maintenance Ho ENCL Enclosure ENGR Engineer EOC End of Curb EQ Equal ESAL Equivalent Single Axle Lo ESMT Easement EV Electrical Vault EVC End of Vertical Curb EVD Emergency Vehicle Detector EW Each Way EX Existing EXP Expansion FACB Fire Alarm Cable FAHH Fire Alarm Handhole FC Face of Curb FCS Flow Control Structure f'c Specified compressive st concrete FDN Foundation	
ELEC Electric/Electrical EMH Electrical Maintenance Ho ENCL Enclosure ENGR Engineer EOC End of Curb EQ Equal ESAL Equivalent Single Axle Lo ESMT Easement EV Electrical Vault EVC End of Vertical Curb EVD Emergency Vehicle Detector EVPD Emergency Vehicle Preent Detector EW Each Way EX Existing EXP Expansion FACB Fire Alarm Cable FAHH Fire Alarm Handhole FC Face of Curb FCS Flow Control Structure f'c Specified compressive stance of concrete FDN Foundation	
EMH Electrical Maintenance Ho ENCL Enclosure ENGR Engineer EOC End of Curb EQ Equal ESAL Equivalent Single Axle Lo ESMT Easement EV Electrical Vault EVC End of Vertical Curb EVD Emergency Vehicle Detect EVPD Emergency Vehicle Preent Detector EW Each Way EX Existing EXP Expansion FACB Fire Alarm Cable FAHH Fire Alarm Handhole FC Face of Curb FCS Flow Control Structure f'c Specified compressive st concrete FDN Foundation	
ENCL Enclosure ENGR Engineer EOC End of Curb EQ Equal ESAL Equivalent Single Axle Lo ESMT Easement EV Electrical Vault EVC End of Vertical Curb EVD Emergency Vehicle Detect EVPD Emergency Vehicle Preend Detector EW Each Way EX Existing EXP Expansion FACB Fire Alarm Cable FAHH Fire Alarm Handhole FC Face of Curb FCS Flow Control Structure f'c Specified compressive standing concrete FDN Foundation	
ENGR Engineer EOC End of Curb EQ Equal ESAL Equivalent Single Axle Lo ESMT Easement EV Electrical Vault EVC End of Vertical Curb EVD Emergency Vehicle Detector EVPD Emergency Vehicle Preend Detector EW Each Way EX Existing EXP Expansion FACB Fire Alarm Cable FAHH Fire Alarm Handhole FC Face of Curb FCS Flow Control Structure f'c Specified compressive state concrete FDN Foundation	ole
EOC End of Curb EQ Equal ESAL Equivalent Single Axle Lo ESMT Easement EV Electrical Vault EVC End of Vertical Curb EVD Emergency Vehicle Detector EVPD Emergency Vehicle Preent EVER Each Way EX Existing EXP Expansion FACB Fire Alarm Cable FAHH Fire Alarm Handhole FC Face of Curb FCS Flow Control Structure f'c Specified compressive st concrete FDN Foundation	
EQ Equal ESAL Equivalent Single Axle Lo ESMT Easement EV Electrical Vault EVC End of Vertical Curb EVD Emergency Vehicle Detector EVPD Emergency Vehicle Preend Detector EW Each Way EX Existing EXP Expansion FACB Fire Alarm Cable FAHH Fire Alarm Handhole FC Face of Curb FCS Flow Control Structure f'c Specified compressive state concrete FDN Foundation	
ESAL Equivalent Single Axle Lo ESMT Easement EV Electrical Vault EVC End of Vertical Curb EVD Emergency Vehicle Detector EW Each Way EX Existing EXP Expansion FACB Fire Alarm Cable FAHH Fire Alarm Handhole FC Face of Curb FCS Flow Control Structure f'c Specified compressive st concrete FDN Foundation	
ESMT Easement EV Electrical Vault EVC End of Vertical Curb EVD Emergency Vehicle Detect EVPD Emergency Vehicle Preent Detector EW Each Way EX Existing EXP Expansion FACB Fire Alarm Cable FAHH Fire Alarm Handhole FC Face of Curb FCS Flow Control Structure f'c Specified compressive state concrete FDN Foundation	
EV Electrical Vault EVC End of Vertical Curb EVD Emergency Vehicle Detector EVPD Emergency Vehicle Preend Detector EW Each Way EX Existing EXP Expansion FACB Fire Alarm Cable FAHH Fire Alarm Handhole FC Face of Curb FCS Flow Control Structure f'c Specified compressive state concrete FDN Foundation	ads
EVC End of Vertical Curb EVD Emergency Vehicle Detect EVPD Emergency Vehicle Preend Detector EW Each Way EX Existing EXP Expansion FACB Fire Alarm Cable FAHH Fire Alarm Handhole FC Face of Curb FCS Flow Control Structure f'c Specified compressive statement of the concrete concrete FDN Foundation	
EVD Emergency Vehicle Detect EVPD Emergency Vehicle Preend Detector EW Each Way EX Existing EXP Expansion FACB Fire Alarm Cable FAHH Fire Alarm Handhole FC Face of Curb FCS Flow Control Structure f'c Specified compressive state concrete FDN Foundation	
EVPD Emergency Vehicle Preend Detector EW Each Way EX Existing EXP Expansion FACB Fire Alarm Cable FAHH Fire Alarm Handhole FC Face of Curb FCS Flow Control Structure f'c Specified compressive state concrete FDN Foundation	
EVPD Detector EW Each Way EX Existing EXP Expansion FACB Fire Alarm Cable FAHH Fire Alarm Handhole FC Face of Curb FCS Flow Control Structure f'c Specified compressive st concrete FDN Foundation	tor
EX Existing EXP Expansion FACB Fire Alarm Cable FAHH Fire Alarm Handhole FC Face of Curb FCS Flow Control Structure f'c Specified compressive st concrete FDN Foundation	nption
EXP Expansion FACB Fire Alarm Cable FAHH Fire Alarm Handhole FC Face of Curb FCS Flow Control Structure f'c Specified compressive st concrete FDN Foundation	
FACB Fire Alarm Cable FAHH Fire Alarm Handhole FC Face of Curb FCS Flow Control Structure f'c Specified compressive st concrete FDN Foundation	
FAHH Fire Alarm Handhole FC Face of Curb FCS Flow Control Structure f'c Specified compressive st concrete FDN Foundation	
FC Face of Curb FCS Flow Control Structure f'c Specified compressive st concrete FDN Foundation	
FCS Flow Control Structure f'c Specified compressive st concrete FDN Foundation	
f'c Specified compressive st concrete FDN Foundation	
FDN Foundation	
	rength of
For Food Ciniohad Flags	
FF Far Face, Finished Floor	
FG Finished Grade	
FHWA Federal Highway Administ	ration
FIG Figure	
FIPT Female Iron Pipe Thread	
FL Flow Line	

REF STD SPEC SEC 1-01.2



NOT TO SCALE

FLG	Flange
FLR	Floor
FLT	Flat Bar
FM	Force Main
FO or FOC	Fiber Optics
FS	Far Side
FT	Feet
FTB	Fluidized Thermal Backfill
FTG	Footing
G	Gas
G REG	Gas Regulator
GA	Gauge
GAL	Gallon
GALV	Galvanize/Galvanized
GAS V	Gas Valve
GFCI	Ground Fault Circuit Interrupter
GIP	Galvanized Iron Pipe
GM	Gas Meter
GND	Ground
GP	Guy Pole
GPM	Gallons Per Minute
GR	Grade
GRHH	Ground Rod Handhole
GS	Gas Service
GSI	Green Stormwater Infrastructure
GSP	Galvanized Steel Pipe
GV	Gate Valve
GVC	Gate Valve Chamber
GVL	Gravel
НВ	Horizontal Bend
HBR	Hose Bib Riser
HDPE	High Density Polyethylene
HEX	Hexagon/Hexagonal

HGL	Hydraulic Grade Line	
НН	Handhole	
НІ	High	
НМА	Hot Mix Asphalt	
HORIZ	Horizontal	
HPG	High Pressure Gas	
HPS	High Pressure Sodium	
HR	Hour	
HSE	House	
HT	Height	
HYD	Hydrant	
ID	Inside Diameter/Dimension	
I/D	Incentive/Disincentive	
IE	Invert Elevation	
IF	Inside Face	
IN	Inch(es)	
INL	Inlet	
INT	Intersection	
INV	Invert (Line)	
IP(S)	Iron Pipe (Size)	
IRC	Irrigation Controller	
IRRG	Irrigation	
IRRGV	Irrigation Valve	
ISO	Isolation Coupling	
JB	Junction Box	
JT	Joint	
К	Kips (1000 lbs)	
KSI	Kips Per Square Inch	
KV	Kilovolt	
LAL	Limited Access Line	
LB, LBS	Pound, Pounds	
LED	Light Emitting Diode	
LF	Linear/Lineal Feet	

REF STD SPEC SEC 1-01.2



NOT TO SCALE

LID	Local Improvement District		
LIT	Large Inlet Top (Catch Basin)		
LOC	Locate/Location		
LONGIT	Longitudinal		
LP	Light Pole		
LS	Lump Sum		
LSCAPE	Landscape, Landscaping		
LT	Left		
LTG	Lighting		
LUM	Luminaire		
MA	Mast Arm		
MATL	Material		
MAX	Maximum		
МВ	Mailbox		
MCV	Manual Control Valve		
MDV	Manual Drain Valve		
мн	Maintenance Hole		
MIC	Monument in Case		
MIN	Minimum		
MIPT	Male Iron Pipe Thread		
MISC	Miscellaneous		
MJ	Mechanical Joint		
ML M॒	Monument Line		
MNRL AGG	Mineral Aggregate		
MOD	Modify/Modified		
MON	Monument		
MUTCD	Manual on Uniform Traffic Control Devices		
MW	Monitor Well		
N	North		
NAD	North American Datum		
NAVD	North American Vertical Datum		
	· ·		

NEMA	National Electrical Manufacturers Association		
NF	Near Face		
NGVD	National Geodetic Vertical Datum		
NIC	Not in Contract		
NO	Number		
NOM	Nominal		
NS	Near Side		
NTS	Not To Scale		
ОС	On Center		
OD	Outside Diameter/Dimension		
OF	Outside Face		
ОН	Overhead		
PAV	Pavement		
PC	Point of Curvature		
PCC	Point of Compound Curve		
PCW	Pervious Concrete Walk		
PDP	Perforated Drain Pipe		
PE	Plain End, Polyethylene		
PED	Pedestrian		
PG	Performance Grade		
PH	Phase		
PI	Point of Intersection		
PL	Plate, Place, Polyethylene		
PL	Property Line		
POC	Point on Curve		
PP	Power Pole, Polypropylene		
PPB	Pedestrian Push Button		
PR	Pair		
PRC	Point of Reverse Curve		
PROP	Proposed		
PRKG	Parking		
PRV	Pressure Reducing Valve		
PS	Pipe Sewer Combined		

REF STD SPEC SEC 1-01.2



NOT TO SCALE

PSD	Pipe Storm Drain		
PSDD	Pipe Storm Drain Detention		
PSI	Pounds per Square Inch		
PSIA	Pounds per Square Inch Absolute		
PSIG	Pounds per Square Inch Gauge		
PSS	Pipe Sewer Sanitary		
PT	Point of Tangency		
PVB	Pressure Vacuum Breaker		
PVC	Polyvinyl Chloride		
PVT	Private		
QTY	Quantity		
R	Radius		
R&R	Remove & Replace		
R/W	Right of Way		
RCP	Reinforced Concrete Pipe		
RD	Roof Drain		
RDWY	Roadway		
RECONN	Reconnect		
RED	Reducer		
REF	Refer/Reference		
REINF	Reinforce/Reinforcement		
RELOC	Relocate		
REM	Remove		
REPL	Replace		
REQD	Required		
RET	Retire/Retired		
RET WALL	Retaining Wall		
RF	Rock Facing		
RGS	Rigid Galvanized Steel		
RIT	Round Inlet Top		
RJ	Restrained Joint		
RLWY	Railway		
RP	Rock Pocket		

RPBA	Reduced Pressure Backflow Assembly	
RR	Railroad	
RRFB	Rectangular Rapid Flashing Beacon	
RS	Rigid Steel	
RT	Right	
RWS	Root Watering System	
S	South	
SB	Sandbox	
SCH	Schedule	
SCL	Seattle City Light	
SDCI	Seattle Department of Construction & Inspections	
SDS	Street Designation Sign	
SD	Service Drain	
SDOT	Seattle Department of Transportation	
SEC	Section	
SF	Square Feet	
SHLD	Shield	
SHT	Sheet	
SL	Sleeve, Street Light	
§.	Survey Line	
SLHH	Street Light Handhole	
SNS	Street Name Sign	
SP	Strain Pole	
SPCS	Spaces	
SPEC	Specifications	
SPR	Seattle Parks & Recreation	
SPU	Seattle Public Utilities	
SQ	Square	
SS	Stainless Steel, Side Sewer-Combined	
SSD	Sub-Surface Drain	
SSS	Side Sewer-Sanitary	
SSTONE	Sandstone	
ST	Street	

REF STD SPEC SEC 1-01.2



NOT TO SCALE

STA Station STD Standard STL Steel STL P Steel Pipe STM LOG Steam Log STRUCT Structure/Structural SVC Service SW Sidewalk SY Square Yard SYS System T Tee TB Test Boring TC Traffic Control TCB Telephone Cable TCD Telephone Conduit TCHH Traffic Control Handhole TD Telephone Enclosure Box TEL Telephone TEMP Temporary TF Top Face TH Test Hole THH Test Hole THH Telephone Manhole TJO Transfer of Jurisdiction Ordinance TMH Telephone Manhole TMT Treatment TN Ton TOC Top of Curb TR Traffic TRCB Traffic Signal Conduit TRSCC Traffic Signal Controller Cabinet TRSCC Television Cable		T	
STL P Steel Pipe STM LOG Steam Log STRUCT Structure/Structural SVC Service SW Sidewalk SY Square Yard SYS System T Tee TB Test Boring TC Traffic Control TCB Telephone Cable TCD Telephone Conduit TCHH Traffic Control Handhole TD Telephone Duct TEB Telephone Enclosure Box TEL Telephone TEMP Temporary TF Top Face TH Test Hole THH Test Hole THH Telephone Manhole TJO Transfer of Jurisdiction Ordinance TMH Telephone Manhole TMT Treatment TN Ton TOC Top of Curb TR Traffic TRCB Traffic Signal Cable TRCD Traffic Signal Conduit TRSCC Traffic Signal Controller Cabinet	STA	Station	
STL P Steel Pipe STM LOG Steam Log STRUCT Structure/Structural SVC Service SW Sidewalk SY Square Yard SYS System T Tee TB Test Boring TC Traffic Control TCB Telephone Cable TCD Telephone Conduit TCHH Traffic Control Handhole TD Telephone Duct TEB Telephone Enclosure Box TEL Telephone TEMP Temporary TF Top Face TH Test Hole THH Telephone Handhole TJO Transfer of Jurisdiction Ordinance TMH Telephone Manhole TMT Treatment TN Ton TOC Top of Curb TR Traffic TRCB Traffic Signal Cable TRCD Traffic Signal Controller Cabinet	STD	Standard	
STM LOG Steam Log STRUCT Structure/Structural SVC Service SW Sidewalk SY Square Yard SYS System T Tee TB Test Boring TC Traffic Control TCB Telephone Cable TCD Telephone Conduit TCHH Traffic Control Handhole TD Telephone Duct TEB Telephone TEL Telephone TEMP Temporary TF Top Face TH Test Hole THH Telephone Handhole TJO Transfer of Jurisdiction Ordinance TMH Telephone Manhole TMT Treatment TN Ton TOC Top of Curb TR Traffic TRCB Traffic Signal Cable TRCD Traffic Signal Conduit TRSCC Traffic Signal Controller Cabinet	STL	Steel	
STRUCT Structure/Structural SVC Service SW Sidewalk SY Square Yard SYS System T Tee TB Test Boring TC Traffic Control TCB Telephone Cable TCD Telephone Conduit TCHH Traffic Control Handhole TD Telephone Duct TEB Telephone Enclosure Box TEL Telephone TEMP Temporary TF Top Face TH Test Hole THH Test Hole THH Telephone Manhole TMH Telephone Manhole TMT Treatment TN Ton TOC Top of Curb TRCB Traffic Signal Conduit TRSCC Traffic Signal Controller Cabinet	STL P	Steel Pipe	
SVC Service SW Sidewalk SY Square Yard SYS System T Tee TB Test Boring TC Traffic Control TCB Telephone Cable TCD Telephone Conduit TCHH Traffic Control Handhole TD Telephone Duct TEB Telephone Enclosure Box TEL Telephone TEMP Temporary TF Top Face TH Test Hole THH Telephone Handhole TJO Transfer of Jurisdiction Ordinance TMH Telephone Manhole TMT Treatment TN Ton TOC Top of Curb TRCB Traffic Signal Conduit TRSCC Traffic Signal Controller Cabinet	STM LOG	Steam Log	
SW Sidewalk SY Square Yard SYS System T Tee TB Test Boring TC Traffic Control TCB Telephone Cable TCD Telephone Conduit TCHH Traffic Control Handhole TD Telephone Duct TEB Telephone Enclosure Box TEL Telephone TEMP Temporary TF Top Face TH Test Hole THH Telephone Handhole TJO Transfer of Jurisdiction Ordinance TMH Telephone Manhole TMT Treatment TN Ton TOC Top of Curb TR Traffic TRCB Traffic Signal Conduit TRSCC Traffic Signal Controller Cabinet	STRUCT	Structure/Structural	
SY Square Yard SYS System T Tee TB Test Boring TC Traffic Control TCB Telephone Cable TCD Telephone Conduit TCHH Traffic Control Handhole TD Telephone Duct TEB Telephone Enclosure Box TEL Telephone TEMP Temporary TF Top Face TH Test Hole THH Telephone Handhole TJO Transfer of Jurisdiction Ordinance TMH Telephone Manhole TMT Treatment TN Ton TOC Top of Curb TR Traffic TRCB Traffic Signal Conduit TRSCC Traffic Signal Controller Cabinet	SVC	Service	
T Tee TB Test Boring TC Traffic Control TCB Telephone Cable TCD Telephone Conduit TCHH Traffic Control Handhole TD Telephone Duct TEB Telephone Enclosure Box TEL Telephone TEMP Temporary TF Top Face TH Test Hole THH Telephone Handhole TJO Transfer of Jurisdiction Ordinance TMH Telephone Manhole TMT Treatment TN Ton TOC Top of Curb TR Traffic TRCB Traffic Signal Cable TRCD Traffic Signal Controller Cabinet	SW	Sidewalk	
T Tee TB Test Boring TC Traffic Control TCB Telephone Cable TCD Telephone Conduit TCHH Traffic Control Handhole TD Telephone Duct TEB Telephone Enclosure Box TEL Telephone TEMP Temporary TF Top Face TH Test Hole THH Telephone Handhole TJO Transfer of Jurisdiction Ordinance TMH Telephone Manhole TMT Treatment TN Ton TOC Top of Curb TR Traffic TRCB Traffic Signal Cable TRCD Traffic Signal Conduit TRSCC Traffic Signal Controller Cabinet	SY	Square Yard	
TB Test Boring TC Traffic Control TCB Telephone Cable TCD Telephone Conduit TCHH Traffic Control Handhole TD Telephone Duct TEB Telephone Enclosure Box TEL Telephone TEMP Temporary TF Top Face TH Test Hole THH Telephone Handhole TJO Transfer of Jurisdiction Ordinance TMH Telephone Manhole TMT Treatment TN Ton TOC Top of Curb TR Traffic TRCB Traffic Signal Cable TRSCC Traffic Signal Controller Cabinet	SYS	System	
TC Traffic Control TCB Telephone Cable TCD Telephone Conduit TCHH Traffic Control Handhole TD Telephone Duct TEB Telephone Enclosure Box TEL Telephone TEMP Temporary TF Top Face TH Test Hole THH Telephone Handhole TJO Transfer of Jurisdiction Ordinance TMH Telephone Manhole TMT Treatment TN Ton TOC Top of Curb TR Traffic TRCB Traffic Signal Cable TRSCC Traffic Signal Controller Cabinet	Т	Tee	
TCB Telephone Cable TCD Telephone Conduit TCHH Traffic Control Handhole TD Telephone Duct TEB Telephone Enclosure Box TEL Telephone TEMP Temporary TF Top Face TH Test Hole THH Telephone Handhole TJO Transfer of Jurisdiction Ordinance TMH Telephone Manhole TMT Treatment TN Ton TOC Top of Curb TR Traffic TRCB Traffic Signal Cable TRSCC Traffic Signal Controller Cabinet	ТВ	Test Boring	
TCD Telephone Conduit TCHH Traffic Control Handhole TD Telephone Duct TEB Telephone Enclosure Box TEL Telephone TEMP Temporary TF Top Face TH Test Hole THH Telephone Handhole TJO Transfer of Jurisdiction Ordinance TMH Telephone Manhole TMT Treatment TN Ton TOC Top of Curb TR Traffic TRCB Traffic Signal Cable TRSCC Traffic Signal Controller Cabinet	TC	Traffic Control	
TCHH Traffic Control Handhole TD Telephone Duct TEB Telephone Enclosure Box TEL Telephone TEMP Temporary TF Top Face TH Test Hole THH Telephone Handhole TJO Transfer of Jurisdiction Ordinance TMH Telephone Manhole TMT Treatment TN Ton TOC Top of Curb TR Traffic TRCB Traffic Signal Cable TRSCC Traffic Signal Controller Cabinet	TCB	Telephone Cable	
TD Telephone Duct TEB Telephone Enclosure Box TEL Telephone TEMP Temporary TF Top Face TH Test Hole THH Telephone Handhole TJO Transfer of Jurisdiction Ordinance TMH Telephone Manhole TMT Treatment TN Ton TOC Top of Curb TR Traffic TRCB Traffic Signal Cable TRSCC Traffic Signal Controller Cabinet	TCD	Telephone Conduit	
TEB Telephone Enclosure Box TEL Telephone TEMP Temporary TF Top Face TH Test Hole THH Telephone Handhole TJO Transfer of Jurisdiction Ordinance TMH Telephone Manhole TMT Treatment TN Ton TOC Top of Curb TR Traffic TRCB Traffic Signal Cable TRCC Traffic Signal Conduit TRSCC Traffic Signal Controller Cabinet	тснн	Traffic Control Handhole	
TEL Telephone TEMP Temporary TF Top Face TH Test Hole THH Telephone Handhole TJO Transfer of Jurisdiction Ordinance TMH Telephone Manhole TMT Treatment TN Ton TOC Top of Curb TR Traffic TRCB Traffic Signal Cable TRCD Traffic Signal Conduit TRSCC Traffic Signal Controller Cabinet	TD	Telephone Duct	
TEMP Temporary TF Top Face TH Test Hole THH Telephone Handhole TJO Transfer of Jurisdiction Ordinance TMH Telephone Manhole TMT Treatment TN Ton TOC Top of Curb TR Traffic TRCB Traffic Signal Cable TRCD Traffic Signal Conduit TRSCC Traffic Signal Controller Cabinet	TEB	Telephone Enclosure Box	
TF Top Face TH Test Hole THH Telephone Handhole TJO Transfer of Jurisdiction Ordinance TMH Telephone Manhole TMT Treatment TN Ton TOC Top of Curb TR Traffic TRCB Traffic Signal Cable TRCD Traffic Signal Conduit TRSCC Traffic Signal Controller Cabinet	TEL	Telephone	
TH Test Hole THH Telephone Handhole TJO Transfer of Jurisdiction Ordinance TMH Telephone Manhole TMT Treatment TN Ton TOC Top of Curb TR Traffic TRCB Traffic Signal Cable TRCD Traffic Signal Conduit TRSCC Traffic Signal Controller Cabinet	TEMP	Temporary	
THH Telephone Handhole TJO Transfer of Jurisdiction Ordinance TMH Telephone Manhole TMT Treatment TN Ton TOC Top of Curb TR Traffic TRCB Traffic Signal Cable TRCD Traffic Signal Conduit TRSCC Traffic Signal Controller Cabinet	TF	Top Face	
TJO Transfer of Jurisdiction Ordinance TMH Telephone Manhole TMT Treatment TN Ton TOC Top of Curb TR Traffic TRCB Traffic Signal Cable TRCD Traffic Signal Conduit TRSCC Traffic Signal Controller Cabinet	TH	Test Hole	
TMH Telephone Manhole TMT Treatment TN Ton TOC Top of Curb TR Traffic TRCB Traffic Signal Cable TRCD Traffic Signal Conduit TRSCC Traffic Signal Controller Cabinet	THH	Telephone Handhole	
TMT Treatment TN Ton TOC Top of Curb TR Traffic TRCB Traffic Signal Cable TRCD Traffic Signal Conduit TRSCC Traffic Signal Controller Cabinet	TJO	Transfer of Jurisdiction Ordinance	
TN Ton TOC Top of Curb TR Traffic TRCB Traffic Signal Cable TRCD Traffic Signal Conduit TRSCC Traffic Signal Controller Cabinet	ТМН	Telephone Manhole	
TOC Top of Curb TR Traffic TRCB Traffic Signal Cable TRCD Traffic Signal Conduit TRSCC Traffic Signal Controller Cabinet	ТМТ	Treatment	
TR Traffic TRCB Traffic Signal Cable TRCD Traffic Signal Conduit TRSCC Traffic Signal Controller Cabinet	TN	Ton	
TRCB Traffic Signal Cable TRCD Traffic Signal Conduit TRSCC Traffic Signal Controller Cabinet	TOC	Top of Curb	
TRCD Traffic Signal Conduit TRSCC Traffic Signal Controller Cabinet	TR	Traffic	
TRSCC Traffic Signal Controller Cabinet	TRCB	Traffic Signal Cable	
	TRCD	Traffic Signal Conduit	
TVCB Television Cable	TRSCC	Traffic Signal Controller Cabinet	
	TVCB	Television Cable	

TVCD	Television Conduit			
TVHH	Television Handhole			
TYP	Typical			
UG	Underground			
UIC	Underground Interconnect			
UNC	Unified National Course			
UP	Utility Pole			
V	Valve, Variable			
V/C	Vertical Curve			
VAR	Variable/Varies			
VB	Vertical Bend			
VBOX	Valve Box			
VCH or VC	Valve Chamber			
VCP	Vitrified Clay Pipe			
VEH	Vehicle			
VERT	Vertical			
VMS	Variable Message Sign			
VO	Vacation Ordinance			
W	Water, West			
W/	With			
WCR	Walkway Curb Ramp			
WD	Wood/Wooden			
WF	Wood Fence			
WIF	Wrought Iron Fence			
WM	Water Meter, Water Main			
WMA	Warm Mix Asphalt			
WMR	Water Main Radius			
WP	Wood Pole			
WS	Water Service			
WSP	Wood Stave Pipe			
WU	Western Union			
WV	Water Valve			
WWF	Welded Wire Fabric			
XP	Transmission Pole			

REF STD SPEC SEC 1-01.2



NOT TO SCALE

DEV DATE: IAN 2013

ITEM EXISTING

PROPOSED

Signal Controller Cabinet

Electrical Vault

| EV

EV

Electrical Conduit

_____1"ECD _____

____<u>1"ECD</u>

Electrical Cable (direct burial)

____ECB_____

ECB_

Electrical Duct

12"X12"ED

____12"X12"E[

Combined Electrical & Telephone Duct

12"X12"ED-TD

12"X12"ED-TD

Span Wire

- ALC

∠—AIC

Cable
Transmission Pole

(steel w/ conc base)

Aerial Interconnect

⟨[]⟩**X**P



City Wood Pole

OEPP

•

City Wood Pole w/

HPS

PP —

•

REF STD SPEC SEC



NOT TO SCALE

STANDARD SYMBOLS ELECTRICAL

REV DATE: AUG 2013

ITEM

Light Pole (metal) w/ HPS

Strain Pole (metal)

Combined Lighting Strain Pole HPS

Luminaire

Mercury Vapor Luminaire

Double Light Pole

Utility Wood Pole


Utility Guy Pole

Anchor

Ground

EXISTING

LP O





\

-<u></u>∵-M

OUP


○GP

)—

 $-\!\!-\!\!\!-\!\!\!\!-\!\!\!\!\!-||_{|\!\!|\!\!|}$

PROPOSED







 \odot

• • •

GP_d

>-

——|II:

REF STD SPEC SEC



NOT TO SCALE

STANDARD SYMBOLS ELECTRICAL

ITEM

Traffic Signal Mast Arm Pole

Traffic Signal Mast Arm Pole w/ Luminaire

Traffic Signal on Span Wire

Multi-Directional Traffic Signal on Span Wire


Traffic Signal Conduit


Traffic Signal Cable

Detector Loop, Dipole (loop schedule)


Detector Loop, Quadrapole (loop schedule)

EXISTING











_____2"TRCD

TRCB ____

PROPOSED







2"TRCD

TRCB



REF STD SPEC SEC



NOT TO SCALE

STANDARD SYMBOLS ELECTRICAL

		REV DATE: JAN
ITEM	EXISTING	PROPOSED
Signal Pedestal	\bigcirc	•
Vehicle Signal	\longrightarrow	
Vehicle Signal w/ Backplate	$+\!\!\!\!+\!$	+
Vehicle Signal (optically programmed)		→
Pedestrian Signal	# >	#
Pedestrian Signal (optically programmed)	#0>	# ~
Pedestrian Push Button Post	0	D
Pedestrian Push Button	\dashv	⊣ PPB
Illuminated Sign		▶
Junction Box		
Handhole	ЕНН	■ HH
Traffic Control Handhole	ТСНН	■ TCHH
Street Light Handhole	SLHH	SLHH
Ground Rod Handhole	GRHH	■ GRHH
Fire Alarm Handhole	FAHH	FAHH
STD SPEC SEC		STANDARD SYMBOLS
City of Seattle	NOT TO SCALE	ELECTRICAL

SIGNALIZATION

- ? Vehicle & Pedestrian Signal Head (?=Identification Number)
- ? Traffic Sign (?=Identification Number)
- Cable Runs
 (?=Run Number per Wiring Schedule)
- ? Removal/Relocation Item (?=Identification Number per Removal/Relocation Plan)
- ? Construction Item (?=Identification Number per Signalization Plan)

Signal Poles, Signal Pedestals, Push Button Pedestals & Push Buttons Identified by Number on Signalization Plan.

CHANNELIZATION & SIGNAGE

- ? Install Channelization/Signage (?=Channelization / Signage Identified on Plan)
- Remove Channelization / Signage
 (?=Channelization / Signage Identified on Plan)
- ? Relocate Signage (?=Signage Identified on Plan)

REF STD SPEC SEC




NOT TO SCALE

STANDARD SYMBOLS SIGNALIZATION/CHANNELIZATION & SIGNAGE

STANDARD PLAN NO 003f 000 GENERAL-LEGAL-MISC **ITEM EXISTING PROPOSED** Pavement, HMA or 2"ASPH WMA (CL $\frac{1}{2}$ ") Roadway Cement 6"CONC Concrete, (type to be shown in drawings) 2" HMA or WMA, CL $\frac{1}{2}$ " 2"ASPH/6"CONC Over Roadway Cement **Concrete Base** 2" HMA or WMA, CL $\frac{1}{2}$ " 8"ASPH over HMA or WMA, CL 1"

REF STD SPEC SEC



NOT TO SCALE

STANDARD SYMBOLS PAVING

		REV DATE: SEP 2022
ITEM	EXISTING	PROPOSED
Type 410b Curb & Gutter		
Type 410c Curb		
Cement Concrete Walk	CW	
Pervious Concrete Walk	PCW	SOS CONTRACTOR OF THE PROPERTY
Curb Ramp		
Type 430a Conc Dwy		
Pervious Concrete Surface	PCS	00000 PCS0000000000000000000000000000000
Grading REF STD SPEC SEC	GRADED	
City of Seattle	NOT TO SCALE	STANDARD SYMBOLS PAVING
Lity of Seattle	NOT TO SCALE	FAVING

REV DATE: IIII V 2021

		REV DATE: JULY 202
ITEM	EXISTING	PROPOSED
Maintenance Holes		MH-7
Inlet Type 250A	г	
Inlet Type 250B		
Inlet Type 252		
Inlet Type 268		
Catch Basin round inlet top	$(\widehat{\otimes})$	
Private CB & Inlet	Ξ	
Catch Basin Type 151 (pre 1985)	(O)	
Catch Basin Type 240A	(C) A	● A
Catch Basin Type 240B	(D) _B	lacksquareB
Catch Basin Type 240C	(2) C	♠ C
Catch Basin Type 240D	(<u>&</u>) _D	$\bigotimes_{\mathbb{D}}$
Catch Basin Type 241		
Catch Basin Type 242A	([])	
Catch Basin Type 242B		
Junction Box Type 277A		
Junction Box Type 277B		
Area Drain		
STD SPEC SEC		
City of Seattle	NOT TO SCALE	STANDARD SYMBOLS SEWER & DRAINAGE

REV DATE: NOV 2015

ITEM EXISTING PROPOSED

Sand Box

Clean Out o

Concrete Culvert

Pipe Sewer
Combined <1'-0"Dia

Pipe Sewer
Combined ≥1'-0"Dia

Cat"PS

24"PS

24"PS

Side Sewer Combined $--\xi^{6}$ "SS _____

Pipe Sewer Sanitary
≥1'-0"Dia

24"PSS

24"PSS

Side Sewer Sanitary ____6"SSS ____ ___ ___6"SSS

Pipe Storm Drain
≥1'-0"Dia

24"PSD

24"PSD

REF STD SPEC SEC



NOT TO SCALE

STANDARD SYMBOLS SEWER & DRAINAGE

ITEM EXISTING

PROPOSED

Service Drain

___<u>_</u>8"SD_____

Inlet & CB Connection -----

Open Ended Pipe — 6"PSD —

Ditch

Stream

REF STD SPEC SEC



NOT TO SCALE

STANDARD SYMBOLS **SEWER & DRAINAGE**

REV DATE: NOV 2015

ITEM EXISTING

PROPOSED

Bench Mark (found or set)

Brass Plug/Cap (found or set)

Hub/Tack (found or set)

Monument in Case (found or set)

Conc. Mon. (found or set)

Section Corner (found or set)

Quarter Corner (found or set)

Section Corner (calculated)

Quarter Corner (calculated)

Rebar/Cap, Pipe/Cap Rebar, Iron Pipe (found or set)

Tack/Lead, Tack PK Nail, Spike (found or set)

Bench Mark (not found)

Brass Plug/Cap (not found)

MIC. (not found)

Conc. Mon. (not found)

Rebar/Cap, Pipe/Cap Rebar, Iron Pipe (not found)

Tack/Lead, Tack PK Nail, Spike (not found)

Survey Shot Point







































+

REF STD SPEC SEC



NOT TO SCALE

STANDARD SYMBOLS TOPOGRAPHIC & MISC

TOPOGRAPHIC & MISC

ITEM EXISTING PROPOSED Center Line Monument Line Survey Line Right of Way Line Lot & Ownership Line Permanent **Easement Line Temp Const Easement Line** Vacated Street or Alley STATE LAL State Highway Limited Access Line Building 1111111111 Chain Link Fence Wood Fence Guardrail Rock Facing **Rock Facing** Riprap 16"TREE **Trees** PER DRAWINGS \bigcirc REF STD SPEC SEC STANDARD SYMBOLS

NOT TO SCALE

City of Seattle

ITEM EXISTING PROPOSED Shrub or Bush Ground, Grade Line 5.6% 5.6% Grade (arrow downhill) Rail Road Tracks CITY OF SEATTLE City Limits SLOPE LINE Slope Line Contours Slope Angle Horiz:Vert H: V Vertical Curve Depression Stump TOP OF CUT Top of Cut Toe of Fill TOE OF FILL **Dimension Line** Match Line Test Hole & Number (test boring) Bench Mark REF STD SPEC SEC



NOT TO SCALE

STANDARD SYMBOLS **TOPOGRAPHIC & MISC**

		REV DATE: DEC 2016
ITEM	EXISTING	PROPOSED
Monitor Well	○ ^{MW}	
Street Name Sign	Ф	
Traffic Sign	\mapsto	\mapsto
US Mail Box	US	
Private Mail Box	0	
Bollard	0	•
Posts		• •
Parking Meter & Pay Station	on 🛚 🗓	
Rectangular Casting		
Circular Casting	\bigcirc	
Column	\bigcirc	
Jersey Barrier & Eco Block		
Tree Pit		
North Arrow horizontal		
North Arrow vertical REF STD SPEC SEC		
City of Seattle	NOT TO SCALE	STANDARD SYMBOLS TOPOGRAPHIC & MISC

REV DATE: MAR 2019

ITEM

EXISTING

PROPOSED

Telephone Cable (direct burial)

Telephone Conduit

Telephone Duct

Telephone Enclosure

Telephone Maintenance Hole

Telephone Pole

Telephone Handhole

Television Cable (direct Burial)

Television Handhole

Telegraph Maintenance

Hole

Steam Log

Steam Vault

Gas Main <1'-0"Dia

Gas Main ≥1'-0"Dia

Gas Valve

Gas Meter

Gas Regulator

Petroleum or Oil

Abandon(ed)

REF STD SPEC SEC

TEL VAULT

TP

ГПтнн

______TVCB

TVHH

TELEG MH

____X

□GM

G REG

_____2<u>"ECD(ABAN)</u>

___2"ECD-ABAN

NOT TO SCALE


STANDARD SYMBOLS PRIVATE UTILITIES

	REV DATE: MAR 2019
EXISTING	PROPOSED
	+
	
	-
8"W	8"W
	36"W
	8"-11 _{1/4} °HBorVB
	8"-22 _{1/2} °HBorVB
	8"-45°HBorVB
————	8"-90°HBorVB
	8"X8"X6"X6"CR
——— ——————————————————————————————————	_,†, 8"X8"X6"T
	
NOT TO SCALE	STANDARD SYMBOLS WATER
	8"W


ITEM EXISTING PROPOSED 6" & Larger **Domestic Service** 3" & 4" Domestic DS Service 4" & Larger Fire $^{\mathsf{I}}\mathsf{DC}$ DC Service 2" & Smaller $\, \square W \, M$ WM Water Service Valve Box Gate Valve Gate Valve _™8"GV W/CH w/ Chamber Gate Valve w/ Vault Chamber 8"X4"RED Reducer Air Valve _O1½"B0 **Blowoff** Fire Standpipe REF STD SPEC SEC STANDARD SYMBOLS City of Seattle WATER NOT TO SCALE

		REV DATE: MAR 2019
ITEM	EXISTING	PROPOSED
Water Test Station		
Water Chamber		
Sprinkler Head	×	×
Irrigation Valve	IRRV ⊠	IRRV
Angle Valve		
Butterfly Valve		
Ball Valve		
Check Valve	N	N
Cone Valve	K	\bowtie
Globe Valve	\bigotimes	
Needle Valve	\triangleright	
Plug Valve		
Resilient Seal Gate Valve	[×]	H
Vertical Bend		
Concrete Blocking		•
REF STD SPEC SEC		OTANDADD OVALDOLO
City of Seattle	NOT TO SCALE	STANDARD SYMBOLS WATER

REV DATE: DEC 2019



PLAN VIEW



PLAN VIEW

NOTES:

- MEASUREMENT PER LINEAR FOOT. PIPE ENDING IN STRUCTURE MEASURED TO EITHER INSIDE FACE OR TO CENTERLINE OF STRUCTURE AS INDICATED, OR TO TEE OR WYE AS INDICATED.
- 2. TEE OR WYE INCLUDING PLUG UNIT PRICE EACH
- ALL PIPE MUST BE MEASURED ON THE SLOPE ALONG THE CENTERLINE OF PIPE TO NEAREST 0.10 LF.

REF STD SPEC SEC DIVISION 7




NOT TO SCALE

SEWER/DRAINAGE MEASUREMENT DIAGRAM

REV DATE: DEC 2019


NOTES:

- 1. MONUMENT CASE TO BE INSTALLED BY CONTRACTOR.
- 2. BASE TO BE PLACED ON A WELL COMPACTED FOUNDATION.
- FRAME AND COVER MUST BE TESTED FOR ACCURACY OF FIT AND MUST BE MARKED IN SETS FOR DELIVERY.
- FRAME AND COVER MUST BE CAST IRON AND HAVE COATING APPLIED TO ALL FACES.
- CASTINGS IN RIGID PAVEMENT MUST HAVE REINFORCING STEEL IN THE PAVEMENT.
- 6. USE LOCKING COVER IN R/W. DRILL AND TAP, APPLY ANTI-SEIZE COATING AND BOLT DOWN WITH 3/8"S.S. ALLEN-HEAD BOLTS -2 PLACES.



-16" #3 BAR SPIRAL, 3" BETWEEN LAYERS (3 LAYERS OF BAR)

RISER RING		DIMENSIONS		
A (SIZE)	1½"	2"	3"	



5½"

4³½"

½"

4³½"

4"

5³½"

5³½"


5³½"

CASE SECTION

SEE SECTION A-A ON

STD PLAN NO 020c

RISER RING SECTION



COVER SECTION


REF STD SPEC SEC 8-13





NOT TO SCALE


SEE NOTE 6.

MONUMENT FRAME & COVER










- STABILIZED ACCESS MUST BE USED IN ALL AREAS OF THE SITE WITH VEHICLE TRAFFIC AND PARKING, INCLUDING PLANTING STRIPS.
- SEE SECTION 9-37.2 (TABLE 3) FOR GEOTEXTILE REQUIREMENTS.
 GEOTEXTILE MODIFICATIONS BASED ON SPECIFIC PROJECT SITE CONDITIONS
 MAY BE APPROVED BY THE ENGINEER.
- STABILIZED CONSTRUCTION ENTRANCES ON SEATTLE PARKS & RECREATION PROPERTY ARE LIMITED TO A MAXIMUM WIDTH OF 10 FEET UNLESS DIRECTED OTHERWISE.


REF STD SPEC SEC 8-01



NOT TO SCALE

STABILIZED CONSTRUCTION ENTRANCE






- 1. STAKE TREES PER STD PLAN NO 100a.
- 2. ONE STAKE PER TREE ON WINDWARD SIDE; SECOND STAKE ON LEEWARD SIDE.
- 3. SLOPES STEEPER THAN 2:1 MAY REQUIRE AN APPROVED EMBANKMENT STABILIZATION SYSTEM TO CREATE A LEVEL TREE PIT SUCH AS:
 - -ROCK FACING -PRECAST CONCRETE WALL UNITS
 - -TIMBER WALL
 - -MANUFACTURED SLOPE RETENTION UNITS
- CHAINLOCK TREE TIE. LOOP EACH TIE AROUND TREE LOOSELY TO PROVIDE 1" SLACK FOR DIAMETER GROWTH.
- SHAPE SOIL TO PROVIDE 3' DIAMETER OR ROOTBALL DIAMETER, WHICHEVER IS GREATER, WATERING RING.
- 6. REMOVE AL WIRE, STRINGS AND OTHER NON-BURLAP MATERIAL; AND REMOVE BURLAP FROM TOP $\frac{2}{3}$ OF ROOTBALL.


REF STD SPEC SEC 8-02




NOT TO SCALE


TREE & SHRUB PLANTING ON SLOPES







REV DATE: MAR 2013




REF STD SPEC SEC 8-02



NOT TO SCALE

GROUND COVER PLANTING

REV DATE: DEC 2019





REF STD SPEC SEC 8-02





NOT TO SCALE

PLANTING PATTERN









- 1. USE TEFLON TAPE ON ALL THREADED FITTINGS.
- 2. FOR TWO-WIRE SYSTEMS, INSTALL COMMUNICATION WIRES AND DECODERS IN ACCORDANCE WITH MANUFACTURER'S INSTRUCTIONS.
- 3. SEE STD PLAN 115a FOR POINT OF CONNECTION DIAGRAM.


MASTER VALVE & FLOW SENSOR


REF STD SPEC SEC 8-03



NOT TO SCALE


IRRIGATION MASTER VALVE & FLOW SENSOR





"U" SHAPED CUT-OUT IN VALVE BOX THAT ALLOWS 2" CLEARANCE FROM TOP OF PIPE TO TOP OF "U'

AUTOMATIC CONTROL VALVE




REF STD SPEC SEC 8-03



NOT TO SCALE

IRRIGATION VALVES

DEV DATE: MAD 2013




REF STD SPEC SEC 8-03



NOT TO SCALE

IRRIGATION VALVES

REV DATE: JUN 2005



REF STD SPEC SEC 8-03





NOT TO SCALE


USE TEFLON TAPE ON ALL THREADED FITTINGS

NOTES:


IRRIGATION VALVES









IRRIGATION TRENCHES





NOT TO SCALE

City of Seattle









TREE IN PLANTING STRIP

NOTES:


- 1. CONSIDER TRAFFIC TURNING VISIBILITY AND PEDESTRIAN VISIBILITY WHEN SELECTING FENCE HEIGHT; TYPICALLY SHORTER FENCING AROUND TREE PITS BETWEEN SIDEWALK AND ROADWAY IS DESIRED.
- TO BE USED FOR TREES IN PLANTING STRIPS AND FOR WORK LASTING 31 CALENDAR DAYS OR MORE. FOR TREES IN TREE PITS AND LASTING 30 CALENDAR DAYS OR LESS, SEE STD PLAN 132b.


REF STD SPEC SEC 1-07.16(2), 8-01



NOT TO SCALE

TREE PROTECTION DURING CONSTRUCTION





- REUSABLE TEMPORARY PROTECTION FENCING USED TO PROTECT TREES IN TREE PITS MUST SURROUND THE ENTIRE UNPAVED TREE PIT AREA AND BE ANCHORED AND MAINTAINED IN A STABLE UPRIGHT CONDITION. SEE SECTION 8-01.3(2)B.
- REUSABLE TEMPORARY PROTECTION FENCING USED ONLY FOR TREES IN TREE PITS AND ONLY FOR WORK LASTING 30 DAYS OR LESS. FOR TREES IN THE PLANTING STRIP AND WORK LASTING LONGER THAN 30 DAYS, SEE STD PLAN 132a.

REF STD SPEC SEC 1-07.16(2), 8-01



NOT TO SCALE

REUSABLE TEMPORARY PROTECTION FENCE

X = 2 FT FOR EVERY 1 INCH OF TRUNK DIA MEASURED 4.5 FT ABOVE GRADE (MIN 8 FT) ΕQ ΕQ **ELEVATION** ZONE C ZONE B TRENCHING/EXCAVATION DIA = XZONE A (INTERIOR CRITICAL ROOT ZONE) ZONE A NO DISTURBANCE ALLOWED WITHOUT SITE VISIT AND DIA=1/2XAPPROVED TVSPP PER SECTION 8-01.3(2)B. TUNNELING REQUIRED TO INSTALL UTILITIES 3'-0" OR ZONE B (CRITICAL ROOT ZONE) NO DISTURBANCE ALLOWED WITHOUT APPROVAL OF METHODS TO MINIMIZE ROOT DAMAGE.


NO MORE THAN 30 PERCENT OF ZONE B SHALL BE DISTURBED. 3. TUNNELING MAY BE REQUIRED FOR BELOW-GRADE IMPROVEMENTS. ZONE C (EXTENDED ROOT ZONE) DISTURBANCE ALLOWED BASED ON APPROVED PLANS. SEE NOTE: SEVERANCE OF ROOTS LARGER THAN 2" REQUIRES ENGINEER'S APPROVAL. PLAN


REF STD SPEC SEC 1-07.16(2), 8-01




NOT TO SCALE

TREE PROTECTION DURING TRENCHING, TUNNELING OR EXCAVATION








- 1. ALL SOIL AREAS DISTURBED OR COMPACTED DURING CONSTRUCTION, AND NOT COVERED BY BUILDINGS OR PAVEMENT, MUST BE AMENDED WITH COMPOST AS DESCRIBED BELOW.
- SUBSOIL SHOULD BE SCARIFIED (LOOSENED) 4 INCHES BELOW AMENDED LAYER, TO PRODUCE 12-INCH DEPTH OF UN-COMPACTED SOIL, EXCEPT WHERE SCARIFICATION WOULD DAMAGE TREE ROOTS OR AS DETERMINED BY THE ENGINEER.
- 3. COMPOST MUST BE TILLED IN TO 8 INCH DEPTH INTO EXISTING SOIL, OR PLACE 8 INCHES OF COMPOST-AMENDED SOIL, PER SOIL SPECIFICATION
- 4. TURF AREAS MUST RECEIVE 1.75 INCHES OF COMPOST TILLED IN TO 8-INCH DEPTH, OR MAY SUBSTITUTE 8" OF IMPORTED SOIL CONTAINING 20-25% COMPOST BY VOLUME. THEN PLANT GRASS SEED OR SOD PER SPECIFICATION.
- 5. PLANTING BEDS MUST RECEIVE 3 INCHES OF COMPOST TILLED IN TO 8-INCH DEPTH, OR MAY SUBSTITUTE 8" OF IMPORTED SOIL CONTAINING 35-40% COMPOST BY VOLUME. MULCH AFTER PLANTING, WITH 2-3 INCHES OF ARBORIST WOOD CHIP MULCH OR APPROVED FOLIAL.
- 6. SETBACKS: TO PREVENT UNEVEN SETTLING, DO NOT COMPOST-AMEND SOILS WITHIN 3 FEET OF UTILITY INFRASTRUCTURES (POLES, VAULTS, METERS ETC.). WITHIN ONE FOOT OF PAVEMENT EDGE, CURBS AND SIDEWALKS SOIL SHOULD BE COMPACTED TO APPROXIMATELY 90% PROCTOR TO ENSURE A FIRM SURFACE.


REF STD SPEC SEC 8-01, 8-02, 9-14




NOT TO SCALE

SOIL AMENDMENT AND DEPTH





- 6. INSTALL SIDE SLOPE BEGINNING AT BOTTOM OF ROADWAY SUBBASE TO TOP OF SOIL CELL AGGREGATE SUBBASE.
- 7. INSTALL REINFORCED SIDEWALK OVER IMPERMEABLE MEMBRANE LINER OVER GEOTEXTILE OVER SOIL CELL DECK. SEE TABLE FOR V VARIABLE SIDEWALK DEPTHS AND REINFORCEMENT REQUIREMENTS.
- 8. 3/8" THROUGH AND CONTRACTION JOINTS MUST BE LOCATED AS REQUIRED BY SECTION 8-14.3(6). SOIL CELL SUPPORTED SIDEWALK JOINTS SHALL HAVE A MINIMUM INTERVAL OF 6' AND A MAXIMUM INTERVAL OF 12' IN THE LONGITUDINAL DIRECTION.
- 9. ALL REINFORCED SIDEWALK MUST BE CLASS 4000 CONCRETE. SIDEWALK FINISHING MUST BE AS REQUIRED BY SECTION 8-14.3(4)B.
- 10. PROVIDE REINFORCED CONC SIDEWALK SLAB ON GRADE TO SPAN 4' BEYOND SOIL CELL SUPPORT.
- 11. SEE STANDARD PLAN 405C FOR DOWEL BAR SIZE, SPACING AND PLACEMENT REQUIREMENTS.



SECTION C-C

SIDEWALK REINFORCMENT GRID REQUIREMENTS

SIDEWALK OVERHANG	TOP MAT (TRANSVERSE)	TOP MAT (LONGITUDINAL)	MINIMUM AREA TOP/FT (IN ²)	BOTTOM MAT (LONGITUDINAL & TRANSVERSE)	MINIMUM AREA BOTTOM/FT (IN ²)	"X"		
>3'-0" TO 4'-0"	#6 @ 6"OC	#3 @ 12"0C	0.78	#3 @ 12"OC	0.11	4'-6"		
>2'-0" TO 3'-0"	#5 @ 6"OC	#3 @ 12"0C	0.50	#3 @ 12"0C	0.11	3'-0"		
>1'-0" TO 2'-0"	#4 @ 6"OC	#3 @ 12"0C	0.25	#3 @ 12"0C	0.11	2'-3"		

REINFORCED SIDEWALK NOTES:


- A. WHEN AN OVERHANG IS LESS THAN 1'-0" USE #3@12"OC FOR BOTH TOP & BOTTOM MAT TRANSVERSELY AND LONGITUDINALLY.
- B. TRANSVERSE STEEL IS IN THE DIRECTION OF OVERHANG IF ONE IS PRESENT.
- C. OVERHANG SLAB SECTIONS MUST BE 6' WIDE LONGITUDINALLY AT A MINIMUM AND CAN BE INCREASED TO A MAXIMUM OF 12'.

REF STD SPEC SEC 8-02.3(27)




NOT TO SCALE

SOIL CELL



- INSTALL A MINIMUM OF TWO ROOT WATERING SYSTEMS (RWS) PER TREE.
 INSTALL IRRIGATION MAINLINE, LATERAL LINES, AND VALVE BOXES ON SIDEWALK SIDE.
 INSTALL RWS A MINIMUM OF 12 INCHES FROM PAVEMENT EDGE AND 18 INCHES FROM

TREE PIT IRRIGATION DETAILS RWS = ROOT WATERING SYSTEM





REF STD SPEC SEC 8-03



NOT TO SCALE

IRRIGATION FOR TREE PITS WITH SOIL CELLS





IRRIGATION DETAIL FOR SOIL CELLS WITHIN PLANTING STRIPS

RWS = ROOT WATERING SYSTEM
NOTE: CENTER DRIP LINE IN SOIL CELLS PER MANUFACTURER

NOTES:


- 1. INSTALL A MINIMUM OF TWO ROOT WATERING SYSTEMS PER TREE.
- 2. CENTER DRIP TUBING IN SOIL CELLS PER MANUFACTURER.
- 3. INSTALL MAINLINE AND VALVE BOXES ON SIDEWALK SIDE OF PLANTING STRIP.
- 4. INSTALL SPRAY HEADS A MINIMUM OF 1 FOOT FROM CURB AND SIDEWALK.
- 5. ADJUST IRRIGATION LAYOUT AND SOIL CELL LAYOUT TO FIT PROJECT PLANS.


REF STD SPEC SEC 8-03





NOT TO SCALE

IRRIGATION FOR PLANTING STRIPS WITH SOIL CELLS












TYPE 205a MAINTENANCE HOLE





NOT TO SCALE


City of Seattle











































REV DATE: NOV 2017



PLAN VIEW (TOP REMOVED)



SECTION A-A

NOTES:


1. SEE STANDARD PLANS NO 2040 THROUGH 212b FOR MAINTENANCE HOLE REQUIREMENTS.


REF STD SPEC SEC 7-05



NOT TO SCALE

FLEXIBLE JOINT FOR VCP CONNECTION TO MAINTENANCE HOLES






RUNNING BOND PATTERN
GROUT BETWEEN ALL BRICKS

REF STD SPEC SEC 7-05



NOT TO SCALE

REBUILD EXISTING BRICK MAINTENANCE HOLE



1. DESIGNATE LOCKING COVER AS TYPE 230L FOR USE IN NON-VEHICULAR TRAFFIC AREAS.
2. COVER THICKNESS IS MEASURED FROM THE BOTTOM OF THE PATTERN.
3. FRAMES MUST BE MANUFACTURED FROM CAST IRON OR DUCTILE IRON.
4. COVERS MUST BE MANUFACTURED FROM DUCTILE IRON.

- 5. CASTING HEIGHTS:

 MUST BE 10" WHEN IN ROADWAY.


 MUST BE 7" WHEN NOT IN ROADWAY
- SEE ALSO STD PLAN NO. 406.


REF STD SPEC SEC 7-05, 9-12



NOT TO SCALE

2'-0" DIAMETER FRAME & COVER






REF STD SPEC SEC 7-05



NOT TO SCALE


MAINTENANCE HOLE LADDER, STEP AND HANDHOLD



HANDHOLD, NOTE 3-STEE STEP, SEE NOTE 5 و, 1' - 01'-6"MIN CLR OPENING

24" HIGH CONCENTRIC CONE

18" HIGH CONCENTRIC CONE



NOTES:

- MATERIAL STEEL REINFORCED POLYPROPYLENE.
- DIMENSIONS FOR THE MH LADDER AND STEP ARE MINIMUM REQUIREMENTS ONLY.
- 3. WHEN THE DISTANCE FROM THE LAST (HIGHEST) STEP OR HANDHOLD TO THE TOP OF THE MH FRAME EXCEEDS 1'-6, A HANDHOLD MUST BE INSTALLED MID-WAY IN THE LEVELING BRICK OR COLLAR.


 4. EITHER STEPS, LADDERS OR A COMBINATION OF THE TWO CAN BE USED. IF BOTH STEPS
- AND LADDERS ARE USED IN ANY MH, THEY MUST BE FROM THE SAME MANUFACTURER.
- STEP ON OPPOSITE SIDE OF MH MUST BE PLACED MID WAY BETWEEN STEPS ON OPPOSING SIDE.


REF STD SPEC SEC 7-05





NOT TO SCALE


MAINTENANCE HOLE LADDER, STEP AND HANDHOLD











NOTES:

- FRAME & GRATE OR FRAME & COVER MUST BE LOCATED OVER TRAP.
- INVERT OF INLET PIPE MUST BE 2"MIN ABOVE INVERT OF OUTLET PIPE.
- SEE STD PLAN 261 FOR ALLOWABLE OUTLET LOCATIONS.

SECTION B-B


СВ	CASTING	
TYPE	FRAME	COVER
240A	PER STD PLAN 230	PER STD PLAN 230
240B	PER STD PLAN 264	PER STD PLAN 264
240C	PER STD PLAN 262	PER STD PLAN 265
240D	PER STD PLAN 263A	PER STD PLAN 265


REF STD SPEC SEC 7-05





NOT TO SCALE


TYPE 240 CATCH BASIN




















& INSTALLATION




NOT TO SCALE

City of Seattle








CURB DETAIL (PLAN VIEW) FOR TYPE 240D & 242C CB & TYPE 250B INLET


REF STD SPEC SEC 7-05




NOT TO SCALE


CATCH BASIN & INLET INSTALLATION WITH STANDARD PLAN 263B ALTERNATIVE HOOD








REV DATE: SEP 2015







REF STD SPEC SEC 9-12




NOT TO SCALE


TYPE 263 ALTERNATIVE INLET HOOD









REV DATE: AUG 2025








NOTES:


- 1. OPEN AREA 100 SQUARE INCHES.
- 2. OTHER GRATES ACCEPTABLE; SPECIFY VANE, SOLID COVER, BI-DIRECTIONAL VANE, ADA OR BEEHIVE ON PLANS.
- 3. SEE STD PLAN NO 265 FOR VANE AND END DETAIL.
- 4. STD PLAN NO 266 DIMENSIONS GOVERN ON END DETAIL.
- 5. REPLACEMENT VANED GRATE FOR TYPE 164 INLET FRAMES.


REF STD SPEC SEC 7-20.3(6), 9-12





NOT TO SCALE


TYPE 266 REPLACEMENT VANED GRATE












- 1. DETENTION PIPE MATERIAL MUST BE AS SHOWN ON THE APPROVED CONSTRUCTION DRAWINGS. MATERIALS THAT MAY BE APPROVED FOR USE IN THE ROW INCLUDE:
 - * DUCTILE IRON PIPE (DIP)
 - * REINFORCED CONCRETE PIPE (RCP)
 - * POLYPROPYLENE PIPE (PP DETENTION)
 - * STEEL REINFORCED POLYETHYLENE PIPE (STL REINF PE DETENTION). ONLY MANUFACTURER SUPPLIED TEES MUST BE USED FOR CONNECTIONS.
- 2. BEDDING FOR DETENTION PIPE MUST BE CLASS B. DIP AND RCP MUST BE BEDDED IN MINERAL AGGREGATE TYPE 9. FLEXIBLE PIPE MUST BE BEDDED IN MINERAL AGGREGATE TYPE 22.
- 3. INTERMEDIATE MAINTENANCE HOLES WILL BE REQUIRED FOR DETENTION PIPE LENGTHS GREATER THAN 350LF.
- 4. OUTLET PIPE MUST CONNECT TO MH ON MAINLINE.
- 5. STRUCTURE DESIGN MUST BE MODIFIED FOR PRIVATE SYSTEM WITH EXCLUSION OF SHEAR GATE
- 6. ROTATE ELBOW RESTRICTOR CLEAR OF ACCESS OPENING.
- 7. FRAME LADDER AND STEPS OFFSET:
 - 7.1. CLEAN OUT IS VISIBLE FROM TOP
- 7.2. CLIMB DOWN SPACE IS CLEAR OF RISER AND CLEAN OUT GATE
- 7.3. MH OPENING MUST NOT BE PLACED DIRECTLY OVER THE TOP OF INLET PIPE
- 8. THE MAINTENANCE HOLES MUST BE SIZED FOR THE OUTSIDE DIAMETER OF THE DETENTION PIPE, WHICH WILL VARY DEPENDING ON THE DETENTION PIPE MATERIAL.

REF STD SPEC SEC 7-16



NOT TO SCALE

FLOW CONTROL STRUCTURE
WITH DETENTION PIPE




- 1. INVERT OF DETENTION PIPE TO BE HIGHER THAN INVERT OF OUTLET PIPE
 2. *SPECIFIC DESIGN INFORMATION WILL BE INDICATED ON ACTUAL CONSTRUCTION DRAWINGS
 3. ROTATE ELBOW RESTRICTOR CLEAR OF ACCESS OPENING
- 4. FOR ALTERNATIVE PIPE MATERIALS, REFER TO STD PLAN NO 270
- FRAME LADDER AND STEPS OFFSET: 5.1. CLEAN OUT IS VISIBLE FROM TOP
- CLIMB DOWN SPACE IS CLEAR OF RISER AND CLEAN OUT GATE
- MH OPENING MUST NOT BE PLACED DIRECTLY OVER THE TOP OF INLET PIPE


REF STD SPEC SEC 7-16



NOT TO SCALE

CMP DETENTION PIPE PRIVATE SYSTEM ONLY





REV DATE: AUG 2013

PIPE DIAMETER			END PLATE THICKNESS	STIFFENER TYPE &	STIFFENER SPACING			SIZE W
D1	D2	D3	t	SIZE	S1	S	N	
TYPE A								
30"	-	-	1/4"	FLAT 2½" X ¼"	6"	6"	3	¾16"
36"	-	ı	1/4"	FLAT 3" X 1/4"	6"	6"	4	³∕ ₁₆ "
48"	ı	ı	1/4"	FLAT 4½" X ½"	8"	8"	4	³ /16"
60"	1	ı	3/8"	L 2½" X 2" X 3%"	10"	10"	4	1/4"
72"	-	ı	³ / ₈ "	L 3" X 3" X 3%"	6"	10"	6	1/4"
TYPE B								
30"	-	6"	<i>1</i> 4"	FLAT 2½" X ¼"	5½"	5½"	3	3/16"
	-	8"			5"	5"	3	
	1	12"			4"	6"	2	
36"	-	6"	<i>Y</i> 4"	FLAT 3" X 1/4"	6"	5½"	4	³/16"
	ı	8"			6"	5"	4	
	i	12"			5½"	5½"	3	
48"	-	6"	<i>Y</i> 4"	FLAT 4¼" X ¼"	8"	8"	4	3/16"
	-	8"			6"	8"	4	
	-	12"			4"	7½"	4	
60"	1	6"	3/8"	L 2½" X 2" X ¾"	7"	9"	5	1/4"
	-	8"			10"	10"	4	
	ı	12"			6"	10"	4	
72"	1	6"	³ / ₆ "	L 3" X 3" X 3 ₈ "	8"	8"	7	1/4"
	-	8"			8"	9"	6	
	-	12"			8"	10"	5	
TYPE C								
48"	30"	_	1/4"	FLAT 4¼" X ¼"	2"	8"	1	³∕ ₁₆ "
60"	36"	-	3/8"	L 2½" X 2" X 3%"	2"	7"	2	1/2"
72"	36"	_	3/8"	L 2" X 3" X 3%"	3"	8½"	3	1/4"

NOTES:


- 1. DESIGNS VALID FOR PIPE INSTALLED WITH 6'-0" OR LESS OF COVER FROM CROWN OF PIPE TO GRADE. MAXIMUM WATER SURCHARGE 3'-0" ABOVE CROWN OF PIPE
- 2. END PLATE MATERIAL: ALUMINUM 6061-T6
- 3. DESIGNS MUST BE USED ONLY FOR ALUMINUM CMP

REF STD SPEC SEC 7-16



NOT TO SCALE

CMP DETENTION STRUCTURE END PLATE DIMENSIONS





REF STD SPEC SEC 7-16




NOT TO SCALE

FLOW CONTROL DEVICE ASSEMBLY







CORRUGATED METAL PIPE



NOT TO SCALE

City of Seattle






- CORRUGATED FLANGE PLATE AND NON-CORRUGATED PIPE MUST BE ALUMINUM.
- SELF-TAPPING SCREWS TO BE STAINLESS STEEL MEETING ASTM A 307.


REF STD SPEC SEC 7-17, 7-16.2




NOT TO SCALE


TEE INSTALLATION CORRUGATED METAL PIPE








REV DATE: 2003






REF STD SPEC SEC 7-16.2, 9-05



NOT TO SCALE

CORRUGATED METAL PIPE COUPLING BANDS



- ALL SANITARY PLUMBING OUTLETS MUST BE CONNECTED TO THE SANITARY SEWER OR COMBINED SEWER. 2'-6"MIN DISTANCE FROM HOUSE, EXCEPT FOR SOIL PIPE CONNECTION. 1'-6"MIN COVER OF PIPE.

- 4. 2'-6"MIN COVER AT PROPERTY LINE.
- 5. 5'-0"MIN COVER AT CURB LINE.
- 6. LAY PIPE IN STRAIGHT LINE BETWEEN BENDS. MAKE ALL CHANGES IN GRADE OR LINE WITH BENDS OR WYES.
 7. STANDARD 4" TO 6" INCREASER.
- 9. 4" SEWER PIPE: MIN SIZE IN STREET, AND ELSEWHERE AS DIRECTED. 2% MIN GRADE, 100% MAX.
 9. 4" SEWER PIPE: MIN SIZE ON PROPERTY. 2% MIN GRADE, 100% (45*) MAX.

- 10. TEST "T" WITH PLUG

 11. CLEANOUT AT UPSTREAM END OF SIDE SEWER.

 12. ALL CONSTRUCTION MUST BE IN ACCORDANCE WITH THE CURRENT SIDE SEWER ORDINANCE.

DIMENSIONS:

- A = FRONT YARD SETBACK
- B = LENGTH OF HOUSE
- C = SIDE YARD SETBACK
- D = WIDTH OF HOUSE

REF STD SPEC SEC 7-18



NOT TO SCALE

SIDE SEWER INSTALLATION


EX SURFACE NEAT LINE WIDTH FOR EXCAVATION & BACKFILL ACTUAL SIDE SLOPE BY CONTRACTOR BEDDING STD PLAN NO 285 EXTRA EXCAVATION AS REQUIRED 3'-4" SMALLER THAN 18" ID 1.5ID+1'-6" 18" ID & LARGER


REF STD SPEC SEC 2-07, 7-17




NOT TO SCALE


TYPICAL TRENCH DETAIL FOR SEWER & STORM DRAIN







CROSSING WATER OVER SEWER/STORM DRAIN



STANDARD SINGLE 18'-0" NOMINAL LENGTH DUCTILE IRON WATER MAIN SECTION CENTERED AT THE POINT OF CROSSING

CROSSING WATER UNDER SEWER/STORM DRAIN

NOTES:


- EXCEPTIONS TO STD PLAN NO 286a & 286b MUST BE APPROVED BY SEATTLE PUBLIC UTILITIES.
- "SEWER/STORM DRAIN" INCLUDES STORM DRAINS, SANITARY SEWER, COMBINED SEWER MAINS AND SIDE SEWER.
- 3. WHERE MINIMUM CLEARANCES CANNOT BE MET, SEWER MUST BE CONSTRUCTED OF MATERIALS AND WITH JOINTS THAT ARE EQUIVALENT TO WATER MAIN STANDARDS INCLUDING WATER MAIN PRESSURE TESTING REQUIREMENTS.
- 4. NO VERTICAL CLEARANCE REQUIRED.
- 5. IF MINIMUM VERTICAL SEPARATION CANNOT BE MET, WATER MAIN MUST BE A STANDARD SINGLE 18'-0" NOMINAL LENGTH DUCTILE IRON WATER MAIN SECTION CENTERED AT THE POINT OF CROSSING.
- 6. SEWER/STORM DRAIN MUST HAVE ADEQUATE FOUNDATION SUPPORT TO PREVENT SETTLEMENT ON THE WATER MAIN AND TO PREVENT DEFLECTION OF WATER MAIN JOINTS.
- 7. CROSSINGS AT AN ANGLE BETWEEN 90° AND 45° MAY OCCUR BETWEEN 9'-0" AND 6'-0" OF WATER MAIN JOINT. FOR CROSSINGS LESS THAN 45°, SEE NOTE 1.


REF STD SPEC SEC 1-07.17, 7-11




NOT TO SCALE

SPACING & CLEARANCES FOR SEWER/STORM DRAIN & WATER







SECTION C-C

SECTION D-D

NOTES:


- ALL ½" STEEL & L3"x 2"x ½" TO BE A-36. 6"Ø PIPE TO BE STANDARD WEIGHT STEEL. AFTER FABRICATION, DRAIN ASSEMBLY TO BE
- HOT DIP GALVANIZED.
- VANED GRATE TO BE PER STD PLAN NO 265.

REF STD SPEC SEC 6-01, 7-05



NOT TO SCALE

BRIDGE DRAIN




- 1. ASTM D 2241 SDR 21 CLASS 200 PVC PIPE OR ASTM D 1785 SCH 40.
- SLOT DIMENSIONS ARE 0.064" WIDE X 1.00" LONG SPACED ALONG PIPE AT 0.3" ON CENTER.

REF STD SPEC SEC 9-05.4(1)



NOT TO SCALE

PVC SUBSURFACE DRAIN PIPE



- TYPICAL MAXIMUM SLOPE ALLOWED IS 2.5H=1V, 3H=1V MAX WHEN WITHIN 50-FEET OF INTERSECTIONS OR CURBLESS ROADWAY.
- BIORETENTION OVERFLOW ELEVATIONS MUST BE SET BELOW SIDEWALK ELEVATION.
- SCARIFY SUBGRADE AS SPECIFIED IN SPEC SECTION 7-21.3(2)B IN THE AREA SUBJECT TO TEMPORARY PONDING BEFORE BIORETENTION SOIL INSTALLATION.

 12" MIN OR 18" MIN IF WATER QUALITY TREATMENT IS REQUIRED PER STORMWATER CODE
- REQUIREMENT.
- CELL MUST BE PLANTED PER APPROVED LANDSCAPE PLAN.
- SOIL UNDER SHOULDERS OR PAVED AREAS MUST BE UNDISTURBED NATIVE SOIL OR
- APPROVED FILL COMPACTED TO 95% DENSITY.

 FACE OF CURB TO TOP OF SLOPE MUST BE MIN 2'-0" FOR NON-MAJOR ARTERIAL STREET, MIN 4'-0" FOR MAJOR ARTERIAL STREET.


 PROVIDE MIN ONE INCH GAP BETWEEN TOP OF WALKS, CURBS, PAVEMENTS AND
- DRIVEWAYS AND TOP OF ARBORIST WOODCHIP MULCH.

REF STD SPEC SEC 7-21



NOT TO SCALE

INFILTRATING BIORETENTION WITH SLOPED SIDES



- TYPICAL MAXIMUM SLOPE ALLOWED IS 2.5H=1V, 3H=1V MAX WHEN WITHIN 50-FEET OF INTERSECTIONS OR CURBLESS ROADWAY.
- BIORETENTION OVERFLOW ELEVATIONS MUST BE SET BELOW SIDEWALK ELEVATION.
- SCARIFY SUBGRADE AS SPECIFIED IN SPEC SECTION 7-21.3(2)B IN THE AREA SUBJECT
- TO TEMPORARY PONDING BEFORE BIORETENTION SOIL INSTALLATION.


 12" MIN OR 18" MIN IF WATER QUALITY TREATMENT IS REQUIRED PER STORMWATER CODE REQUIREMENT.
- CELL MUST BE PLANTED PER APPROVED LANDSCAPE PLAN.
 SOIL UNDER SHOULDERS OR PAVED AREAS MUST BE UNDISTURBED NATIVE SOIL OR
 APPROVED SOIL COMPACTED TO 95% DENSITY.
- FACE OF CURB TO TOP OF SLOPE MUST BE MIN 2'-0" FOR NON-MAJOR ARTERIAL STREET, MIN 4'-0" FOR MAJOR ARTERIAL STREET.
- PROVIDE MIN ONE INCH GAP BETWEEN TOP OF WALKS, CURBS, PAVEMENTS AND DRIVEWAYS AND TOP OF ARBORIST WOODCHIP MULCH.


REF STD SPEC SEC 7-21



NOT TO SCALE

INFILTRATING BIORETENTION WITH SLOPED SIDES & UNDER DRAIN






- 1. TYPICAL MAXIMUM SLOPE ALLOWED IS 2.5H=1V, 3H=1V MAX WHEN WITHIN 50-FEET OF INTERSECTIONS OR CURBLESS ROADWAY.
- 2. BIORETENTION OVERFLOW ELEVATIONS MUST BE SET BELOW SIDEWALK ELEVATION.
- 12"MIN OR 18" MIN IF WATER QUALITY TREATMENT IS REQUIRED PER STORMWATER CODE REQUIREMENT.
- 4 CELL MUST BE PLANTED PER APPROVED LANDSCAPE PLAN
- SOIL UNDER SHOULDERS OR PAVED AREAS MUST BE UNDISTURBED NATIVE SOIL OR APPROVED SOIL COMPACTED TO 95% DENSITY
- 6. FACE OF CURB TO TOP OF SLOPE MUST BE MIN 2'-0" FOR NON-MAJOR ARTERIAL STREET, MIN 4'-0" FOR MAJOR ARTERIAL STREET.
- PROVIDE MIN ONE INCH GAP BETWEEN TOP OF WALKS, CURBS, PAVEMENTS AND DRIVEWAYS AND TOP OF ARBORIST WOODCHIP MULCH.


REF STD SPEC SEC 7-21



NOT TO SCALE

NON-INFILTRATING BIORETENTION
WITH SLOPED SLIDES
& UNDER DRAIN





- TYPICAL MAXIMUM SLOPE ALLOWED IS 2.5H=1V, 3H=1V MAX WHEN WITHIN 50-FEET OF INTERSECTIONS OR CURBLESS ROADWAY.
- CONVEYANCE SWALE OVERFLOW ELEVATIONS MUST BE SET BELOW SIDEWALK ELEVATION.
- LONGITUDINAL SLOPE GREATER THAN OR EQUAL TO 4%, CHECK DAM REQUIRED.
 UNDISTURBED NATIVE SOIL OR APPROVED SOIL COMPACTED TO 95% DENSITY.
- PROVIDE MIN ONE INCH GAP BETWEEN TOP OF WALKS, CURBS, PAVEMENTS AND DRIVEWAYS AND TOP OF TREATMENT LAYER.


- PLANTING PER APPROVED LANDSCAPE PLAN. FACE OF CURB TO TOP OF SLOPE MUST BE MIN 2'-0" FOR NON-MAJOR ARTERIAL STREETS, MIN 4'-0" FOR MAJOR ARTERIAL STREETS.

REF STD SPEC SEC 7-21



NOT TO SCALE


VEGETATED CONVEYANCE SWALE (NOT FOR WATER QUALITY TREATMENT)





City of Seattle


TYPICAL DRAIN CURB CUT LOCATION FOR BIORETENTION WITH SLOPED SIDES


NOT TO SCALE











- 1. ALL FITTINGS MUST BE DUCTILE IRON
- 2. ALL EXCAVATION MUST PROVIDE A MINIMUM OF 1'-0" CLEAR AROUND PIPE AND FITTINGS.
 3. THESE PLANS ARE FOR DIP AND CIP WATERMAINS 12" OR SMALLER DIA OTHER SIZES AND TYPES SEE PROJECT DRAWINGS
- 4. REDUCED PRESSURE BACKFLOW ASSEMBLY (RPBA) MUST BE INSTALLED AS A UNIT (TWO SHUT-OFF VALVES, RELIEF PORT, TWO CHECK VALVES AND FOUR TEST COCKS). WHEN RPBA IS CONNECTED TO HYDRANT AND THE HOSE BIB FAUCET SAMPLE THEY MUST BE CAPPED WHEN NOT IN USE. ASSEMBLY MUST BE TESTED WHEN INSTALLED BY A WASHINGTON STATE CERTIFIED BACKFLOW ASSEMBLY TESTER (BAT) AND A CURRENT TEST REPORT MUST BE ON SITE. FOR INSTALLATION PROCEDURES CALL 684-3536.
- 5. ALL FITTINGS AND MATERIALS FURNISHED BY CONTRACTOR AND TO BE INSTALLED BY SPU MUST BE VERIFIED, INSPECTED AND ON THE JOB SITE PRIOR TO SHUTDOWN OF EXISTING MAIN. FAILURE TO MEET THIS REQUIREMENT COULD RESULT IN DELAYS.

LEGEND


- /1\ CLEAN & DISINFECTED POTABLE WATER HOSE ONLY. SIZE FLUSHING RISER PER TABLE IN STD SPEC SEC 7-11.3(12)
- 2. HYDRANT PERMIT REQUIRED
- 3. CHECK WITH SEWER UTILITY BEFORE DISCHARGE TO SEWERS
- CONTRACTOR TO DETERMINE ALIGNMENT, GRADE AND OUTSIDE DIAMETER OF EXISTING PIPE PRIOR TO INSTALLING NEW WATERMAIN. ENGINEER TO DETERMINE OUTSIDE DIAMÉTER OF EXISTING PIPE WHEN CONTRACTOR EXCAVATES TO DETERMINE ALIGNMENT & GRADE.
- ALL EXCAVATION, PIPE, FITTINGS (EXCEPT AS NOTED BELOW), OTHER MATERIAL, BEDDING, BACKFILL, COMPACTION & STREET RESTORATION BY CONTRACTOR. ALL MATERIALS MUST BE ON JOB SITE PRIOR TO SHUTDOWN OF EXISTING MAIN.
- (3.) INSTALLED BY CONTRACTOR
- \langle 4.angle connection pipe: contractor furnished, installed by SPU
- $\langle \mathsf{5.}
 angle$ watermain with plain ends
- $\langle 6
 angle$ mechanical joint sleeve with spacer cut to fit gap, furnished and inserted at time of connection by spu
- $\langle 7.
 angle$ TAPPING SLEEVE & TAPPING VALVE FURNISHED AND INSTALLED BY SPU
- $\langle 8.
 angle$ applies to pipes 4" through 12". All larger sizes to be addressed on drawings
- (9) MECHANICAL JOINT SLEEVE, FURNISHED BY CONTRACTOR AND INSTALLED BY SPU, SPACERS BY SPU WHERE REQUIRED.


REF STD SPEC SEC 7-11



NOT TO SCALE


CONNECTIONS TO **EXISTING WATERMAINS**





EXISTING PLUGGED TEE OR CROSS

NEW PLUGGED TEE OR CROSS



CONNECTIONS TO EXISTING TEE OR CROSS- PLAN VIEW


NOTE:

 $\overline{\langle X \rangle}$ = SEE STD PLAN NO 300a FOR LEGEND

TABLE

SIZE OF WATERMAIN	DISTURBANCE ZONE
UP TO & INCLUDING 10"ø	10'-0"
OVER 10"ø	12'-0"

^{*} SPU MAY INCREASE DISTURBANCE ZONE. SEE CONTRACT DOCUMENTS




REF STD SPEC SEC 7-11



NOT TO SCALE

CONNECTIONS TO EXISTING WATERMAINS





REF STD SPEC SEC 1-07.17



NOT TO SCALE

WATER SERVICE RELOCATION FOR UP TO 2" SERVICE PIPE THROUGH BIORETENTION






- 1. HORIZONTAL SETBACK DISTANCE FROM THE WATER MAIN (MEASURED FROM THE EDGE OF THE PIPE TO THE EDGE OF ANY BIORETENTION CELL) MUST BE MINIMUM 3.5 FEET FOR WATER MAIN UP TO AND INCLUDING 12"0 WATER MAIN. WATER MAIN LARGER THAN 12"0 MUST BE EVALUATED AND APPROVED ON A CASE BY CASE BASIS BY SEATTLE PUBLIC UTILITIES. IF SOIL WITHIN SETBACK IS DISTURBED A SUPPORT PLAN AND SOIL RE-COMPACTION TO 95% MIN COMPACTION WILL BE REQUIRED. EXCEPTIONS TO THE MINIMUM 3.5' HORIZONTAL SETBACK MUST BE APPROVED BY SEATTLE PUBLIC UTILITIES PLAN REVIEW SECTION AND WATER QUALITY DIVISION.
- 2. SOIL WITHIN THE ZONE OF INFLUENCE MUST NOT BE DISTURBED IN ORDER TO MAINTAIN STRUCTURAL SUPPORT TO THE WATER MAIN.
 3. BIORETENTION CELL MUST MAINTAIN 3' MIN CLEARANCE FROM THE EDGE OF ANY EXISTING FIRE HYDRANT SERVICE LINE TO THE EDGE OF THE BIORETENTION. FOR THE FIRE HYDRANT OPERATION THERE MUST BE A 4' MIN CLEARANCE AROUND THE FIRE HYDRANT WHERE NOTHING CAN BE AS TALL AS THE FIRE HYDRANT OPENING NUT.
- 4. BIORETENTION CELL MUST MAINTAIN 2' MIN CLEARANCE FROM THE EDGE OF THE BIORETENTION TO THE EDGE OF THE EXISTING 4" OR LARGER WATER SERVICE LINE OR SERVICE VAULT.
- 5. SEE STANDARD PLAN NO 292, 293A AND 293B FOR BIORETENTION REQUIREMENTS.
- 6. HORIZONTAL SETBACK DISTANCE BETWEEN EXISTING WATER MAIN AND THE BIORETENTION SSD PIPE MUST COMPLY WITH STD PLAN NO 286A. EXCEPTION TO STD PLAN NO 286A PARALLEL INSTALLATION APPLIES IF THE UNDER DRAIN PIPE ONLY RECEIVES TREATED RUNOFF PER STORMWATER CODE REQUIREMENTS FOR WATER QUALITY TREATMENT.

REF STD SPEC SEC 1-07.17




NOT TO SCALE

WATERMAIN SETBACK REQUIREMENT FOR C.I. LEAD JOINT AND D.I. SLIP JOINT PIPE




DETAIL





NOT TO SCALE


City of Seattle




STANDARD PLAN NO 311b










- 1.) UNION POINT 2' OUTSIDE OF VAULT/METER BOX, 2' FROM R/W MARGIN UNLESS OTHERWISE NOTED ON PLANS.
- (2.) 5' CLEARANCE MINIMUM FROM EDGE OF NEW OR EXISTING TREES. IF EXCAVATION IS REQUIRED WITHIN ROOT ZONE OF EXISTING TREES, THE EXCAVATION MUST BE ACCOMPLISHED BY HAND METHODS, CONDUCTED TO PREVENT DAMAGE TO FEEDER AND SURFACE ROOTS, AND MINIMIZE COMPACTION OF SOILS.
- (3.) 5' CLEAR FROM EDGE OF POLES.
- 4. 2' CLEAR FROM EDGE OF DRIVEWAY OR ADA RAMP WING.
- (5.) WATER SERVICE NOT TO BE INSTALLED IN DRIVEWAY, BEHIND ADA RAMP, OR STREET CORNER.
- SIDE SEWER HORIZONTAL
 CLEARANCE 10' FOR CIP,
 GALVANIZED OR PLASTIC WATER
 PIPE OR 5' FOR DIP OR COPPER
 WATER PIPE.
- (7.) SIDE SEWER VERTICAL CLEARANCE 1.5' MIN.
- (8.) VAULT HORIZONTAL CLEARANCE 3' MIN FROM OTHER UTILITIES. UNLESS OTHERWISE NOTED IN STD _ SPECS.
- VERTICAL CLEARANCE 12" MIN FOR ALL OTHER UTILITY CROSSINGS UNLESS OTHERWISE NOTED IN STD SPECS
- (10) ALLOWABLE LOCATION OF WATER SERVICE VAULT, 2' MINIMUM CLEAR OF BACK OF CURB.

PERMIT REQUIREMENTS WILL
DETERMINE LOCATION AND ORIENTATION
OF ALL SERVICE VAULTS & METER
BOXES IN THE RIGHT OF WAY. VAULTS
& METER BOXES SHOWN ON THIS STD
PLAN ARE FOR GRAPHICAL PURPOSES
ONLY.

EXCEPTIONS TO THE STANDARDS LOCATIONS REQUIRE CITY REVIEW AND APPROVAL.





REF STD SPEC SEC 1-07.17(2)




NOT TO SCALE

CLEARANCES FOR TYPICAL WATER SERVICE VAULTS & METER BOXES





OPERATING NUT EXTENSION DETAIL



- NOTES:


 1. FRAME AND COVER MUST BE TESTED FOR ACCURACY OF FIT AND MUST BE MARKED IN SETS FOR DELIVERY

 2. CASTINGS AND EXTENSIONS MUST BE HOT-DIPPED IN
- ASPHALTIC VARNISH ROYSTON ROSKOTE #612XM OR 2 COATS OF MASTIC ROYSTON INSIDE AND OUT.


 3. VALVE BOXES MUST BE EAST JORDAN: COVER & TOP
- SECTION #3664, BOTTOM SECTION #8555; OR OLYMPIC FOUNDRY: LID #1908-33, TOP SECTION #1106-33, BASE SECTION #1301-33
- 4. ALL CASTINGS MUST BE DUCTILE OR GREY CAST IRON


LEGEND:

- AN OPERATING NUT EXTENSION MUST BE INSTALLED WHEN THE GROUND SURFACE IS MORE THAN $2^{\prime}-6^{\prime\prime}$ ABOVE THE VALVE OPERATING NUT. THE OPERATING NUT EXTENSION MUST EXTEND INTO THE TOP SECTION OF THE STANDARD VALVE BOX AND MUST CLEAR THE BOTTOM OF THE LID BY 6" MIN
- $\overline{\langle 2. \rangle}$ EXTENSION PIECES (WHEN USED) MUST CONFORM TO MINIMUM THICKNESS REQUIREMENTS AND MUST FIT INTO THE TOP SECTION AND OVER THE BOTTOM SECTION



EXTENSION PIECE 2 WHEN REQUIRED






REF STD SPEC SEC 7-12, 9-30




NOT TO SCALE

CAST IRON VALVE BOX & OPERATING NUT EXTENSION



2" OR SMALLER WATER SERVICE CONNECTION



4" OR LARGER WATER SERVICE CONNECTION (NTS)

NOTES:

- SPU PROVIDES MATERIALS, INSTALLS, AND CONNECTS SERVICES 2" AND SMALLER WITH CONTRACTOR ASSISTANCE.
 CONTRACTOR PROVIDES MATERIALS FOR SERVICES 4" AND LARGER EXCEPT FOR SLEEVE TO EXISTING PIPE. SEE STANDARD SPECIFICATIONS SECTION 7-15.

- 2. CURB STOP IS INSTALLED FOR 1.5" AND 2" SERVICES. CONTRACTOR TO INSTALL VALVE BOX PER STD PLAN 315.

 3. NON-COPPER SERVICES MUST BE RENEWED UP TO THE WATER METER.


 4. WHERE INDICATED IN DRAWINGS OR THE WATER SERVICE TABLE, THE WATER SERVICE MUST BE RENEWED TO THE EXISTING
- 5. BEDDING AND BACKFILL OF SERVICE LINES MUST BE THE SAME AS THE WATER MAIN.
 6. LIMITS OF EXCAVATION MAY BE LARGER. REFER TO DRAWINGS FOR ACTUAL EXTENTS OF WATER SERVICE INSTALLATION.


REF STD SPEC SEC 7-11, 7-15




NOT TO SCALE

WATER SERVICE CONNECTION TO NEW WATER MAIN







Т	Υ	Ρ	Έ	С

	TYPE "C" BLOCKING FOR 111/4", 221/2", 45" AND 90" VERTICAL BENDS THRUST BLOCK AREA IN SQUARE FEET											
	SOIL	FIRM SILT OR FIRM SILTY SAND				COMPACT SAND			COMPACT SAND & GRAVEL			
	FITTING	90° BEND	TEE, 45° BEND & DEAD END	11¼* & 22½* BEND	90° BEND	TEE, 45° BEND & DEAD END	11¼° & 22½° BEND	90° BEND	TEE, 45° BEND & DEAD END	11¼* & 22½* BEND		
Щ	4"	5.8	4.2	1.7	2.9	2.1	1.0	2.2	1.6	1.0		
SIZE	6'	13.3	9.4	3.8	6.7	4.7	1.9	5.0	3.5	1.4		
PIPE	8"	23.3	16.7	6.7	11.7	8.4	3.4	8.8	6.3	2.5		
	12"	53.0	37.5	15.0	26.5	18.8	7.5	20.0	14.0	5.6		
	AREAS CALCULATED ON 300 PSI TEST PRESSURE AND 3'-0" MIN COVER OVER WATERMAIN											


- 1. LOCATION AND SIZE OF BLOCKING FOR PIPE LARGER THAN 12" DIAMETER AND FOR SOIL TYPES DIFFERENT THAN SHOWN MUST BE DETERMINED BY THE ENGINEER.
- ALL BLOCKING FOR VERTICAL FITTINGS (POURED IN PLACE) MUST BEAR AGAINST UNDISTURBED NATIVE GROUND.
- 3. ALL POURED THRUST BLOCKS MUST BE BACKFILLED AFTER MIN. 1 DAY. PRESSURE TESTING MUST OCCUR AFTER CONCRETE HAS REACHED f'c.
- 4. ALL BLOCKING MUST BE CONCRETE CL 3000.
- AFTER INSTALLATION, SHACKLE RODS & TURNBUCKLES MUST BE CLEANED AND COATED WITH 2 COATS OF ASPHALTIC VARNISH, ROYSTON ROYKOTE #612M OR APPROVED EQUAL.
- 6. SHACKLE RODS MUST BE FUSION BONDED EPOXY COATED ROUND MILD STEEL, ASTM A 36, WITH THREADS ON ENDS ONLY.
- BLOCKING AGAINST FITTINGS MUST BEAR AGAINST THE GREATEST FITTING SURFACE AREA POSSIBLE, BUT MUST NOT COVER OR ENCLOSE BELL ENDS, JOINT BOLTS OR GLANDS. REASONABLE ACCESS TO BOLTS AND GLANDS MUST BE PROVIDED.

REF STD SPEC SEC 7-11



NOT TO SCALE

WATERMAIN THRUST BLOCKING VERTICAL FITTINGS



	THRUST BLOCK AREA IN SQUARE FEET (SEE STD PLAN NO 331B)											١		
	SOIL	OIL FIRM SILT OR FIRM SILTY SAND					COMPACT SAND				COMPACT SAND & GRAVEL			
PIPE SIZE	FITTING	90° BEND	TEE	45° BEND CAP OR PLUG	11½° & 22½° BEND	90° BEND	TEE	45° BEND CAP OR PLUG	11½° & 22½° BEND	90° BEND	TEE	45° BEND CAP OR PLUG	11¼* & 22½* BEND	
	4"	7.0	4.2	4.2	1.7	2.9	2.1	2.1	1.0	2.2	1.6	1.6	1.0	
	6"	13.3	9.4	9.4	3.8	6.7	4.7	4.7	1.9	5.0	3.5	3.5	1.4	
	8"	23.3	16.7	16.7	6.7	11.7	8.4	8.4	3.4	8.8	6.3	6.3	2.5	
	12"	53.0	37.5	37.5	15.0	26.5	18.8	18.8	7.5	20.0	14.0	14.0	5.6	
	AREAS CALCULATED ON 300 PSI TEST PRESSURE AND 3'-0" MIN COVER OVER WATERMAIN													


ECOLOGY BLOCKS, PER STD PLAN NO 460, MAY BE USED, AT THE DISCRETION OF THE ENGINEER ONLY, IN LIEU OF POURED-IN-PLACE BLOCKING FOR FITTINGS IN HEAVY OUTLINED PORTION OF TABLE. ECOLOGY BLOCKS USED FOR THRUST BLOCKING AT TEES MUST TRANSFER LOAD TO THE PIPE BODY PER SPEC SECTION 7-11.3(13).

REF STD SPEC SEC 7-11



NOT TO SCALE

WATERMAIN THRUST BLOCKING HORIZONTAL FITTINGS




- LOCATION AND SIZE OF BLOCKING FOR PIPE LARGER THAN 12" DIAMETER AND FOR SOIL TYPES DIFFERENT THAN SHOWN MUST BE DETERMINED BY THE ENGINEER.
- 2. ALL BLOCKING FOR HORIZONTAL FITTINGS (POURED IN PLACE) MUST BEAR AGAINST UNDISTURBED NATIVE GROUND.
- 3. ALL POURED THRUST BLOCKS MUST BE BACKFILLED AFTER MIN. 1 DAY. PRESSURE TESTING MUST OCCUR AFTER CONCRETE HAS REACHED f'c.
- 4. ALL BLOCKING TO BE CONCRETE CL 3000.
- BLOCKING AGAINST FITTINGS MUST BEAR AGAINST THE GREATEST FITTING SURFACE AREA POSSIBLE, BUT MUST NOT COVER OR ENCLOSE BELL ENDS, JOINT BOLTS OR GLANDS. ACCESS TO BOLTS AND GLANDS MUST BE PROVIDED.
- 6. ALL HORIZONTAL BLOCKING THRUST AREAS MUST BE CENTERED ON PIPE.
- 7. WHERE POURED-IN-PLACE BLOCKING IS REQUIRED AT A POINT OF CONNECTION TO AN EXISTING WATERMAIN, THE BLOCKING MUST BE INSTALLED PRIOR TO CONNECTION.
- 8. TEMPORARY BLOCKING, IF USED, MUST BE APPROVED BY ENGINEER.


REF STD SPEC SEC 7-11





NOT TO SCALE

WATERMAIN THRUST BLOCKING HORIZONTAL FITTINGS











REF STD SPEC SEC 7-20



NOT TO SCALE

REBUILD EXISTING BRICK WATER VALVE CHAMBER






TYPE 361b VALVE CHAMBER


FRAME & COVER IN

PEDESTRIAN PATHWAYS





NOT TO SCALE

City of Seattle



VEHICULAR TRAVELWAYS






SECTION A-A f=MACHINED FINISH

REF STD SPEC SEC 7-12, 7-20



NOT TO SCALE

TYPE 361d WATER VALVE REPLACEMENT COVER IN PEDESTRIAN PATHWAYS



REF STD SPEC SEC 7-11



NOT TO SCALE

JOINT BONDING FOR DIP WATERMAINS & JOINT BONDING DETAIL #10 AWG, BLACK TEST STATION WIRE

#10 AWG, BLACK TEST STATION WIRE

#10 AWG, YELLOW

#10 AWG, YELLOW

11/40 CONDUIT TO TEST

STATION SEE STD PLAN


NO 360

TERMINATE END (
OF CONDUIT AS
CLOSE TO MAIN
AS POSSIBLE


ZINC REFERENCE CELL PLACE
AT SPRING LINE OR BELOW,

4"±2" FROM WATER MAIN

STANDARD 3-WIRE TEST STATION



INSULATING COUPLING 5-WIRE TEST STATION



INSULATING FLANGE 5-WIRE TEST STATION

NOTE:


WIRE INSTALLATION PER STD SPEC SEC 9-30.12(3)

REF STD SPEC SEC 7-11.3(15), 9-30.12




NOT TO SCALE

ELECTROLYSIS TEST STATION WIRE INSTALLATION DETAILS



TYPICAL SINGLE HORIZONTAL ANODE INSTALLATION



TYPICAL SINGLE VERTICAL ANODE INSTALLATION

NOTES:


- SPU CORROSION PROTECTION MAY SPECIFY TYPE AND REQUIRED SPACING OF ANODE(S)
 LONGITUDINALLY ALONG WATER MAIN TO BE SHOWN IN DESIGN DRAWINGS. MAXIMUM SPACING
 MUST BE 36' UNLESS OTHERWISE NOTED ON PLANS.
- FOR VERTICAL ANODE INSTALLATION, IF ANODE IS NOT PRE-PACKAGED, BARE ANODE MUST BE INSTALLED W/MIN 6" SACRIFICIAL ANODE BACKFILL PER SPEC SECTION 9-30.(7), AROUND ALL SIDES OF ANODE
- 3. ANODE SIZE MUST BE 17LB HIGH POTENTIAL MAGNESIUM ANODE, UNLESS OTHERWISE NOTED ON THE PLANS.
- 4. PLACE RED "CAUTION" OR "DANGER" TAPE 6" OVER ANODE WIRES. TAPE MUST BE MIN 3" WIDE.
- 5. BACKFILL OVER ANODE WITH SUITABLE NATIVE MATERIAL OR APPROVED EQUAL.


REF STD SPEC SEC 7-11, 9-30



NOT TO SCALE

SACRIFICIAL ANODE BONDED TO PIPE INSTALLATION DETAILS





TERMINAL BOARD, DETAIL A

NOTES:


- 1. REQUIRED SPACING OF ANODE(S) TO BE SHOWN IN DESIGN DRAWINGS.
- FOR VERTICAL INSTALLATION, IF ANODE IS NOT PRE-PACKAGED, BARE ANODE MUST BE INSTALLED W/ MIN 6" SACRIFICIAL ANODE BACKFILL PER SPEC SECTION 9-30.9(7), AROUND ALL SIDES OF ANODE.
- ANODE SIZE MUST BE 17LB HIGH POTENTIAL MAGNESIUM ANODE, UNLESS OTHERWISE NOTED ON THE PLANS.
- PLACE RED "CAUTION" OR "DANGER" TAPE 6" OVER ANODE WIRES AND CONDUIT. TAPE MUST BE MIN 3" WIDE.
- 5. BACKFILL OVER ANODE WITH SUITABLE NATIVE MATERIAL OR APPROVED EQUAL.

REF STD SPEC SEC 7-11, 9-30



NOT TO SCALE

SACRIFICIAL ANODE INSTALLATION DETAILS - MULTIPLE ANODES CONNECTED AT TEST STATION



NOTE:

- POSITIVE DRAINAGE FLOW SLOPING FROM THE ROW LINE TO THE TOP OF CURB MUST BE PROVIDED.
 - SEE RIGHT OF WAY IMPROVEMENT MANUAL FOR DIMENSIONS.

 - ** UNLESS OTHERWISE APPROVED BY THE ENGINEER.

 *** 2% MAXIMUM, 0.5% MINIMUM; USE 1.5% UNLESS OTHERWISE
 SHOWN IN CONTRACT OR APPROVED BY THE ENGINEER.

REF STD SPEC SEC 2-04




NOT TO SCALE

HALF SECTION, GRADING

RESIDENTIAL PAVEMENT


SECTIONS



2026 Draft Edition City of Seattle Standard Plans for Municipal Construction

NOT TO SCALE


City of Seattle




NOTES:

IF CONC THICKNESS IS 9 INCH OR GREATER
OPTIONAL KEYWAY MAY BE USED SEE STD PLANS
NO 405c & 405d FOR DETAILS


OPTIONAL KEYWAY FOR LONGITUDINAL JOINT



402A-ROADWAY CEMENT CONCRETE PAVEMENT ON CRUSHED ROCK



402B-HOT MIX ASPHALT ON ROADWAY CEMENT CONCRETE BASE ON CRUSHED ROCK



402C-HOT MIX ASPHALT ON CRUSHED ROCK

HMA DESIGN CRITERIA:


- 1. 10 MILLION ESAL'S UNLESS OTHERWISE SPECIFIED IN CONTRACT DOCUMENTS.
- 2. ASPHALT PG 58H-22 UNLESS OTHERWISE SPECIFIED IN CONTRACT DOCUMENTS.
- WARM MIX ASPHALT MAY BE USED IN PLACE OF HMA WHERE SHOWN ON THE DRAWINGS.
 PROTECT ADJACENT PANELS FROM DAMAGE DUE TO UNDERMINING DURING EXCAVATION &
- PLACEMENT OF SUBGRADE. SEE SPEC SECTION 1-07.13.

REF STD SPEC SEC 4-04, 5-04, 5-05, 8-04




NOT TO SCALE

COMMERCIAL AND ARTERIAL PAVEMENT SECTIONS



CONCRETE ALLEY PAVEMENT



PERVIOUS CONCRETE PAVEMENT

NOTES:

- WHEN ALLEY PAVEMENT IS 16'-0" OR WIDER PLACE CONSTRUCTION JOINT WITH TIE BAR PER STD PLAN NO 405 ALONG CENTERLINE OF ALLEY.
- FOR ADA ACCESSIBLE ACCESS TO ENTRY IN ALLEY CONSIDER ALTERNATIVE DESIGN; SUBJECT TO APPROVAL BY THE ENGINEER.

 8" OR AS SHOWN IN CONTRACT OR APPROVAL BY THE ENGINEER.

 MIN CROSS SLOPE IS 1%. MAX CROSS SLOPE IS 2%.

 PERMEABLE BALLAST MUST BE MINERAL AGGREGATE TYPE 13, COS STD


- SPEC 9.03-13, UNLESS DETERMINED OTHERWISE BY ENGINEER.
- FOR PERVIOUS CONCRETE ALLEYS, CONTRACTION JOINTS MUST NOT EXCEED 12 FT. FOR PAVEMENT THICKNESS OF 9 IN. OR LESS. FOR THICKER PAVEMENT, CONTRACTION JOINTS MAY BE 15 FT.

REF STD SPEC SEC 5-06, 8-17, 8-19




NOT TO SCALE

ROADWAY CEMENT CONCRETE **ALLEY PAVEMENTS**



TYPICAL PATCH FOR RIGID PAVEMENT



TYPICAL PATCH FOR FLEXIBLE PAVEMENT

NOTES:


- DEPTH OF RESTORATION MUST MEET THE REQUIREMENTS OF "RIGHT OF WAY OPENING AND RESTORATION RULES".
- FOR RIGID PAVEMENT (FULL DEPTH), WIDTH OF RESTORATION MUST EXTEND TO FULL PANEL WIDTH, OR AS REQUIRED IN THE "RIGHT OF WAY OPENING AND RESTORATION RULES" FOR OVERSIZED OR NON-STANDARD PANELS.
- FOR FLEXIBLE PAVEMENT (FULL DEPTH & OVERLAY) RESTORATION WIDTH MUST MEET REQUIREMENTS OF STANDARD PLAN NO 404c AND THE "RIGHT OF WAY OPENING AND RESTORATION RULES".

REF STD SPEC SEC 2-02, 5-04, 5-05



NOT TO SCALE

PAVEMENT PATCHING



NOTES:

1. DEPTH OF RESTORATION MUST MEET THE REQUIREMENTS OF THE "RIGHT OF WAY OPENING AND RESTORATION RILLES"

HOT MIX ASPHALT OVER SHEET ASPHALT, BRICK, OR STONE BLOCK PAVEMENT
HALF SECTION

OPENING AND RESTORATION RULES".


2. WIDTH OF RESTORATION MUST EXTEND TO FULL PANEL WIDTH, OR AS REQUIRED IN THE "RIGHT OF WAY OPENING AND RESTORATION RULES" FOR OVERSIZED OR NON-STANDARD PANELS.

REF STD SPEC SEC 2-02, 5-04, 5-05



NOT TO SCALE

PAVEMENT PATCHING



- NOTES:

 1. DUE TO POTENTIAL LOSS OF SOIL STRENGTH IN AREAS ADJACENT TO TRENCH OPENINGS, PAVEMENT REMOVAL MUST BE WIDENED TO INCLUDE THE TONIC OF INFILITEMENT.
- THE ZONE OF INFLUENCE.


 2. SEE "RIGHT-OF-WAY OPENING AND RESTORATION RULES" FOR MORE INFORMATION ON PAVEMENT OPENINGS ZONE OF INFLUENCE. HTTP://WWW.SEATTLE.GOV/TRANSPORTATION/STUSE_PAVEMENTOPEN.HTM


REF STD SPEC SEC 2-02, 2-04



NOT TO SCALE

PAVEMENT OPENING ZONE OF INFLUENCE






15'-0"MAX IF D>9" TRANSVERSE 12'-0"MAX IF D<9" CONTRACTION OR CONSTRUCTION JOINT (TYP.) (SEE SECTION WIDTH LANE LONGITUDINAL CONTRACTION OR CONSTRUCTION JOINTS (TYP.) (SEE SECTION WIDTH VIEWS) TIE BARS ~ 5%" BARS X 30" ON 36" LANE CENTERS. TYPICAL ALL LANES. WIDTH DOWEL BARS. SEE TABLE FOR SIZES & LANE SPACING. TYPICAL ALL LANES UNLESS NOTED IN THE DWG. PLAN VIEW LONGITUDINAL JOINTS (SEE SECTION VIEWS) PANEL REPLACEMENT


NOTES:

- 1. DO NOT PLACE LONGITUDINAL JOINTS OR SKEWED JOINTS WITHIN BIKE LANES.
- WHEN A JOINT IS WITHIN 18 INCHES OF A CASTING JOINTS SHOULD BE SKEWED TO MEET THE CASTING AT 90 DEGREES UNLESS OTHERWISE DIRECTED BY THE ENGINEER OR SHOWN ON THE DRAWINGS.
- SEE STD PLAN NO 406 OR DRAWINGS FOR REBAR DETAIL AROUND CASTING
- DOWEL BARS MUST NOT BE PLACED WITHIN 15 INCHES OF THE EDGE OF PAVEMENT OR A PARALLEL JOINT.
- DOWEL BARS NOT REQUIRED FOR RESIDENTIAL PAVEMENT SECTIONS. SEE STD PLAN NO 401.
- DO NOT INSTALL PREMOLDED JOINT FILLER IN CONSTRUCTION JOINTS OF CEMENT CONCRETE BASE PAVEMENTS.
- CONTRACTION JOINTS IN CEMENT CONCRETE BASE PAVEMENTS MUST BE WEAKENED PLANE JOINTS PER STD SPEC SEC 5-05.3(8)A4.


DEPTH (D) OF RDWY CEM. CONC	SOLID STEEL DOWEL BAR SIZE OUTSIDE DIAMETER (OD) X LENGTH (L) @ ON CENTER (OC)	TUBULAR DOWEL BAR SIZE OUTSIDE DIAMETER (OD), WALL THICKNESS X LENGTH (L) @ ON CENTER (OC)
8" ≤ D <9"	1.00" OD X 18" L @ 12" OC	1.375" OD, 0.120: MIN X 18" L @ 12" OC
9" ≤ D <11"	1.25" OD X 18" L @ 12" OC	1.375" OD, 0.120: MIN X 18" L @ 12" OC
11" ≤ D	1.50" OD X 18" L @ 12" OC	1.625" OD, 0.120: MIN X 18" L @ 12" OC




SECTION VIEW LONGITUDINAL CONTRACTION JOINT



LONGITUDINAL CONSTRUCTION JOINT



SECTION VIEW
TRANSVERSE CONTRACTION JOINT



SECTION VIEW
TRANSVERSE CONSTRUCTION JOINT


REF STD SPEC SEC 5-05




NOT TO SCALE

ROADWAY CONCRETE PAVEMENT JOINTS

EPOXY COATING



BY THE ENGINEER



KEYWAY DETAIL LONGITUDINAL JOINT WITH KEYWAY (OPTIONAL FOR ≥9 INCHES ONLY)


NOTE:
USE OF OPTIONAL KEYWAY MAY BE REVOKED BY THE ENGINEER AT ANYTIME DUE TO QUALITY CONTROL ISSUES WITH MAINTAINING PLACEMENT REQUIREMENTS WITHIN $\pm \frac{3}{2}$ INCH VERTICALLY.


REF STD SPEC SEC 5-05




NOT TO SCALE

THROUGH JOINTS AND OPTIONAL KEYWAYS FOR **CEMENT CONCRETE ROADWAY**








10" 21/2" 5" 21/2" -1½"R 1½"R-EXISTING PAVEMENT

EXTRUDED ASPHALT CONCRETE CURB



EXTRUDED CEMENT CONCRETE CURB

NOTE:

- ALTERNATELY, THE USE OF EPOXY BONDING AGENT, IN PLACE OF #3
- DEFORMED BARS, WILL BE ALLOWED.


 2. EXTRUDED CURB MUST NOT BE USED IN SDOT MANAGED PUBLIC RIGHT OF WAY.


REF STD SPEC SEC 8-06





NOT TO SCALE

EXTRUDED CURB










TYPICAL SIDEWALK & CURB RAMP DETAIL



SECTION B-B

NOTES:

- . 3/8" THROUGH AND CONTRACTION JOINTS MUST BE LOCATED AS REQUIRED BY SECTION 8-14.3(6).
- SAWCUT SCORING MUST MATCH PATTERN IN ADJACENT EXISTING SIDEWALK OR MUST BE A 2' SQUARE SCORING PATTERN UNLESS OTHERWISE OTHERWISE APPROVED BY THE ENGINEER.
- 3. FOR CURB RAMPS, SEE STANDARD PLANS 422a TO 422I.
- 4. FOR TREE PITS, SEE STANDARD PLAN NO 424.
- 5. PROVIDE 12" MINIMUM BETWEEN EDGE OF RAMP WING AND PLANTING STRIP. AREA BEHIND RAMP WING MUST BE FILLED IN WITH SIDEWALK, AS LANDSCAPING IS NOT ALLOWED.
- 6. ALL SIDEWALK MUST BE NON-ROADWAY CEM CONC W/ 25% POZZOLANS.
- 7. 6'-0" MINIMUM CONTINUOUS SIDEWALK MUST BE MAINTAINED AROUND CORNERS.


REF STD SPEC SEC 8-14



NOT TO SCALE

CONCRETE SIDEWALK DETAILS

REV DATE: NOV 2025




"H" MUST BE 6" FROM FINISHED ROADWAY GRADE UNLESS OTHERWISE SPECIFIED


REF STD SPEC SEC 8-14





NOT TO SCALE


SIDEWALK WITH MONOLITHIC CURB












CURB RAMP DETAILS

NOTES: RAMP CENTERLINE MUST BE RADIAL/PERPENDICULAR TO THE ALIGNMENT OF THE FACE OF CURB. THE SLOPE ON THE LANDING MUST BE A MINIMUM OF 0.5% IN ANY ONE DIRECTION AND MUST NOT EXCEED 2% BUILDING OR OTHER OBSTRUCTION IN THE APPLICABLE DIRECTION OF TRAVEL. UPPER LANDING AT THE TOP OF THE CURB RAMP MUST MATCH THE FULL WIDTH OF THE RAMP AND MUST HAVE A MINIMUM DEPTH OF 4'-0" FOLL WIDTH OF THE KAMP AND MUST HAVE A MINIMUM DEPTH OF 4'-O". IF THE LANDING IS LIMITED AT THE BACK-OF-SIDEWALK BY A PERMANENT VERTICAL BARRIER, THE DEPTH OF THE TURNING SPACE MUST BE 5'-O" MINIMUM, MEASURED PARALLEL TO THE RUN OF THE CLEAR SPACE AT THE BOTTOM OF THE RAMP MUST BE 5-O" MINIMUM IN WIDTH AND MUST EXTEND A MINIMUM OF 4'-O' BEYOND THE RAMP LOWER GRADE BREAK. THE CLEAR SPACE MUST FALL WHOLLY WITHIN THE LEGAL CROSSWALK, MARKED OR UNMARKED. THE CLEAR SPACE MUST FIT BEHIND LINES EXTENDING FROM THE FACE OF CURB RUNNING PARALLEL TO EACH ROADWAY. THERE IS NO ALLOWABLE EXEMPTION FOR MINIMUM CLEAR SPACE REQUIREMENTS AT SHARED DIAGONAL PERPENDICULAR CURB UPPER LANDING SEE NOTE 2 DETECTABLE WARNING STD PLAN 422K. SLOPE SEE NOTE 5 SIDEWALK MAX 10% RAMP SEE NOTE ♦ THROUGH JOINT DIAGONAL PERPENDICULAR CURB (TYP) RAMPS. DETECTABLE WARNING SURFACE MUST BE 8" MAXIMUM FROM FACE OF CURB. WINGS MUST HAVE A MAXIMUM SLOPE OF 10%. WINGS MUST HAVE A BRUSHED FINISH PARALLEL TO THE <u> ও</u> CURB. THE CONCRETE WALK THICKENED EDGE ALONG THE CURB THICKENED EDGE ALONG THE CORB MUST CONTINUE THROUGH EACH WING. WINGS MUST BE MONOLITHIC WITH THE CURB RAMP RUN. RAMP SURFACE MUST HAVE A HEAVY BROOM BRUSHED SURFACE PARALLEL TO THE CLIBB TO THE CURB REFER TO DETAILS 422K AND 422L FOR GENERAL NOTES AND TYPICAL SECTIONS. MY Ö 10% MAX SLOPE MAX SLOPE IN EITHER DIRECTION CLEAR SPACE, SEE NOTE 4 FACE OF CURB EXTENDED (TYP)-SHARED DIAGONAL PERPENDICULAR CURB RAMP (TYPE 422F) PAY LIMIT PAY LIMITS 422F CURB RAMP LOCATIONS CW CW CW LSCAPE **REF STD SPEC SEC 8-14**

NOT TO SCALE


City of Seattle




NOTES:

- SIZE, SHAPE, AND/OR DIMENSIONS OF CHANNELIZING ISLANDS OR PEDESTRIAN REFUGE ISLANDS MAY VARY DETAILS SHOWN ARE INTENDED TO SHOW MINIMUM REQUIRED CLEARANCES AND DETECTABLE WARNING
- CLEARANCES AND DETECTABLE WARNING SURFACE PLACEMENT LOCATIONS.
 ACCESS THROUGH CHANNELIZING ISLANDS OR PEDESTRIAN REFUGE ISLANDS MAY BE CUT-THROUGH OR ACCESS MAY BE PROVIDED USING STANDARD CURB RAMP DETAILS.
 AT PEDESTRIAN REFUGE ISLANDS, DETECTABLE WARNING MUST NOT TO BE INSTALLED IF THE REFUGE AREA IS LESS THAN 6'-O" IN DEPTH (IN THE DIRECTION OF TRAVEL).
 PROVIDE A MINIMUM 4'-O" WIDTH x 4'-O" DEPTH CLEAR SPACE FOR ACCESS FROM THE CHANNELIZING ISLAND OR PEDESTRIAN REFUGE ISLAND FOR EACH CROSSWALK.
- REFUGE ISLAND FOR EACH CROSSWALK.








ISLAND CUT-THROUGHS (TYPE 422H)

REF STD SPEC SEC 8-14





NOT TO SCALE


CURB RAMP DETALS



TACTILE DIRECTIONAL INDICATOR - SURFACE APPLIED







NOTES:

- STRIP CENTERLINE MUST BE PARALLEL TO THE ALIGNMENT OF THE PEDESTRIAN ACCESS ROUTE.
- METHYL METHACRYLATE (MMA) TACTILE DIRECTIONAL INDICATOR MUST COMPLY WITH ALL THE DIMENSIONS RANGES SHOWN ON THIS STANDARD PLAN FOR SURFACE APPLIED, AND MUST BE APPROVED BY THE ENGINEER. PLASTIC SURFACE MOUNT TACTILE DIRECTIONAL INDICATOR MAY BE USED IN LIEU OF CAST—IN—PLACE IF APPROVED BY THE ENGINEER.

REF STD SPEC SEC 8-14, 9-36



NOT TO SCALE

TACTILE WARNING SURFACE **INDICATORS**


400 STREET PAVING & APPURTENANCES

CURB RAMP GENERAL NOTES:


- TWO CURB RAMPS MUST BE INSTALLED AT EACH CORNER UNLESS
 OTHERWISE DIRECTED BY ENGINEER. SHARED DIAGONAL PERPENDICULAR
 RAMPS MUST NOT BE INSTALLED UNLESS ALL OTHER DESIGN OPTIONS ARE
 UNABLE TO BE CONSTRUCTED DUE TO EXISTING SITE CONSTRAINTS.
- CURB RAMPS MUST BE AS CLOSELY ALIGNED WITH THE SIDEWALK AND THE PEDESTRIAN STREET CROSSING SERVED AS POSSIBLE.
- CURB RAMP MUST BE CONSTRUCTED WITH COMPANION RAMP ON OPPOSITE SIDE OF THE ROADWAY WHERE NO RAMP IS PROVIDED UNLESS OTHERWISE DIRECTED BY ENGINEER.
- 4. CURB RAMPS MUST HAVE A MAXIMUM RUNNING SLOPE OF 8.3% AND A MINIMUM WIDTH OF 4'-O" UNLESS OTHERWISE DIRECTED BY ENGINEER. THE CROSS SLOPE OF CURB RAMPS MUST BE A MAXIMUM OF 2%. CURB RAMPS ARE NOT REQUIRED TO EXCEED A LENGTH OF 15 FEET UNLESS OTHERWISE DIRECTED BY ENGINEER.*
- 5. GRADE BREAKS AT THE TOP AND THE BOTTOM OF CURB RAMP RUNS MUST BE PERPENDICULAR TO THE PATH OF TRAVEL. CURB RAMP RUNS ARE DEFINED BY RUNNING SLOPES THAT EXCEED 5% BUT ARE NO MORE THAN 8.3%. SURFACES ABUTTING AT CURB RAMP GRADE BREAKS MUST BE FLUSH.
- 6. AREAS ADJACENT TO CURB RAMPS OR CURB RAMP LANDINGS USABLE BY PEDESTRIANS MUST COMPLY WITH STANDARD PLAN SIDEWALK SLOPE LIMITS OR A CURB RAMP WING MUST BE PROVIDED AS SHOWN IN THE APPLICABLE CURB RAMP DETAILS. THE INSTALLATION OF CURBED EDGES MAY BE USED AT THE SIDES OR BACKS OF CURB RAMPS OR CURB RAMP LANDING WHERE THE ADJACENT SURFACE IS LANDSCAPED OR OTHERWISE NOT USABLE BY PEDESTRIANS.
- 7. THE COUNTER SLOPE OF THE GUTTER OR THE STREET AT THE BOTTOM OF CURB RAMP RUNS MUST BE 5% MAXIMUM. IF TURNING OR CHANGE OF ORIENTATION IS REQUIRED WITHIN THE PEDESTRIAN CROSSING AT THE BOTTOM OF CURB RAMP RUNS, THE SLOPE MUST BE 2% MAXIMUM IN ANY DIRECTION FOR A MINIMUM 4'-O"WIDTH X 4'-O"DEPTH MEASURED FROM THE RAMP BOTTOM GRADE BREAK.
- 8. CURB RAMPS WITH RUNS THAT TERMINATE AT THE ENTRANCE TO THE PEDESTRIAN STREET CROSSING MUST HAVE A CLEAR SPACE AT THE BOTTOM OF THE RAMP. "CLEAR SPACE" IS DEFINED AS A NAVIGABLE 4'-0" BY 4'-0" SPACE, EXTENDING FROM THE RAMP LOWER GRADE BREAK, THAT FALLS WHOLLY WITHIN THE LEGAL CROSSWALK, MARKED OR UNMARKED, AND OUTSIDE THE PARALLEL VEHICULAR TRAFFIC LANE.
- 9. A 4'-0" MINIMUM WIDTH UNOBSTRUCTED PEDESTRIAN ACCESS ROUTE MUST BE PROVIDED FROM EACH CURB RAMP, BLENDED TRANSITION, OF FLUSH TRANSITION TO THE LEGAL CROSSWALK THAT IS SERVED, MARKED OR UNMARKED, AND LOCATED OUTSIDE THE PARALLEL VERTICAL TRAFFIC LANE.
- 10. DETECTABLE WARNING MUST BE PROVIDED AT CURB RAMPS AND AT LOCATIONS WHERE THE SIDEWALK AND ROADWAY ARE FLUSH. THE DETECTABLE WARNING SURFACE MUST HAVE A TRUNCATED DOME PATTERN AS SHOWN, WITH A MINIMUM DEPTH OF 2'-O", AND MUST BE PLACED AT THE BACK OF CURB BUT NO MORE THAN 8" FROM THE FACE OF CURB FOR MONOLITHIC CURBS OR ATYPICAL CURB WIDTHS. DETECTABLE WARNING MUST MATCH THE WIDTH OF THE RAMP RUN OR THE OPENING WHERE THE SIDEWALK AND ROADWAY ARE FLUSH. THE TRUNCATED DOMES ON THE

- DETECTABLE WARNING SURFACE SHOULD ALIGN WITH THE CURB RAMP RUN OR THE DIRECTION OF TRAVEL. DOMES MAY BE ON A RADIAL GRID PATTERN WHERE RADIAL DETECTABLE WARNING SURFACE IS PLACED AT CURB RADII. DETECTABLE WARNING COLOR MUST BE "FEDERAL SAFETY YELLOW", UNLESS
- 11. DETECTABLE WARNING COLOR MUST BE "FEDERAL SAFETY YELLOW", UNLESS OTHERWISE DIRECTED BY THE ENGINEER.
- 12. DETECTABLE WARNING SURFACES MUST NOT BE CUT OR ALTERED TO FIT UNLESS OTHERWISE DIRECTED BY THE ENGINEER. IT APPROVED, CUT OR ALTER THE DETECTABLE WARNING SURFACE PER THE MANUFACTURER'S DIRECTIONS. DETECTABLE WARNING SURFACES PLACED AT CURB RADII MUST MATCH THE CURB RADII WITHOUT GAPS OR INCONSISTENCIES IN PLACEMENT.
- HANDHOLES, UTILITY CASTINGS, OR ANY OTHER SURFACE OBSTRUCTIONS MUST NOT BE INSTALLED IN THE CURB RAMP RUN(S) OR LANDING(S)

 UNLESS OTHERWISE DIRECTED BY THE ENGINEER. IF NECESSARY DUE TO EXISTING CONSTRAINTS, HANDHOLES, UTILITY CASTINGS, OR OTHER SURFACE OBSTRUCTIONS MAY BE LOCATED WITHIN A RAMP RUN, LANDING, OR TURNING SPACE BUT MUST ADHERE TO SURFACE REQUIREMENTS. LEVEL CHANGES BETWEEN SURFACES MUST NOT EXCEED 1/4" OR 1/2" WITH A 1:2 BEVEL. GAPS BETWEEN SURFACES OR GRATINGS MAY NOT EXCEED 1/2". SURFACES MUST BE FIRM, STABLE, AND SLIP RESISTANT.
- 14. HANDHOLES, UTILITY CASTINGS, OR OTHER SURFACE OBSTRUCTIONS MUST NOT REDUCE THE REQUIRED DEPTH OF DETECTABLE WARNING.
- 15. POLES, HYDRANTS AND OTHER ABOVE GROUND OBSTRUCTIONS MUST HAVE A MINIMUM LATERAL CLEARANCE OF 1'-0" FROM RAMP RUN(S) OR LANDING(S). EXCEPT FOR PUSHBUTTON POSTS.
- 16. ALL CHANGES IN LEVEL ACROSS JOINTS MUST BE FLUSH. ANY DIFFERENCE IN ELEVATION OF 3/16 INCH OR GREATER MUST BE REPAIRED OR REPLACED.
- 17. CURB RAMPS ARE DESIGNED TO ENSURE THAT WATER DOES NOT ACCUMULATE ON RAMP SURFACES AND IN FRONT OF THE CURB RAMP WHERE IT IS FLUSH WITH THE ROADWAY. THE CONTRACTOR MUST CHECK GRADE LINES AND GUTTER FLOW LINE PRIOR TO CONSTRUCTION. IF THE CHECK REVEALS THAT SITE CONDITIONS WOULD RESULT IN PONDING, OR WOULD CONFLICT WITH OBTAINING THE GRADES AT THE BOTTOM OF CURB RAMPS OR AT CURB RAMP LOWER LANDINGS AS SHOWN ON THE DRAWINGS OR PLANS, THE CONTRACTOR MUST NOTIFY THE ENGINEER IMMEDIATELY AND STOP WORK ON THE CURB RAMP UNTIL DIRECTED TO CONTINUE BY THE ENGINEER.
- **IT IS RECOMMENDED THAT CURB RAMPS RUNNING SLOPES BE DESIGNED TO 7.5% MAX. AND CURB RAMP LANDINGS BE DESIGNED TO 1.5% MAX TO ALLOW FOR A LIMITED MARGIN OF ERROR DURING CONSTRUCTION.





SIDE/BACK CURB - DOWELED



DEPRESSED CURB AND GUTTER DETAIL

REF STD SPEC SEC 8-14







DETECTABLE WARNING TRUNCATED DOMES PATTERN




NOT TO SCALE

CURB RAMP DETAILS







FOR ADDITIONAL SIDEWALK SCORING REQUIREMENTS SEE STD PLAN NO 420

TYPE C

TREE PIT DIMENSIONAL REQUIREMENTS:

- 24 SQ FT MIN TREE PIT SIZE
- 3'-0"MIN REQ'D BETWEEN TREE Q & FACE OF CURB 2'-0"MIN REQ'D BETWEEN TREE Q & CONC SIDEWALK 6'-0"MIN CONC WALKING SURFACE

NOTES:


- TISTALLATIONS REQUIRING LESS THAN STANDARD MIN CLEARANCES MUST BE ALLOWED ONLY WITH APPROVAL BY THE ENGINEER.
- INSTALL ROOT BARRIER AS NOTED. SEE STANDARD PLAN NO 100a.
- SEE STD PLAN NO 420 FOR CW SCORING DETAILS.
 WHEN INSTALLING NEW TREE PITS IN EXISTING SIDEWALK, REMOVE
 SIDEWALK TO FULL PANE WIDTH. INSTALL TREE PIT AS SHOWN ON THIS DETAIL.

REF STD SPEC SEC 8-02, 8-14




NOT TO SCALE


TREE PIT DETAIL



PERVIOUS CONC CEM SIDEWALK DEPTH TRANSITION AT DRIVEWAYS PROFILE VIEW



PERVIOUS CONC SECTION A



HOT MIX ASPHALT PAVEMENT SIDEWALK SECTION

NOTES:


- 1. DEPTHS SHOWN FOR PAVEMENT SECTIONS ARE COMPACTED DEPTH.
- SIDEWALK DEPTH AT DRIVEWAY TO MATCH DRIVEWAY PAVEMENT DEPTH.
 DEPTH OF POROUS CEMENT CONCRETE FOR DRIVEWAYS MUST BE 8" MIN.
- 4. 6% MAX. PERVIOUS CEMENT CONCRETE PROFILE GRADE.
- WHERE PERVIOUS CONCRETE IS SHOWN ON PLANS FOR ALLEY, PERVIOUS CONCRETE MUST BE 8" WITH 3" AGGREGATE DISCHARGE SUBBASE.
- APPLY SEPARATION GEOTEXTILE SEC. 9-37, ON BOTTOM AND SIDES. EXTEND GEOTEXTILE ABOVE PERVIOUS CONCRETE FOR SIDEWALK PAVEMENT. AFTER PAVEMENT HAS CURED AND ADJACENT FINISHED GRADE HAS BEEN STABILIZED, CUT SEPARATION GEOTEXTILE AT FINISHED GRADE (TYP.)
- 7. CONTRACTION JOINTS FOR PERVIOUS CONCRETE SIDEWALKS MUST BE PLACED AT A MAXIMUM OF 15 FT ON CENTER SPACING.


REF STD SPEC SEC 5-04, 5-06




NOT TO SCALE

ALTERNATIVE WALKWAYS










NOT TO SCALE

CEMENT CONCRETE DRIVEWAY PLACED WITH CEMENT **CONCRETE SIDEWALK**




MULTI PURPOSE TRAIL AT ARTERIAL STREET W/BULB-OUT (TYP)

NOTES:

- FOR CURB RAMP AND DETECTABLE WARNING DETAILS SEE STANDARD PLAN NO 422 (SERIES).
- FOR CROSSWALK DETAILS SEE STANDARD PLAN NO 712.
- FOR BOLLARD DETAIL SEE STANDARD PLAN NO 463.
- ASPHALT TRAIL CROSS SLOPE MINIMUM 1%, MAXIMUM 2%. CEMENT CONCRETE WARNING PAD THICKNESS TO MATCH ASPHALT THICKNESS OR MINIMUM 6" THICK WHICHEVER IS
- GREATER.
- CRUSHED ROCK ON EDGE OF TRAIL AS NEEDED TO DISBURSE DRAINAGE FLOW.
- ALL CHANGES IN LEVEL ACROSS JOINTS MUST BE FLUSH WITH A MAXIMUM DIFFERENCE IN ELEVATION OF $\%_6$ INCH. ALL SLOPE GRADES MUST BE MEASURED OFF THE
- HORIZON-LINE. IF EXISTING SITE CONDITIONS CONFLICT WITH OBTAINING GRADES SHOWN, THE CONTRACTOR MUST MAKE MINIMUM ADJUSTMENTS TO THE GRADES TO ACCOMMODATE EXISTING SITE CONDITIONS, ADJUSTMENTS ARE SUBJECT TO APPROVAL BY THE ENGINEER.
- ALL CEMENT CONCRETE WARNING PADS MUST BE BRUSHED FINISHED AND "V" GROOVED TO MATCH PATTERN IN ADJACENT
- OR NEARBY SIDEWALKS.

 10. CURB RAMP WIDTH, EXCLUDING WINGS, MUST MATCH THE WIDTH OF THE MULTI-PURPOSE TRAIL (SHARED USED PATH). 6" THICK.





REF STD SPEC SEC 8-22





NOT TO SCALE


MULTI-PURPOSE TRAIL AT STREET CROSSING












- FLIGHTS OF STAIRS MUST HAVE MAX VERTICAL RISE OF 12' BEFORE A LANDING.
- AVOID FEWER THAN 2 RISERS PER FLIGHT.
- STEPS IN FLIGHT MUST HAVE UNIFORM TREAD RUNS AND UNIFORM RISER HEIGHTS WITH TOLERANCE OF ±3/8".
- TREADS MUST BE 11"MIN, 12"MAX. RISERS MUST BE 5"MIN, 7"MAX.
 LANDINGS BETWEEN FLIGHTS OF RISERS MUST HAVE SAME WIDTH AS STEPS AND A MIN LENGTH OF 4'-0".
- STAIRWAYS WITH 1 OR MORE RISERS MUST HAVE HANDRAILS ON BOTH SIDES.
- HANDRAILS MUST BE CONTINUOUS ACROSS LANDINGS BETWEEN FLIGHTS OF STEPS.
- ALL STEEL MUST BE HOT DIPPED GALVANIZED.
- PIPE MATERIAL MUST BE ASTM A53 AND ROUND BAR ASTM A36.
- 10. REINFORCING STEEL MUST BE ASTM A615 GR 60.
 11. FOR FORMAL DRAINAGE PICK-UP SEE DETAIL B ON STD PLAN NO 440b (THIS IS OPTIONAL AND MUST BE CALLED OUT ON DRAWINGS).
 12. PIPE DIAMETERS SHOWN CORRESPOND TO PIPE "SHAPE" AS DEFINED IN AMERICAN INSTITUTE OF STEEL CONSTRUCTION MANUAL.
- CONCRETE CLASS CL3000.
- 14. LANDINGS MUST BE 0.5%MIN FOR A MIN LENGTH OF 4', ADJACENT SIDEWALK MAY BE PART OF LANDING IF SLOPE CRITERIA AND SETBACKS FROM HANDRAILS ARE MET.
- 15. TREAD SURFACE MUST HAVE GROOVES AT THE NOSE FOR TRACTION.
- 16. IF LANDING IS ELEVATED, LANDING MUST HAVE VERTICAL RAILING PER RIGHT OF WAY IMPROVEMENT MANUAL.
- 17. STAIRWAYS DEVIATING FROM STANDARD PLAN TO ACCOMMODATE BICYCLE FEATURES MAY BE USED PER STD PLAN NO 440C OR 440D.
- 18. DIMENSION FROM THE BOTTOM LANDING RAILING TO THE NOSE OF THE TREAD MUST BE 12"MIN + 1 TREAD LENGTH.
 19. HANDRAIL GRIPPING SURFACE AND ADJACENT SURFACES MUST BE FREE FROM SHARP OR ABRASIVE ELEMENTS AND MUST HAVE ROUNDED EDGES.
- 20. BOTTOM HANDRAIL EXTENSION MUST EXTEND ONE TREAD LENGTH MINIMUM PARALLEL TO THE SLOPE OF THE STAIR BEYOND BOTTOM STAIR NOSING.
 21. TOP HANDRAIL EXTENSION MUST EXTEND HORIZONTALLY ABOVE LANDING 12" MINIMUM BEYOND TOP STAIR NOSING.
- 22. REBAR SIZING AND SPACING MAY CHANGE FOR WIDER OR NARROWER STAIRWAYS.
- 23. EXTERNAL VENT HOLES MUST BE AS CLOSE TO THE WELD AS POSSIBLE AND MUST BE 25% THE SIZE OF THE I.D. OF THE PIPE, BUT NOT LESS THAN 3/8" IN DIA.
- 24. VENT HOLES IN END SECTIONS OR IN SIMILAR SECTIONS MUST BE ½" IN DIA.
 25. ENDS MUST BE LEFT COMPLETELY OPEN. ANY DEVICE USED FOR FIELD-ERECTION THAT PREVENTS FULL OPENINGS ON ENDS OF HORIZONTAL RAILS AND VERTICAL LEGS MUST BE GALVANIZED SEPARATELY AND ATTACHED AFTER GALVANIZING.


REF STD SPEC SEC 8-18




NOT TO SCALE


CEMENT CONCRETE STAIRWAY & HANDRAIL








STANDARD PLAN NO 440d














ROLL FORMED SECTIONS

MEMBER

	BRACE RAIL & TOP RAIL						LINE & BRACE POST					
TYPE	ROUND		H-COLUMN		ROLL FORMED		ROUND		H-COLUMN		ROLL FORMED	
	ID PIPE INCHES	WEIGHT PER FT POUNDS	SIZE INCHES	WEIGHT PER FT POUNDS	SIZE INCHES	WEIGHT PER FT POUNDS	ID PIPE INCHES	WEIGHT PER FT POUNDS	SIZE INCHES	WEIGHT PER FT POUNDS	SIZE INCHES	WEIGHT PER FT POUNDS
1	1.25		1.25X1.62	1.35	- 15/ ₈ X ¹ / ₄	1.35	2	3.65	21/4	4.0		
3		2.27					1½	2.72	1%	2.72	1%X1%	2.34
4		2.27		·			1½	2.72	1%	2.72	1%X1%	2.34
6			1.25X1.62	1.35			2	3.65	21/4	4.0		

MEMBER

	END,	CORNER &	GATE POST ROUND		ALL POSTS		
TYPE	RO	UND	H-CC	DLUMN		WEIGHT PER FT POUNDS	LENGTH
	ID PIPE INCHES	WEIGHT PER FT POUNDS	SIZE INCHES	WEIGHT PER FT POUNDS	SIZE INCHES		
1	21/2	5.79		5.14	3½	9.1	8'-8"
3	2	3.65	3%×3%				8'-8"
4	2	3.65	3/2/3/2				5'-6"
6	2½	5.79					5'-6"

NOTES:

ALL CONCRETE POST BASES MUST BE 10" MINIMUM DIAMETER, CL3000


- 2. POSTS MUST BE SPACED AT 10'-0" MAXIMUM INTERVALS UNLESS OTHERWISE DIRECTED BY THE ENGINEER
 3. TOP OR BOTTOM TENSION WIRES MUST BE PLACED WITHIN THE LIMITS OF THE FIRST FULL FABRIC WEAVE
- THE ILLUSTRATIVE DETAIL SHOWN HEREON MUST NOT BE CONSTRUED AS LIMITING TO HARDWARE DESIGN OR POST SELECTION FOR ANY PARTICULAR FENCE TYPE
- 5. CONCRETE OR GROUT AROUND POST AT GROUND LINE MUST BE MOUNDED FOR DRAINAGE


REF STD SPEC SEC 8-12




NOT TO SCALE


CHAIN LINK FENCE







TEMPORARY CURB RAMP PARALLEL TO CURB



TEMPORARY CURB RAMP PERPENDICULAR TO CURB

NOTES:

- ① CURB RAMPS ARE REQUIRED TO BE AT LEAST 36 INCHES WIDE WITH A FIRM, STABLE, AND NON-SLIP SURFACE.
- ② EDGE PROTECTION WITH A TWO-INCH MINIMUM HEIGHT IS REQUIRED FOR RAMPS WITH A RISE GREATER THAN SIX INCHES OR A SIDE APRON SLOPE GREATER THAN 33 PERCENT.
- 3 EDGE PROTECTION IS REQUIRED ON RAMPS WITH A VERTICAL ELEVATION OVER SIX INCHES AND SHOW A CONTRASTING COLOR WHERE THE WALKWAY CHANGES DIRECTION (TURNS).
- CURB RAMPS AND LANDINGS ARE REQUIRED TO HAVE A TWO-PERCENT MAXIMUM CROSS SLOPE.
- (5) PROVIDE A CLEAR SPACE OF AT LEAST 48 INCHES BY 48 INCHES ABOVE AND BELOW THE CURB RAMP.
- (6) MARK THE CURB RAMP WALKWAY EDGE WITH A CONTRASTING COLOR TWO TO FOUR INCHES WIDE UNLESS COLOR-CONTRASTING EDGING IS USED, AS REQUIRED BY ITEM 3 ABOVE.
- 7 WATER FLOW IN THE GUTTER SHOULD HAVE MINIMUM RESTRICTION.
- B LIMIT LATERAL JOINTS OR GAPS BETWEEN SURFACES TO BE LESS THAN
- (9) CHANGES BETWEEN SURFACE HEIGHTS SHOULD NOT EXCEED HALF AN INCH. LATERAL EDGES SHOULD BE VERTICAL UP TO 0.25 INCHES HIGH AND BEVELED AT 1:2 WHEN BETWEEN 0.25 AND 0.5 INCHES HIGH.


REF STD SPEC SEC 1-07.23



NOT TO SCALE

TEMPORARY PEDESTRIAN CURB RAMP

REV DATE: 2003




CONCRETE TONGUE & GROOVE BLOCK


REF STD SPEC SEC 7-11




NOT TO SCALE


ECOLOGY BLOCK, CONCRETE







REV DATE: JAN 2020




NOTES:

- 1. UNLESS OTHERWISE SPECIFIED, TRAFFIC SIGNAL CONTROLLER CABINET MUST BE FURNISHED BY THE CITY
- UNLESS OTHERWISE SPECIFIED, EXACT CABINET DIMENSIONS & ANCHOR BOLT LOCATIONS MUST BE PROVIDED BY THE TRAFFIC SIGNAL SHOP
- 3. PLACE CABINET DOOR ON SIDEWALK SIDE OF FOUNDATION
- 4. SEAL CABINET TO FOUNDATION WITH GREY OR CLEAR SILICONE TO PREVENT MOISTURE FROM ENTERING THE CABINET
- CABINET FOUNDATIONS INSTALLED IN A LANDSCAPE AREA MUST INCLUDE A CONCRETE SIDEWALK MAINTENANCE PAD ON THE SDOT DOOR SIDE OF THE FOUNDATION, SEE STD SPEC SEC 8-32.3(2)B

DIMENSION	TYPE II	TYPE III	VI		
А	30"	44"	44"		
В	17"	25 ½"	25½"		
С	38" TO 52"	50" TO 58"	64¾" TO 67½"		

SIGNAL CONTROLLER CABINET-TYPES II, III, VI



SIGNAL CONTROLLER FOUNDATION


SEE STD PLANS NO 500b & 500c FOR CONDUIT LAYOUT

REF STD SPEC SEC 8-31, 8-32




NOT TO SCALE

SIGNAL CONTROLLER CABINET & FOUNDATION



CONDUIT LAYOUT - TYPE II SIGNAL CONTROLLER FOUNDATION




CONDUIT LAYOUT - TYPE III/VI SIGNAL CONTROLLER FOUNDATION


REF STD SPEC SEC 8-31, 8-32




NOT TO SCALE


SIGNAL CONTROLLER FOUNDATION CONDUIT LAYOUT







REV DATE: 2003




SUSPENDED SIGNAL MOUNTING DETAIL


REF STD SPEC SEC 8-31




NOT TO SCALE

VEHICULAR SIGNAL MOUNTING





METAL POLE MOUNT



- 1. BOLT AND WASHERS MUST BE STAINLESS STEEL PER ASTM A 563 DH AND ASTM F 436
- 2. MOUNTING MUST BE AS FOLLOWS:
 - -ON METAL POLES THINNER THAN 7 GAUGE, USE $\frac{3}{6}$ " STAINLESS STEEL RIVNUTS -ON METAL POLES 7 GAUGE OR THICKER, DRILL
 - AND TAP FOR 3/8" BOLT (STAINLESS STEEL RIVNUTS OPTIONAL)
 - -ON POLES FILLED WITH OR MADE FROM CONCRETE USE $\frac{3}{8}$ "X2 $\frac{1}{2}$ " STUD BOLT ANCHORS WITH HEX NUT
- 3. FOR STREET NAME SIGN PEDESTAL INSTALLATION, SEE STD PLAN NO 623


PEDESTAL MOUNT


REF STD SPEC SEC 8-31





NOT TO SCALE


PEDESTRIAN SIGNAL CLAMSHELL MOUNTING














CURB/PAVEMENT ENTRANCE FOR DETECTOR LOOP WIRES

NOTES:

- SHARP EDGE TOOLS MUST NOT BE USED IN PLACING CONDUCTORS IN SAW CUTS EACH PAIR OF LOOP WIRES IN THE RETURN CUT MUST BE TWISTED A MINIMUM OF 3
- TURNS PER FOOT AND MAY SHARE COMMON RETURN CUTS WITH OTHER TWISTED PAIRS MAX 3 LOOPS PER CUT.
- MAX 3 LOOPS PER CUT.

 3. TAPE LOOP WIRE A MINIMUM OF 2 TURNS AT EACH CORNER

 4. REMOVE SHARP CORNER EDGES IN SAW CUTS WHERE LOOP WIRE WILL BE BENT AROUND

 5. PERFORM RESISTANCE AND CONTINUITY TESTS PRIOR TO SEALING LOOP WIRES


 6. COIL 5'-0" OF LOOP WIRE IN HANDHOLE


REF STD SPEC SEC 8-31



NOT TO SCALE

DETECTOR LOOP LEAD-IN





DETECTOR LEAD-IN WIRE SPLICE DETAIL


NOTE:
SOLDER CONNECTION AFTER CRIMPING

REF STD SPEC SEC 8-31



NOT TO SCALE


DETECTOR LOOP WIRE & SIGNAL CABLE SPLICE




REV DATE: JAN 2020

	FOUNDATION SCHEDULE								
POLE TYPE	PROJECTION	ANCHOR BOLTS	ANCHOR PLATE DIMENSIONS						
	Р	(TOTAL 4 PER POLE)	BOLT CIRCLE DIA	SIZE	BOLT HOLE	CENTER HOLE	CORNER RADIUS		
Т	7½"	1½" DIA X 60"	14½"	³ ⁄ ₈ " X 16" X 16"	15/8"	10"	15/8"		
٧	9"	1¾" DIA X 72"	18"	¾" X 16" X 16"	1%"	12½"	15/8"		
Х	10"	2" DIA X 72"	20"	³ ⁄ ₈ " X 18" X 18"	21/8"	14"	2"		
Z	11½"	2½" DIA X 72"	22"	½" X 20" X 20"	25/8"	15"	21/4"		

FOUNDATION PER PLAN. WHERE POLE TYPE OTHER THAN NOTED ABOVE IS REQUIRED, REFER TO PLANS FOR ANCHOR BOLTS AND ANCHOR PLATE DIMENSIONS.







INCLINED CONDITION

NOTES:

1. CONCRETE MUST BE CLASS 4000P.


- ANCHOR BOLTS FOR TYPE T,V,X AND Z MUST CONFORM TO ASTM F1554 GRADE 105 CLASS 2A THREADS INCLUDING SUPPLEMENTARY REQUIREMENTS S2 THROUGH S4. PROVIDE NUTS ACCORDING TO ASTM A536 HEAVY HEX GRADE DH AND NUTS PER ASTM F436.
- 3. ANCHOR PLATE: ASTM A36. HOT DIP GALVANIZED PER ASTM A123.
- ALL REINFORCING BARS MUST BE DEFORMED BILLET STEEL CONFORMING TO ASTM CLASS A706, GRADE 60.
- 5. ANCHOR BOLTS MUST BE HOT DIP GALVANIZED PER ASTM F2329 INCLUDING NUTS & WASHERS (FULL LENGTH) WITH 18" OF THREADS ON TOP & 12" ON BOTTOM
- 6. TAPE THE TOP OF ANCHOR BOLTS WITH CORROSION PROTECTION TAPE PER STD SPEC SEC 8-32.3(2)A PRIOR TO POURING CONCRETE.
- 7. FOUNDATION DEPTH, REINFORCEMENT AND ANCHOR BOLTS MUST BE IN CONFORMANCE WITH "AASHTO STANDARD SPECIFICATIONS FOR STRUCTURAL SUPPORTS FOR HIGHWAY SIGNS, LUMINAIRES AND TRAFFIC SIGNALS" (6TH EDITION, 2013). DESIGN BASIC WIND SPEED IS 85 MPH AND RECURRENCE INTERVAL/DESIGN LIFE IS 50 YEARS


REF STD SPEC SEC 8-32



NOT TO SCALE

STRAIN POLE FOUNDATION SCHEDULE & NOTES (TYPE T, V, X & Z)






- 1. SEE SCL CONSTRUCTION STANDARD 1716.34 FOR POLE MOUNTING AND GROUT DETAIL
- ANCHOR BOLTS MUST BE HOT DIP GALVANIZED ASTM A153 OR F2329, FULL LENGTH AND FABRICATED FROM ASTM F1554 OR A576 WITH 12" THREADS ON TOP
- ALL SHRUBBERY AND FOLIAGE MUST BE PLANTED A MINIMUM OF 2' FROM SCL STRUCTURE PER SCL CONSTRUCTION STANDARD 0214.00


REF STD SPEC SEC 8-32



NOT TO SCALE

STREET LIGHT POLE FOUNDATIONS





- 1. SEE SCL CONSTRUCTION STANDARD 1716.34 FOR POLE MOUNTING AND GROUT DETAIL
- 2. ANCHOR BOLTS MUST BE HOT DIP GALVANIZED TO ASTM A153 OR F2329, FULL LENGTH AND FABRICATED FROM ASTM F1554 OR A576 WITH $8^{\prime\prime}$ OF THREADS ON TOP
- 3. SEE SCL MATERIAL STANDARD 5756.09 FOR POLES
- 4. SEE SCL CONSTRUCTION STANDARD 1716.07 FOR STREETLIGHT HANDHOLE AND CONDUIT REQUIREMENTS.
- ALL SHRUBBERY AND FOLIAGE MUST BE PLANTED A MINIMUM OF 2' FROM SCL STRUCTURE PER SCL CONSTRUCTION STANDARD 0214.00


REF STD SPEC SEC 8-32




NOT TO SCALE

PEDESTRIAN STREET LIGHT POLE FOUNDATIONS

- THE COVER MUST HAVE 1/6" TO 1/8" CLEARANCE ON EACH EDGE WITHIN THE FRAME AFTER GALVANIZING.
- THE GROUND ROD MUST EXTEND 4" ABOVE THE BOTTOM OF THE HANDHOLE OR MINERAL AGGREGATE.
- 3. TYPE 1, 2, 3, 5 & 6 HANDHOLE COVERS MUST HAVE "SDOT" OR "SL" ON THEM, AS APPROPRIATE.
- TYPE 4 HANDHOLE MUST BE INSTALLED IN ROADWAYS, PARKING LOTS, ETC.
- 5. FOR PAVEMENT DEPTH GREATER THAN 7" USE FRAME EXTENSIONS (SEE STD PLAN NO 231) TO BRING THE COVER UP THE THE LEVEL OF THE FINISHED PAVEMENT WITHOUT EMBEDDING THE BOTTOM FLANGE OF THE CASTING IN THE PAVEMENT.
- 6. A 4' LENGTH OF #6 THWN OR THHN COPPER WIRE MUST BE SECURED FROM THE HANDHOLE COVER TO THE FRAME. BOND FROM FRAME LID, AND LID TO GROUND ROD.
- ALL HANDHOLE COVERS AND FRAMES MUST HAVE A NON-SKID SURFACE (SEE STD SPEC SEC 9-34.6)
- ALL HANDHOLES MUST HAVE A LOAD RATING OF H2O.
- GROUND ROD REQUIRED IN ALL STREETLIGHT HANDHOLES PER SCL CONSTRUCTION STD 1714.50
- 10. SEE SCL CONSTRUCTION STANDARD 1716.07 & SCL MATERIAL STD 7203.10 FOR STREETLIGHT HANDHOLE AND CONDUIT REQUIREMENTS.
- 11. ALL SHRUBBERY AND FOLIAGE MUST BE PLANTED A MINIMUM OF 2' FROM SCL STRUCTURE PER SCL CONSTRUCTION STANDARD 0214.00



HANDHOLE INSTALLATION DETAIL




City of Seattle


NOT TO SCALE

HANDHOLES


HANDHOLE SCHEDULE

HANDHOLE TYPE		UNIT MENSI	INSIDE ON	EXTENSION UNIT(E)		VER SIONS
	L	W	Н	Н	L	W
1	22"	17"	12"	12"	17¾"	12¾"
2	33"	22"	12"	12"	27¾"	16¾"
3	36"	24"	12"	12"	35"	24"
4	24"ø		VAR	NA	NA	NA
5	36"	24"	32"	NA	35"	24"
6	42"	42"	38½"	NA	33½"	33¾"
GRHH	8"ø			NA		





TYPE 6 HANDHOLE



NOTES:

ALL HANDHOLES MUST HAVE A H20 LOAD RATING.
 ALL HANDHOLE COVERS AND FRAMES MUST HAVE A
 NON-SKID SURFACE (SEE STD SPEC SEC 9-34.6)

GROUND ROD HANDHOLE (GRHH)

REF STD SPEC SEC 8-33



NOT TO SCALE


HANDHOLES

- . ALL NON-DELIBERATE TRAFFIC PULL BOX COVERS MUST COMPLY WITH ALL TEST PROVISIONS OF ANSI/SCTE 77 2010 "SPECIFICATION FOR UNDERGROUND ENCLOSURE INTEGRITY", & MUST MEET THE TIER 15 APPLICATION. MARKING SHOWING THE TIER 15 RATING MUST BE EMBOSSED IN THE TOP SURFACE OF THE COVER.
- 2. ALL NON-DELIBERATE TRAFFIC PULL BOXES MUST COMPLY WITH ALL TEST PROVISIONS OF ANSI/SCTE 77 2012 "SPECIFICATION FOR UNDERGROUND ENCLOSURE INTEGRITY", & MUST MEET THE TIER 22 APPLICATION. MARKINGS SHOWING THE TIER 22 RATING MUST BE LABELED OR STENCILED ON THE INSIDE & OUTSIDE OF THE BOX.
- BE LABELED OR STENCILED ON THE INSIDE & OUTSIDE OF THE BOX.


 3. ALL NON-DELIBERATE TRAFFIC PULL BOXES & COVERS MUST BE MADE OF POLYMER CONCRETE WITH FIBERGLASS REINFORCEMENT. THE BOX MUST HAVE CONTINUOUS FIBERGLASS CLOTH REINFORCEMENT ON THE INSIDE & OUTSIDE PERIMETERS. THE COVER MUST HAVE A MINIMUM OF TWO LAYERS OF FIBERGLASS CLOTH REINFORCEMENT.
- 4. ALL NON-DELIBERATE TRAFFIC PULL BOXES & COVERS MUST BE TESTED & CERTIFIED, MEETING ALL TEST PROVISIONS ON THE ANSI/SCTE 77, TO THE 66WF, MEETING ALL TEST PROVISION OF THE LATEST REVISION OF ANSI/SCTE 77.
- 5. PULL SLOTS MUST BE RATED FOR MINIMUM PULL OUT OF 3.000 POUNDS.
- 6. TYPE 4 HANDHOLE MUST BE INSTALLED IN ROADWAYS PARKING LOTS, ETC. ALL COVERS MUST BE COMPLETE WITH A MOLDED LOGO, MANUFACTURES NAME & TIER RATING LOGO (NO GLUE IN LOGO). LOGO MUST READ "SDOT" OR "SL" UNLESS STATED OTHERWISE BY THE CITY OF SEATTLE.
- THE GROUND ROD MUST EXTEND 4" ABOVE THE BOTTOM OF THE HANDHOLE OR MINERAL AGGREGATE.
- 8. FOR PAVEMENT DEPTH GREATER THAN 7" USE FRAME EXTENSIONS (SEE STD PLAN NO 231) TO BRING THE COVER UP THE THE LEVEL OF THE FINISHED PAVEMENT WITHOUT EMBEDDING THE BOTTOM FLANGE OF THE CASTING IN THE PAVEMENT.
- 9. A 4' LENGTH OF #6 THWN OR THHN COPPER WIRE MUST BE SECURED FROM THE HANDHOLE COVER TO THE FRAME. WITH A 4'-0" LENGTH FROM FRAME THAT CAN BE HOOKED UP TO A GROUND ROD.
- 10. ALL HANDHOLE COVERS AND FRAMES MUST HAVE A NON-SKID SURFACE (SCL MATERIAL STANDARD 7203.10)
- 11. SEE SCL CONSTRUCTION STANDARD 1716.07 FOR STREET HANDHOLE AND CONDUIT REQUIREMENTS.

HANDHOLE SCHEDULE

HANDHOLE TYPE	i	TOP UNIT INSIDE DIMENSION		EXTENSION UNIT(E)	COVER DIMENSIONS	
	L	W	Н	Н	L	W
1	24"	13"	12"	12"	24"	13"
2	30"	17"	12"	12"	30"	17"
3	36"	24"	18"	12"	36"	24"
4	24"ø		VAR	NA	NA	NA
5	30"	48"	36"	NA	30"	48"
6	48"	48"	48"	NA	48"	48"
GRHH	8"ø		NA			



TYPE 3 HANDHOLE (COVER SAME AS TYPE 5)



REF STD SPEC SEC 8-33



TYPE 1 & 2 HANDHOLE

NOT TO SCALE

6"ø DRAIN HOLE (OPENED)_

TYPE 5 HANDHOLE

POLYMER CONCRETE HANDHOLES

GALV STRUT 18" LONG 1 EACH SIDE 12" X 12" KNOCKOUT ALL SIDES-Н (4) 43/4"ø KNOCKOUT ALL SIDES 3000 LB PULLING EYE, 1 EACH SIDE-6"ø DRAIN (2) 2½″ø GROUND ROD KNOCKOUTS HOLE (OPENED)_

TYPE 6 HANDHOLE

NOTES:


- 1. FOR DETAILS NOT SHOWN, SEE STD PLAN NO 550b
 2. ALL HANDHOLE COVERS AND FRAMES MUST HAVE A
 NON-SKID SURFACE (SEE STD SPEC SEC 9-34.6)


REF STD SPEC SEC 8-33



NOT TO SCALE

POLYMER CONCRETE HANDHOLES





	POLE SCHEDULE				
	POLE BASE PLATE				
MAST ARM LENGTH	SQUARE	BOLT CIRCLE 'A"	BOLT HOLE		
15'-0" TO 30'-0"	16" X 16"	14½"	1 ¹³ ⁄ ₁₆ "		
31'-0" TO 40'-0"	18" X 18"	16½"	21/16"		
41'-0" TO 45'-0"	18" X 18"	18"	21/16"		
46'-0" TO 60'-0"	20" X 20"	20"	25/16"		

POLE FOUNDATION NOTES

- 1. CONCRETE MUST BE CLASS 4000P
- ANCHOR BOLTS MUST BE ASTM F1554 GRADE 105 CLASS 2A THREADS INCLUDING SUPPLEMENTARY REQUIREMENTS S2 THROUGH S4. NUTS: ASTM A563 HEAVY HEX GRADE DH. HARDENED STEEL WASHERS: ASTM F436.
- 3. BOTTOM ANCHOR PLATE: ASTM A36. HOT DIP GALVANIZED PER ASTM A123.
- ALL REINFORCING BARS MUST BE DEFORMED BILLET STEEL CONFORMING TO ASTM CLASS A706, GRADE 60.
- ANCHOR BOLTS MUST BE HOT DIP GALVANIZED PER ASTM F2329 INCLUDING NUTS & WASHERS (FULL LENGTH) WITH A MINIMUM OF 18" OF THREADS ON TOP & 12" ON BOTTOM.
- TAPE THE TOP OF ANCHOR BOLTS WITH CORROSION PROTECTION TAPE PER STD SPEC SEC 8-32.3(2)A PRIOR TO POURING CONCRETE.
- 7. SEE STD PLAN NO 541a FOR FOUNDATION DETAILS.
- 8. FOUNDATION DEPTH, REINFORCEMENT AND ANCHOR BOLTS MUST BE IN CONFORMANCE WITH "AASHTO STANDARD SPECIFICATIONS FOR STRUCTURAL SUPPORTS FOR HIGHWAY SIGNS, LUMINAIRES AND TRAFFIC SIGNALS" (6TH EDITION, 2013). DESIGN BASIC WIND SPEED IS 85 MPH AND RECURRENCE INTERVAL/DESIGN LIFE IS 50 YEARS

FOUNDATION SCHEDULE								
MAST ARM LENGTH		NCHOR BOLT	S	ANCHOR PLATE DIMENSIONS				
	PROJECTION "P"	BOLT CIRCLE DIA	SIZE	SIZE	BOLT HOLE	CENTER HOLE	CORNER RADIUS	
15'-0" TO 30'-0"	7½"	14½"	1½" X 60"	3/8" X 16" X 16"	15%"	10"	15/8"	
31'-0" TO 40'-0"	9"	16½"	1¾" X 72"	¾" X 16" X 16"	17/8"	12½"	15%"	
41'-0" TO 45'-0"	9"	18"	1¾" X 72"	¾" X 16" X 16"	17/8"	12½"	15%"	
46'-0" TO 60'-0"	10"	20"	2" X 72"	¾" X 18" X 18"	21/8"	14"	2"	


FOUNDATION DEPTH MUST BE PER PLANS.


REF STD SPEC SEC 8-31, 8-32





NOT TO SCALE

STEEL MAST ARM POLE FOUNDATION SCHEDULE & DETAIL W/O METRO TROLLEY LOADS)









REV DATE: JAN 2020

	POLE SCHEDULE								
POLE TYPE	GROUND LINE DIA "A"		POLE BASE PLATE SIZE		BOLT CIRCLE DIA	BOLT HOLE	ANCHOR BOLTS		
	STD	CSB	STD	CSB	"B"				
V	12"	12"	1¾"X18"X18"	1¾"X23"X23"	18"	21/16"	1¾"DIA X 72"		
×	14"	12½"	2"X20"X20"	2"X23"X23"	20"	25/16"	2"DIA X 72"		
Z	15"		2½"X23"X23"		22"	213/16"	2½"DIA X 72"		

NOTES:


- T. POLE SHAFT AND REINFORCING SLEEVE: ASTM A572 GRADE 50, 60 OR 65 (Fy=50, 60 OR 65 KSI RESPECTIVELY) OR ASTM A595 GRADE A OR B (Fy=55 OR 60 KSI RESPECTIVELY).
- 2. BASE PLATE AND HANDHOLE REINFORCING RIM: ASTM A36 OR ASTM A572 GRADE 42. BASE PLATE Fy≥0.65 POLE SHAFT Fy THE BASE PLATE THICKNESS MAY BE REDUCED BY ¼" IF ASTM A572 GRADE 42 STEEL IS USED.
- REINFORCING SLEEVE MUST BE FABRICATED FROM THE SAME MATERIAL AND YIELD STRENGTH AS THE POLE SHAFT.
- 4. POLE SHAFTS MUST HAVE NO MORE THAN TWO LONGITUDINAL WELDS IN FACH PLY
- MINIMUM SHAFT WALL THICKNESS OF EACH PLY MUST BE 0.239" (3 GAUGE). POLE MUST HAVE A MAXIMUM OF TWO PLYS NOT INCLUDING THE ¼" REINFORCING SLEEVE.
- MAXIMUM SILICON CONTENT IN STEEL MUST BE 0.04%. SEE STD SPEC SECTION 9-33.1(3) FOR GENERAL GALVANIZING REQUIREMENTS.
- 7. POLE DIAMETER FOR 12 OR MORE SIDED POLES MUST BE MEASURED FROM THE POINT TO POINT DIMENSION.
- POLES MUST MEET DEFLECTION CRITERIA STATED IN STD SPEC SECTION 9-33.2(2) WITH THE DEAD LOAD APPLIED AT 25' ABOVE GROUND LINE.
- POLE STRENGTH MUST MEET REQUIREMENTS OF AASHTO STANDARD SPECIFICATIONS FOR STRUCTURAL SUPPORTS FOR HIGHWAY SIGNS, LUMINAIRES AND TRAFFIC SIGNALS (6TH EDITION, 2013). DESIGN WIND SPEED IS 85 MPH AND RECURRENCE INTERVAL/DESIGN LIFE IS 50 YEARS.

REF STD SPEC SEC 8-32, 9-33



NOT TO SCALE


STRAIN POLE DETAILS (TYPE V, X & Z POLES)



REV DATE: JAN 2020

NOTES:

- POLE STRENGTH MUST MEET REQUIREMENTS OF AASHTO STANDARD SPECIFICATIONS FOR STRUCTURAL SUPPORTS FOR HIGHWAY SIGNS, LUMINAIRES AND TRAFFIC SIGNALS (6TH EDITION, 2013). DESIGN WIND SPEED IS 85 MPH AND RECURRENCE INTERVAL/DESIGN LIFE IS 50 YEARS.
- POLE SHAFT: ASTM A572 GRADE 50, 60 OR 65 (Fy=50, 60 OR 65 KSI RESPECTIVELY), OR ASTM A595 GRADE A OR B (Fy=55 OR 60 KSI RESPECTIVELY)
- 3. BASE PLATE AND HANDHOLE REINFORCING RIM: ASTM A36 OR ASTM A572 GRADE 42. BASE PLATE Fy \geq 0.65 POLE SHAFT Fy THE BASE PLATE THICKNESS MAY BE REDUCED BY $\frac{1}{4}$ " IF ASTM A572 GRADE 42 STEEL IS USED.
- 4. POLE SHAFTS MUST HAVE NO MORE THAN TWO LONGITUDINAL WELDS IN EACH PLY.
- MINIMUM SHAFT WALL THICKNESS OF EACH PLY MUST BE 0.239" (3 GAUGE). POLE MUST HAVE A MAXIMUM OF TWO PLYS.
- MAXIMUM SILICON CONTENT IN STEEL MUST BE 0.04%. SEE STD SPEC SECTION 9-33.1(3) FOR GENERAL GALVANIZING REQUIREMENTS.
- 7. POLE DIAMETER FOR 12 OR MORE SIDED POLES MUST BE MEASURED FROM THE POINT TO POINT DIMENSION.
- 8. POLES MUST MEET DEFLECTION CRITERIA STATED IN STD SPEC SECTION 9-33.2(2) WITH THE DEAD LOAD APPLIED AT 27' ABOVE GROUND LINE.
- 9. THE POLES MUST BE COMPACT AND MUST MEET THE REQUIREMENTS IN AASHTO SECTION 4, TABLE 1.4 1B(1).




REF STD SPEC SEC 8-32, 9-33




NOT TO SCALE

TYPE T STRAIN POLE DETAILS
TRAFFIC SIGNAL ONLY




BRACKET ARM EXTENSION 2" STD PIPE (SCH 40) BRACKET ARM EXTENSION

REQUIRED



NOTE: FLANGE DIMENSIONS AND HOLE LOCATIONS MUST MATCH THOSE ON FLANGE PLATE ON POLE (SEE STD PLAN NO 563a)

BRACKET ARM FLANGE PLATE



NOMINAL SPAN

NOMINAL SPAN

BEND RADIUS

TAPER

NOTE: BEVEL TUBE AS NECESSARY
FOR FLUSH WELD

SEE BRACKET ARM
FLANGE PLATE DETAIL

2' THRU 10' BRACKET ARMS

NOM SPAN	H*	BEND RADIUS	TUBE REQUIREMENT
2'	5¼"	-	2" STD PIPE
4'	12"	6'	11 GAUGE
6'	18"	9'	11 GAUGE
8'	24"	13'	11 GAUGE
10'	30"	15'	11 GAUGE

MATERIAL SPECIFICATION
PLATE AND SHAPES:
ASTM A36
POLE SHAFTS:
ASTM A570
GR 40 MIN.
ANCHOR BOLTS:
ASTM A307
BRACKET ARM FLANGE
PLATE BOLT: ASTM A325

* THESE DIMENSIONS ARE ONLY ILLUSTRATIVE OF THE GENERAL OUTLINE AND MATERIALS USED IN THE CONSTRUCTION OF THESE ARMS AND ARE NOT INTENDED TO EXCLUDE MANUFACTURER'S STANDARD PRODUCTS.

NOTE:

1. ALL OTHER ARM LENGTHS REQUIRE SCL REVIEW AND APPROVAL


POLE BASE PLATE

REF STD SPEC SEC 8-32



NOT TO SCALE

STEEL STREET LIGHT POLE WITH BRACKET ARM



CONDUIT RISER (WITH STAND-OFF BRACKET*)

*WHEN THERE WILL BE ONLY ONE CONDUIT ($1\frac{1}{2}$ " OR SMALLER) ON THE POLE, TWO HOLE MALLEABLE IRON CLAMPS WITH DOUBLE HEADED NAILS MUST BE USED TO SECURE THE CONDUIT TO THE POLE IN LIEU OF THE STAND-OFF BRACKETS

NOTES:


- ON POLES WITH EXISTING CONDUITS, NEW CONDUITS MUST BE INSTALLED IN ACCORDANCE WITH THIS STANDARD PLAN.
- RIGID STEEL CONDUIT MUST BE GROUNDED JUST BELOW COUPLING, APPROXIMATELY 8'-0" TO 10'-0" ABOVE GROUND, AS SHOWN
- 3. ALL RISERS BONDED IN HH
- 4. THE GROUND WIRE MUST BE ONE CONTINUOUS LENGTH. INSERT THE GROUND WIRE FORM THE BOTTOM OF THE GROUND CLAMP & BEND OVER THE CLAMP BEFORE TIGHTENING
- ALL STEEL HARDWARE MUST BE HOT DIPPED GALVANIZED AFTER FABRICATION PER ASTM A123
- CONDUIT CLAMP SPACING MUST BE PER THE NEC WITH A MINIMUM OF TWO HOLE CLAMP PER 10'-0" LENGTH OF CONDUIT
- SERVICE AND SIGNAL CONDUCTORS MUST NOT BE PLACED IN THE SAME CONDUIT.
- WHEN POSSIBLE, RISER MUST BE INSTALLED ON DOWNSTREAM SIDE OF TRAFFIC
- SEE SCL CONSTRUCTION STANDARD 1714.50 FOR STREETLIGHT HANDHOLE AND CONDUIT REQUIREMENTS & 0224.34 FOR STREETLIGHT CONDUIT RISERS.


REF STD SPEC SEC 8-33




NOT TO SCALE

TRAFFIC CONDUIT RISER





STREET DESIGNATION SIGN



SI AIT WITE MOUNTED SION

NOTES:

- ALL HARDWARE MUST BE STAINLESS STEEL. OTHER THAN HARDWARE MUST BE HOT DIP GALVANIZED.
- 2. NEOPRENE GASKETS MUST NOT BE USED FOR SPAN WIRE OR AERIAL CONNECTIONS.


REF STD SPEC SEC 8-21




NOT TO SCALE

OVERHEAD SIGNS SPANWIRE MOUNTED

REV DATE: AUG 2010



SIGN MOUNTING ON MAST ARM



TEMPORARY SIGN MOUNTING ON METAL POLE

NOTES:


- 1. EXCEPT AS NOTED OTHERWISE, ALL HARDWARE MUST BE STAINLESS STEEL.
- MOUNTING OF TRAFFIC SIGNS MUST BE AS FOLLOWS: ON METAL POLE THINNER THAN
 7 GAUGE, USE 3/8" STAINLESS STEEL RIVNUTS ON METAL POLES 7 GAUGE OR
 THICKER, FOR 3/8" BOLT (STAINLESS STEEL RIVNUT OPTIONAL) ON POLES FILLED
 WITH OR MADE FROM CONCRETE, USE 3/8"X21/2"MIN STUD BOLT ANCHORS WITH
 HEX NUT.
- 3. FOR SIGN FEATURE, CONTACT TRAFFIC ENGINEER.


REF STD SPEC SEC 8-21




NOT TO SCALE


SIGN INSTALLATION (NON-SPANWIRE MOUNTING)







NOT TO SCALE



POST ANCHOR INSTALLATIONS

NOTE:


- CONTACT SEATTLE DEPARTMENT OF TRANSPORTATION (684-5087) FOR DETAILS REGARDING SIGN MESSAGE AND FOUNDATION.
- 2. STEEL SELF-TAPPING #10 X $\frac{1}{2}$ " WITH HEX WASHER HEAD ZINC PLATED
- 3. RED AND WHITE SLEEVE
- 4. SEE STANDARD 621a FOR OTHER WARNING & REGULATORY SIGN POST


REF STD SPEC SEC 8-21




NOT TO SCALE

STOP AND YIELD SIGN POST AND ANCHOR INSTALLATION







HEAVY DUTY ANCHOR

NOTES:

- 1. FOR UNLEVEL SIDEWALKS INSERT WASHERS AS SPACERS BETWEEN PLATE AND SIDEWALK.
- IF BOLT CANNOT PENETRATE SIDEWALK AT LEAST 3", CONTACT THE ENGINEER.


 2. USE CONCRETE FOOTINGS FOR ALL SIGNS LARGER THAN 96 SQUARE INCHES.


REF STD SPEC SEC 8-21




NOT TO SCALE

WARNING AND REGULATORY SIGN POST ANCHOR INSTALLATIONS







- 1. CAP MUST BE MADE OF THE SAME MATERIAL AS THE SURROUNDING PAVED SURFACE AND MUST BE MOUNDED FOR DRAINAGE AWAY FROM POST.
- BLOCKOUTS MUST BE PROVIDED FOR POST LOCATIONS WHERE NEW CONCRETE PAVEMENT (SIDEWALK, ROADWAY, ETC) IS BEING INSTALLED.
- WHERE POST IS BEING INSTALLED IN EXISTING PAVED AREAS, HOLE IN PAVED SURFACE MUST NOT EXCEED 1'-0" NOMINAL DIAMETER.


REF STD SPEC SEC 8-21



NOT TO SCALE

POST CAP

REV DATE: DEC 2019



PERFORATED TELESPAR STANDARD SIGN POST (TS-5, TS-10, TS-12)(SEE NOTE 2)

NOTES:

1. SEE STD PLANS NO 620 & 621.


2. SUFFIXES ATTACHED TO TELESPAR NAME DESIGNATIONS INDICATE SLEEVE TYPES: RW-RED/WHITE, FYG-FLOURESCENT YELLOW GREEN, Y-FHWA YELLOW.

REF STD SPEC SEC 8-21



NOT TO SCALE

TRAFFIC SIGN POSTS




- IN THE CASE WHERE ALL APPROACHES OF THE INTERSECTION ARE PRIMARILY AT THE SAME LEVEL WITH RESPECT TO GRADES (LESS THAN 3%) THE LOWER SET OF SIGNS MUST FACE THE HIGHER TRAFFIC VOLUME STREET
- 2. IN THE CASE WHERE AN APPROACH HAS A GRADE LARGER THAN 3% THE HIGHER SIGNS WILL FACE THE STEEPEST APPROACH TO ALLOW BETTER SIGHT DISTANCE
- 3. PLACE A MINIMUM OF THREE (3) REFLECTORS ON EACH AND EVERY SIDE OF POST OR PLACE THREE (3) HIGH INTENSITY REFLECTORIZED STRIPS COMPLETELY AROUND POST


REF STD SPEC SEC 8-21



NOT TO SCALE

OBJECT MARKER INSTALLATION IN TRAFFIC CIRCLE






- 1. WAYFINDING BLADE MUST BE INSTALLED POINTING IN THE DIRECTION OF THE LOCATION ON BLADE.
- 2. CITY OF SEATTLE WILL FABRICATE WAYFINDING SIGNS. CONTRACTOR MUST SUPPLY MOUNTING HARDWARE AND INSTALL SIGNS.
- 3. MAINTAIN 8 FEET MINIMUM OF VERTICAL CLEARANCE FROM CONCRETE WALK TO THE BOTTOM OF PEDESTRIAN WAYFINDING BLADES.


REF STD SPEC SEC 8-21



NOT TO SCALE

PEDESTRIAN WAYFINDING SIGN






TYPICAL TURN LANE CHANNELIZATION

NUMBER OF LEGEND SETS REQUIRED BASED ON THE LENGTH OF APPROACH LINES

APPROACH LENGTH	LEGEND SETS
LESS THAN 50 FEET	1 SET AT X-WALK END OF POCKET
50 FEET TO 120 FEET	2 SETS
125 FEET TO 300 FEET	3 SETS (SECOND LEGEND LOCATED MIDWAY BETWEEN FIRST AND LAST LEGENDS)
OVER 300 FEET	ADDITIONAL SETS SPACED AT APPROX 100 FT INTERVALS BETWEEN FIRST AND LAST SETS

NOTES:

TEFT TURN LANE LAYOUT SHOWN ABOVE. SAME LAYOUT APPLIES FOR OTHER TURN LANES.



TYPICAL TWO WAY LEFT TURN LANE CHANNELIZATION

NUMBER OF LEGEND SETS REQUIRED BASED ON THE LENGTH OF TYPICAL TWO WAY LEFT TURN LANES

APPROACH LENGTH	LEGEND SETS		
LESS THAN 50 FEET	1 SET AT X-WALK END OF POCKET		
50 FEET TO 300 FEET	2 SETS		
OVER 300 FEET	3 SETS (SECOND LEGEND LOCATED MIDWAY BETWEEN FIRST AND LAST LEGENDS) ADDITIONAL SETS SPACED AT APPROX 300 FT INTERVALS		

NOTE:


LINE CALLOUTS ARE IDENTIFIED & DESCRIBED IN STD SPEC SEC 8-22.

REF STD SPEC SEC 8-22



NOT TO SCALE

TYPICAL TURN LANE CHANNELIZATION AND LEGEND PLACEMENT



LEGENDS, SYMBOLS & ARROWS MUST BE CENTERED
WITHIN THE LANE TO WHICH THEY APPLY, AS SHOWN.

TABLE A				
POSTED OR	X MAX MIN			
85TH-PERCENTILE SPEED	MUTCD TABLE 2C-4 CONDITION A	MERGING TAPER		
20 MPH	225 FT	75 FT		
25 MPH	325 FT	115 FT		
30 MPH	460 FT	165 FT		
35 MPH	565 FT	225 FT		
40 MPH	670 FT	295 FT		
45 MPH	775 FT	375 FT		

TYPICAL LEGEND AND SYMBOL INSTALLATION DETAILS

LINE LENGTH	LEGEND SETS			
LINE LENGTH	WITHIN APPROACH LINE	WITHIN DOTTED LINE		
LESS THAN 50 FEET	APPROACH LINE (1 TOTAL)	NA		
50 FEET TO 120 FEET	ADD 1 SET AT BEGINNING OF APPROACH LINE (2 TOTAL)	ADD 1 SET MIDWAY BETWEEN FIRST SET AND APPROACH LINE (2 TOTAL)		
125 FEET TO 300 FEET	ADD 1 SET LOCATED MIDWAY BETWEEN FIRST AND LAST SETS (3 TOTAL)	ADD 1 SET, WITH EQUAL INTERVALS, BETWEEN FIRST SET AND APPROACH LINE		
OVER 300 FEET	ADD SETS SPACED AT APPROX. 100 FEET INTERVALS BETWEEN FIRST AND LAST SETS	(3 TOTAL)		

NOTE:


- 1. SEE MUTCD SECTION 2B.20 FOR GUIDANCE ON SIGNS.
- 2. MANDATORY MOVEMENT LANE CONTROL SIGNS MUST BE PAIRED WITH LEGENDS PLACED WITHIN THE APPROACH LINE


REF STD SPEC SEC 8-22





NOT TO SCALE

TYPICAL LANE DROP CHANNELIZATION AND LEGEND PLACEMENT










REV DATE: JUL 2019

Α	S	Χ	L	W	С	Α
45°	15'	15'	21.21	8.5	12.02	
	15'	15'	21.30	9.0'	12.75	
	16'	16'	22.63	9.0'	12.73	60°
	17'	17'	24.04	9.5'	13.44	
	18'	18'	25.46	10.0'	14.14	

	Α	S	X	L	W	С
		15'	8.66	17.32	8.5'	9.81
		15'	8.5	17.2	9.0'	10.5
	60°	16'	9.24	18.48	9.0'	10.39
		17'	9.81	19.63	9.5'	10.97
		18'	10.39	20.78	10.0'	11.55



- (A) ANGLE OF STALL IN RELATION TO CURB
- S STALL DEPTH
- igotimes PERPENDICULAR OFFSET
- L LENGTH OF STALL LINE
- W STALL WIDTH
- © CURB LENGTH

NOTES:

- 1. THE WIDTH OF THE TRAVEL LANE NEXT TO ANGLED PARKING SPACES MUST BE A MINIMUM OF 12'-6" FOR 45-DEGREE STALLS AND 17'-0" FOR 60-DEGREE STALLS.


 2. BARRIER CROSSHATCH LINES MUST BE ALIGNED AS SHOWN, INTERSECTING THE EDGE
- BARRIER CROSSHATCH LINES MUST BE ALIGNED AS SHOWN, INTERSECTING THE EDGE
 OF THE PARKING LANE AT 45-DEGREES AND ANGLED AGAINST THE ANGLING OF THE
 PARKING SPACES


REF STD SPEC SEC 8-22





NOT TO SCALE


TYPICAL ANGLED PARKING STALL CHANNELIZATION













REF STD SPEC SEC 8-22



NOT TO SCALE

OPTIONAL MOVMENT ARROWS WITH OBLIQUE ARROWS






728A CHEVRON WITH TRIANGLE

NOTF.

THIS SYMBOL MAY BE RESIZED FOR BIKE FACILITIES.
DIMENSIONS IN THOSE INSTANCES MUST BE SHOWN ON
DESIGN DRAWINGS.




728B
CENTER CUSHION TRIANGLE

REF STD SPEC SEC 8-22





NOT TO SCALE

SPEED HUMP & SPEED CUSHION SYMBOL










729B YIELD LINE WITH 36" TALL TRIANGLES


REF STD SPEC SEC 8-22




NOT TO SCALE

YIELD LINE LAYOUT & YIELD LINE TRIANGLE SYMBOLS






"BUS" LEGEND



"SLOW" LEGEND

THIS SYMBOL MAY BE RESIZED FOR BIKE FACILITIES

730A




NOTE:

REF STD SPEC SEC 8-22

City of Seattle

NOT TO SCALE

PAVEMENT MARKINGS LEGENDS




T40A INTERNATIONAL SYMBOL OF ACCESSIBILITY

REF STD SPEC SEC 8-22



NOT TO SCALE

INTERNATIONAL SYMBOL OF ACCESSIBILITY




741A PEDESTRIAN SYMBOL

REF STD SPEC SEC 8-22





NOT TO SCALE

PEDESTRIAN SYMBOL





DEL / DATE ALLO 0005





770B BICYCLE LANE THROUGH ARROW







REF STD SPEC SEC 8-22



NOT TO SCALE

HELMETED BICYCLIST SYMBOL WITH ARROW





772
BICYCLE DETECTOR SYMBOL


NOTE: SEE STD PLAN NO 530b FOR PLACEMENT


REF STD SPEC SEC 8-22




NOT TO SCALE


BICYCLE DETECTOR **SYMBOL**







775A NARROW BIKE LANE LEFT ARROW



775B NARROW BIKE LANE RIGHT ARROW


1. TURN ARROWS TO BE USED IN BIKE LANES LESS THAN 5' WIDE IN COMBINATION WITH THE HELMETED BICYCLIST SYMBOL 770C.
2. LAYOUT SIMILAR TO 770A WITH 6' SPACING.

REF STD SPEC SEC 8-22




NOT TO SCALE

NARROW BIKE LANE TURN ARROW SYMBOLS



- WHERE STRIPED CROSSWALK DOES NOT EXIST, CROSS BIKE MUST BE PLACED AT LANE LINE AND 1/2 LANE WIDTH CONSISTENT WITH STANDARD PLAN 712. IF NO CROSSWALK OR LANE LINE EXISTS, CROSSBIKE MUST BE ALIGNED WITH DIRECTION OF CROSS—TRAFFIC AND MUST BE PLACED AT 5' ON CENTERS.
- CROSS BIKE MATERIAL MUST BE MMA OR PRE-FORMED THERMOPLASTIC.
 WHEN CONNECTING BIKE LANES OF VARYING WIDTH, THE CROSSBIKE WIDTH MUST BE SIZED TO THE NARROWER OF THE TWO FACILITIES.
 FOR SKEWED CROSSING, THE WHITE PAVEMENT MARKINGS MUST BE ORIENTED TO ALIGN WITH DIRECTION OF BICYCLE TRAFFIC.




REF STD SPEC SEC 8-22



NOT TO SCALE

CROSS BIKE PAVEMENT MARKING



DRIVEWAY CROSSING LAYOUT

NOTES:


- DRIVEWAY CROSSING MATERIAL MUST BE MMA OR PRE-FORMED THERMOPLASTIC
 MATCH DRIVEWAY APRON IF WIDER THAN 20'

REF STD SPEC SEC 8-22



NOT TO SCALE

BIKE LANE PAVEMENT MARKING AT DRIVEWAY



- 1. THIS PLAN ONLY COVERS MINIMUM GEOMETRIC REQUIREMENTS. FINAL WALL GEOMETRY MUST BE DETERMINED BY THE DESIGNER AND MUST FOLLOW CURRENT EDITION OF AASHTO LRFD BRIDGE DESIGN SPECIFICATIONS. CALCULATIONS AND GEOTECHNICAL INFORMATION SHALL BE SUBMITTED FOR REVIEW AND APPROVAL.

 2. CONCRETE FOR SUPPORT WALL MUST BE CLASS 4000
- 3. REINFORCING STEEL ASTM A706 (AASHTO M 31 GRADE 60). MINIMUM SIZE BAR, #4.
- 4. BASE OF SUPPORT WALL TO BE BEARING ON COMPACTED SUITABLE MATERIAL 5. BACK FORM FOR SUPPORT WALL MAY BE OMITTED AND CONCRETE PLACED AGAINST NATIVE EARTH WHEN GROUND CONDITIONS PERMIT. CLEAR COVER MUST BE 1-1/2" UNLESS NOTED OTHERWISE.
- 6. WALL MUST BE DESIGNED TO ACCOMMODATE VEHICULAR LOADS AND PEDESTRIAN RAILING.

REF STD SPEC SEC 8-17, 8-19



NOT TO SCALE

SUPPORT WALL

