

APPENDIX 3H

Sample Notes for Pavement Plans, Including Metro Coordination

I. INTRODUCTION

All notes in these sets are illustrative and require review and revision by the Engineer for each project and specific project conditions. Yellow highlights indicate a note to the designer.

2. ROADWAY NOTES

For roadway notes unless otherwise noted.

1. PAVEMENT, SIDEWALK AND CURB REMOVALS MUST EXTEND TO EXISTING JOINT, TO LIMITS IDENTIFIED AS "SAWCUT" ON THE DRAWINGS, OR TO LIMITS DETERMINED BY THE ENGINEER. SEE COS STD SPEC 2-02.3(3).
2. ALL JOINTS AT MEET LINES OF NEW CONSTRUCTION AND EXISTING SURFACES MUST BE BUTT JOINTS. SEE COS STD SPEC 5-04.3(10)B.
3. PAVING AROUND INLETS AND CATCH BASINS MUST BE SLOPED TO ESTABLISH A DRAINAGE TRANSITION ZONE PER COS STD PLAN 260A.
4. WHERE PLANS DENOTE "MEF" FOR CURB RAMP ELEMENTS. THIS DESIGNATION IS FOR REFERENCE ONLY AND MUST BE FIELD VERIFIED BY THE ENGINEER. THE CONTRACTOR MUST NOTIFY THE ENGINEER PER COS STD SPEC 8-14.3(7) AND ALLOW THE ENGINEER THE OPPORTUNITY TO INSPECT THE CURB RAMP LAYOUT AND DIRECT ADJUSTMENTS AS NEEDED. EVERY EFFORT WILL BE MADE TO ACHIEVE AN ADA COMPLIANT RAMP.
5. ADJUSTMENT OF AN EXISTING WATER VALVE BOX MUST BE DONE BY PER COS STD SPEC 7-20.3(4). RING EXTENSIONS ARE NOT ALLOWED.
6. CONTRACTOR MUST ADJUST CASTINGS IN ACCORDANCE WITH COS STD SPEC SECTION 7-20. CASTINGS MUST BE ADJUSTED TO FINISH GRADE PRIOR TO CONSTRUCTION OF FINAL SURFACE COURSE PER COS STD SPEC 5-04.3(8)A. WORN OR BROKEN CASTINGS TO BE REPLACED MUST BE REPLACED PRIOR TO INSTALLATION OF FINAL SURFACE.

3. METRO COORDINATION NOTES

If needed, add any of the following that fit your project needs.

1. TO SCHEDULE BUS SHELTER REMOVAL BY METRO CONTACT: PLANSERVEVIEW@KINGCOUNTY.GOV ADVANCE NOTIFICATION IS REQUIRED A MINIMUM OF 3 WEEKS IS REQUIRED BEFORE REMOVAL DATE.
2. ALL METRO SHELTER FOOTINGS MUST BE INSPECTED BY METRO BEFORE ANY CONCRETE IS POURED. CONTACT METRO INSPECTORS AT 206-263-130 OR 206-947-1574 OR PAUL.MILLER@KINGCOUNTY.GOV. ADVANCE NOTICE OF 3 WORKING DAYS IS REQUIRED.

Chapter 3 Design for Construction
Appendix 3H Sample Notes for Pavement Plans,
including Metro Coordination

3. AFTER BUS SHELTER FOOTINGS ARE INSTALLED, CONTACT PLANSERVEVIEW@KINGCOUNTY.GOV TO SCHEDULE BUS SHELTER FRAME INSTALLATION AND BUS STOP FLAG POST INSTALLATION.